

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
	3	<b>Part I.C - Special Conditions</b>			
	4	<b>Compliance with Water Quality Standards – General Requirements - Part I.C.1.a - c</b>			
Not Included in NOI	5	Part I.C.1 - Compliance with Water Quality Standards Pursuant to Clean Water Act §402(p)(3)(B)(iii) and 40 CFR §122.44(d)(1), this permit includes provisions to ensure that discharges from the permittee's MS4 do not cause or contribute to exceedances of applicable surface water quality standards, in addition to requirements to control discharges to the maximum extent practicable (MEP) set forth in Part I.D. Permittees shall address storm water management through development of the SWMP that shall include the following elements and specific requirements included in Part VI (sections below).	Part I.C.1 - AMAFCA's proposed plan for compliance with related Permit activities are described in the applicable sections of the AMAFCA SWMP.	• AMAFCA's measurable goals for compliance with related Permit activities are described in the applicable sections of the AMAFCA SWMP.	See specific Permit section and activity.
Not Included in NOI	6	Part I.C.1.a - Permittee's discharges shall not cause or contribute to an exceedance of surface water quality standards (including numeric and narrative water quality criteria) applicable to the receiving waters. In determining whether the SWMP is effective in meeting this requirement or if enhancements to the plan are needed, the permittee shall consider available monitoring data, visual assessment, and site inspection reports.	Part I.C.1.a - Compare AMAFCA monitoring data results to applicable surface water quality standards that occur in the following programs: Compliance with Water Quality Standards - Dissolved Oxygen Program, Compliance with Water Quality Standards - PCB Program, Compliance with Water Quality Standards - Temperature Program, Compliance with Water Quality Standards - Discharges to Impaired Waters with Approved TMDL Program, and the Wet Weather Monitoring Program. Refer to these sections for additional information.	• Compare AMAFCA monitoring data results to applicable surface water quality standards that occur in the following programs: Compliance with Water Quality Standards - Dissolved Oxygen Program, Compliance with Water Quality Standards - PCB Program, Compliance with Water Quality Standards - Temperature Program, Compliance with Water Quality Standards - Discharges to Impaired Waters with Approved TMDL Program, and the Wet Weather Monitoring Program. • AMAFCA's measurable goals for compliance with related Permit activities are described in the applicable sections of the AMAFCA SWMP.	See specific Permit section and activity.
Not Included in NOI	7	Part I.C.1.b - Applicable surface water quality standards for discharges from the permittees' MS4 are those that are approved by EPA and any other subsequent modifications approved by EPA upon the effective date of this permit found at New Mexico Administrative Code §20.6.4. Discharges from various portions of the MS4 also flow downstream into waters with Pueblo of Isleta and Pueblo of Sandia Water Quality Standards.	Part I.C.1.b - Compare AMAFCA monitoring data results to the applicable New Mexico Administrative Code §20.6.4, Pueblo of Isleta Water Quality Standards (amended on 3/18/2002, effective 7/22/2005 per EPA website), and Pueblo of Sandia Water Quality Standards (effective 3/9/2010). Compare AMAFCA monitoring data results to applicable surface water quality standards that occur in the following programs: Compliance with Water Quality Standards - Dissolved Oxygen Program, Compliance with Water Quality Standards - PCB Program, Compliance with Water Quality Standards - Temperature Program, Compliance with Water Quality Standards - Discharges to Impaired Waters with Approved TMDL Program, and the Wet Weather Monitoring Program. Refer to these sections for additional information.	• Compare AMAFCA monitoring data results to applicable surface water quality standards that occur in the following programs: Compliance with Water Quality Standards - Dissolved Oxygen Program, Compliance with Water Quality Standards - PCB Program, Compliance with Water Quality Standards - Temperature Program, Compliance with Water Quality Standards - Discharges to Impaired Waters with Approved TMDL Program, and the Wet Weather Monitoring Program. • AMAFCA's measurable goals for compliance with related Permit activities are described in the applicable sections of the AMAFCA SWMP.	See specific Permit section and activity.

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
Not Included in NOI	8	<p><u>Part I.C.1.c</u> - The permittee shall notify EPA and the Pueblo of Isleta in writing as soon as practical but not later than 30 calendar days following each Pueblo of Isleta water quality standard exceedance at an in-stream sampling location. In the event that EPA determines that a discharge from the MS4 causes or contributes to an exceedance of applicable surface water quality standards and notifies the permittee of such an exceedance, the permittee shall, within sixty (60) days of notification, submit to EPA, NMED, Pueblo of Isleta (upon request) and Pueblo of Sandia (upon request), a report that describes controls that are currently being implemented and additional controls that will be implemented to prevent pollutants sufficient to ensure that the discharge will no longer cause or contribute to an exceedance of applicable surface water quality standards. The permittee shall implement such additional controls upon notification by EPA and shall incorporate such measures into their SWMP as described in Part I.D of this permit. NMED or the affected Tribe may provide information documenting exceedances of applicable water quality standards caused or contributed to by the discharges authorized by this permit to EPA Region 6 and request EPA take action under this paragraph.</p>	<p><u>Part I.C.1.c</u> - AMAFCA will notify EPA and the Pueblo of Isleta of any Pueblo of Isleta of water quality standard exceedances at an in-stream sampling location (within the Rio Grande). Notification will be in writing as soon as practicable. Lab reports are typically received within 45 days of a sampling event. Preliminary review of the results typically requires 5 days. AMAFCA will include requirements to their contractors to review and report in-stream exceedances in a timely manner so that AMAFCA can better meet this requirement. AMAFCA will notify EPA and the Pueblo of Isleta within 30 days of the data review to determine a Pueblo of Isleta water quality standard exceedance at an in-stream (within the Rio Grande) sampling location. The Permit is unclear if this notification is required just for MS4 Permit compliance sampling, or if this includes results from other monitoring, such as citizen science projects. AMAFCA will provide this notification for in-stream samples that AMAFCA is involved with sampling, that result in a Pueblo of Isleta water quality standard exceedance. In addition, AMAFCA will continue to use sondes in the Rio Grande to monitor DO and temperature (refer to the Compliance with Water Quality Standards - Dissolved Oxygen (DO) Program). AMAFCA will continue to provide Isleta Pueblo with access to the real-time DO and temperature sonde data.</p>	<ul style="list-style-type: none"> <li>• AMAFCA will notify EPA and the Pueblo of Isleta of any Pueblo of Isleta water quality standard exceedances at an in-stream sampling location (within the Rio Grande). Notification will be in writing as soon as practicable.</li> <li>• AMAFCA will add the in-stream notification of Pueblo of Isleta water quality standard exceedance to monitoring reporting tasks with sub-consultants to ensure that results are reviewed and reported in a timely manner.</li> <li>• AMAFCA will continue to use sondes in the Rio Grande to monitor DO and temperature (refer to the Compliance with Water Quality Standards - Dissolved Oxygen Program). AMAFCA will continue to provide Isleta Pueblo with access to the real-time DO and temperature sonde data.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• AMAFCA notified EPA and the Pueblo of Isleta of any Pueblo of Isleta water quality standard exceedances at any in-stream sampling location (within the Rio Grande). Notification was in writing as soon as practical. AMAFCA notified the Pueblo of Isleta and EPA of exceedances related to CMC monitoring, AMAFCA water quality monitoring, and citizen science monitoring (BEMP).</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
<b>9 Compliance with Water Quality Standards – Dissolved Oxygen &amp; Part I.C.1.d and Endangered Species Act (ESA) Requirements - Dissolved Oxygen Strategy - Part I.C.3.a</b>					
Not Included in NOI	10	<p>According to the requirements in <u>Part I.C.1.d</u> and <u>Part I.C.3.a(ii)</u>, the permittees shall revise the May 1, 2012 Strategy to continue taking measures to address concerns regarding discharges to the Rio Grande by implementing controls to eliminate conditions that cause or contribute to exceedances of applicable dissolved oxygen water quality standards in waters of the United States.</p> <p>The permittee shall, as part of this revised strategy, complete the following activities [activities are listed in sections below]. Activities listed are a combination of permit activities in Part I.C.1.d - Special Conditions, Compliance with Water Quality Standards, Phase I Dissolved Oxygen Program and Part I.C.3.a - Dissolved Oxygen Strategy in Receiving Waters of the Rio Grande.</p>	<p><u>Part I.C.1.d</u> and <u>Part I.C.3.a(ii)</u> - The potential for low DO discharges to the Rio Grande at the NDC Embayment has been a concern which AMAFCA has been addressing, with the USFWS and EPA, since 2004. Several strategies, including various NDC Embayment modifications, have been implemented from 2011-2014. In 2015-2016, AMAFCA completed construction, after coordination with USFWS, of the NDC Outfall Grade Control Structures Modification Project and NDC Embayment Regrading Project.</p> <p>The NDC Embayment was filled in and regraded in 2015-2016, thereby removing the constant hydraulic connection between the Rio Grande and the NDC Bathtub/Outfall. In normal river flow conditions, water from the Rio Grande will not be able to stagnate in the Embayment and create low DO conditions. These improvement projects provide control measures to eliminate conditions that cause or contribute to exceedances of applicable DO water quality standards.</p> <p>These NDC projects and this Dissolved Oxygen Program Strategy were coordinated with the USFWS. AMAFCA received a Final BO from the USFWS and Special Conditions from USACE allowing the NDC Embayment to be filled in and revegetated.</p>	<p>• AMAFCA has completed the NDC Outfall Grade Control Structures Modification Project to fill in and revegetate the NDC Embayment and will continue following the terms of the Final BO from the USFWS and Final Special Conditions from USACE. This project is the revised strategy for the MS4 Permit elements related to DO.</p> <p>• A new vegetation assessment study and removal training will be conducted to determine the types of vegetation and optimal time for seeding. A revised monitoring plan, developed in consultation with the USACE, will be in place moving forward.</p>	<p><b>Met FY 2023 Goals.</b></p> <p>• In FY 2023, USACE provided a letter releasing AMAFCA from any further revegetation monitoring requirements at the NDC outfall related to the special conditions of the USACE Regional General Permit. USACE determined that the site has met the revegetation performance goals. AMAFCA received notification from USACE in FY 2023 documenting that the Special Conditions of the Regional General Permit relative to revegetation monitoring had been fully satisfied and monitoring was no longer required at the NDC Outfall.</p>
Not Included in NOI	11	<p><u>Part I.C.1.d(i)</u> and <u>Part I.C.3.a(i)</u> - Identify (or continue identifying) structural elements, natural or man-made topographical and geographical formations, MS4 operations activities, or oxygen demanding pollutants contributing to reduced dissolved oxygen in the receiving waters of the Rio Grande. Both dry and wet weather discharges shall be addressed. Assessment may be made using available data or collecting additional data;</p>	<p><u>Part I.C.1.d(i)</u> and <u>Part I.C.3.a(i)</u>: The NDC Outfall/Embayment is the primary structural element identified by AMAFCA, City of Albuquerque, EPA, and USFWS as potentially contributing to low dissolved oxygen (DO) in the receiving waters of the Rio Grande. This Dissolved Oxygen Strategy is primarily focused on addressing this element.</p> <p>No other specific structural elements in the watershed have been identified as contributing to reduced DO in the receiving waters of the Rio Grande. Other stormwater outfalls, including the South Diversion Channel/Tijeras Arroyo, Calabacillas Arroyo, San Antonio Arroyo, will continue to be monitored.</p> <p>AMAFCA will continue to operate sondes in the Rio Grande deployed for monitoring DO and temperature. The sonde locations throughout the length of the Rio Grande through the UA will assist AMAFCA with bracketing segments of the Rio Grande to better understand elements that may be contributing to reduced DO in the receiving waters of the Rio Grande. DO results from AMAFCA monitoring efforts will assist AMAFCA in determining if there are other elements that may be contributing to reduced DO in the receiving waters of the Rio Grande. AMAFCA will update its SWMP if any other specific structural elements in the watershed are identified as contributing to reduced DO in the receiving waters of the Rio Grande.</p>	<p>• AMAFCA will follow the monitoring measurable goals in Part I.C.1.d.(iii) below.</p> <p>• Related to identifying structural elements in the watershed that may be contributing to reduced DO, AMAFCA will continue to use sondes in the Rio Grande to monitor DO and temperature; the sonde data will provide valuable data related to potential DO - stormwater related connections.</p>	<p><b>Met FY 2023 Goals.</b></p> <p>• In FY 2023, related to identifying structural elements in the watershed that may be contributing to reduced DO, AMAFCA operated four sondes, given safe flow conditions, in the Rio Grande (US 550 at Bernalillo, Sandia Pueblo Boundary, Central Ave., and Isleta Pueblo Boundary). Additional details on the sonde monitoring are available below and in the Dissolved Oxygen Program Summary for the Annual Report.</p> <p>• Related to identifying structural elements in the watershed that may be contributing to reduced DO, AMAFCA collected and analyzed DO data from stormwater samples collected for the MS4 program (cooperative monitoring, AMAFCA monitoring, and Citizen Science monitoring). Details on this monitoring are provided in the Dissolved Oxygen Program Summary for the Annual Report.</p>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
Not Included in NOI	12	<p><u>Part I.C.1.d.(ii)</u> - Continue implementing controls, and updating/revising as necessary, to eliminate structural elements or the discharge of pollutants at levels that cause or contribute to exceedances of applicable water quality standards for dissolved oxygen in waters of the United States;</p>	<p><u>Part I.C.1.d.(ii)</u> - The primary controls for this DO Program are the NDC Outfall Grade Control Structures Modification Project and Embayment Grading Project. The water quality improvement goal for the NDC Outfall Grade Control Structures Modification Project is to improve maintenance operations, thereby improving efficiency of sediment, trash and debris removal due to better access and improved geometry. The NDC Embayment Regrading Project, as discussed above, removes the constant hydraulic connection between the Rio Grande and the NDC Bathtub/Outfall. These improvement projects provide control measures to mitigate conditions that cause or contribute to exceedances of applicable DO WQSS.</p> <p>In addition to the NDC Outfall and Embayment Projects, AMAFCA will continue to install stormwater quality structures within the watershed. AMAFCA plans, designs, and builds regional stormwater BMPs throughout the watershed to help eliminate the discharge of pollutants that cause or contribute to exceedances of applicable water quality standards for DO in waters of the Rio Grande.</p> <p>Pollutant source reduction strategies, such as public education and encouragement of GI/LID, are also part of the ongoing controls for this Program. AMAFCA actively participates in the MRGSQT, which organizes and leads public education, outreach, involvement, and participation activities which relate to this Program.</p>	<ul style="list-style-type: none"> <li>• AMAFCA will continue to plan, design, and build structural BMPs (regional water quality structures) throughout the MRG watershed.</li> <li>• AMAFCA will continue to contribute and participate in the MRGSQT which provides public education, outreach, and participation opportunities related to stormwater impacts to water quality.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• AMAFCA continued to use floating booms in the NDC Outfall to assist with trash and debris collection. Removal of trash and debris will assist with mitigating low DO issues in this area.</li> <li>• AMAFCA continued to plan, design, and build structural BMPs (regional water quality structures) throughout the MRG watershed. Refer to the Construction Control Measure and the Post Construction Control Measure for additional information.</li> <li>• AMAFCA continued to contribute and participate in the MRGSQT - refer to the Public Education and Outreach Control Measure and the Public Involvement and Participation Control Measure for additional information.</li> </ul>
Not Included in NOI	13	<p><u>Part I.C.1.d.(iii)</u> Continue sampling for DO and temperature in the North Diversion Channel (NDC) Embayment until the data indicate the discharge does not exceed applicable DO water quality standards in waters of the United States.</p> <p>This coincides with the requirements in <u>Part I.C.3.a.(ii)(a)</u>, the revised strategy shall include:</p> <p>A. A Monitoring Plan describing all procedures necessary to continue conducting continuous monitoring of DO and temperature in the NDC Embayment and at 1 location in the Rio Grande downstream of the mouth of the NDC within the action area (e.g., Central Bridge).</p> <p>B. A Quality Assurance and Quality Control (QA/QC) Plan describing all standard operating procedures, quality assurance and quality control plans, maintenance and implementation schedules that will assure timely and accurate collection and reporting of water temperature, DO, oxygen saturation, and flow. The QA/QC plan should include all procedures for estimating oxygen data when any oxygen monitoring equipment fail.</p>	<p><u>Part I.C.1.d.(iii)</u> - With the NDC Embayment filled in since 2016, AMAFCA cannot physically measure the DO in the Embayment. AMAFCA will provide continuous monitoring of DO and temperature (using sondes) in the Rio Grande at the most appropriate locations for the purpose of complying with the MS4 Permit requirements in Part I.C.1.d.(iii) and Part I.C.3.a.(ii)(a). The sonde locations throughout the stretch of the Rio Grande through the Urbanized Area (UA) will assist AMAFCA with bracketing segments of the Rio Grande to better understand locations of elements that may be contributing to reduced DO in the receiving waters of the Rio Grande.</p> <p>For compliance with this Permit Activity, AMAFCA will deploy sondes to provide continuous DO, oxygen saturation, and temperature monitoring; sondes are currently located at the following locations:</p> <ul style="list-style-type: none"> <li>- Rio Grande at Sandia Pueblo Boundary (just above the confluence with the NDC outfall)</li> <li>- Rio Grande at Central Ave. Bridge</li> <li>- Rio Grande at the Isleta Dam</li> </ul> <p>Note - sonde locations may change based on the results and program needs as well as river stage.</p> <p><u>Part I.C.3.a.(ii)(a) A and B</u> - For the sonde monitoring, AMAFCA has standard operating procedures, quality assurance plans, maintenance, and implementation schedules in place.</p>	<ul style="list-style-type: none"> <li>• For compliance with this Permit Activity, AMAFCA will deploy sondes in the most appropriate locations to provide continuous DO and temperature monitoring.</li> <li>• AMAFCA will continue following the standard operating procedures, quality assurance plans, maintenance, and implementation schedules that are in place for the sonde monitoring. AMAFCA will continue to pursue, as applicable, data collection and reporting improvements to this program.</li> <li>• AMAFCA will continue to provide Isleta Pueblo with access to the real-time DO and temperature sonde data.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• Related to the NDC Embayment monitoring, AMAFCA deployed four sondes to provide continuous DO, pH, water depth, turbidity, and temperature monitoring at the following locations: US 550 Bridge in Bernalillo, Sandia Pueblo Boundary, Central Ave., and Isleta Dam. Additional details on the sonde program and results are provided in the In-Stream Water Quality Memos, which are available upon request. Use of sondes in the Rio Grande have physical challenges that make the measurement, monitoring, and maintenance difficult as well as time/staff intensive. There are times when the sonde data is not available due to maintenance and other issues with the equipment.</li> <li>• In FY 2023, AMAFCA continued to operate real-time telemetry capabilities to these four sondes allowing AMAFCA to be aware of sonde issues in real time, resulting in less data gaps. The sonde data was made available to the Pueblo of Isleta to improve data sharing and coordination with watershed stakeholders.</li> <li>• AMAFCA and monitoring consultants followed the standard operating procedures, quality assurance plan, maintenance, and implementation schedules that are in place for the sonde monitoring.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
Not Included in NOI	14	<p><u>Part 1.C.1.d.(iv)</u> Submit a revised strategy to FWS for consultation and EPA for approval within a year of the effective date of the permit and progress reports with the subsequent annual reports. Progress reports to include:</p> <p>(a) Summary of data.</p> <p>(b) Activities undertaken to identify MS4 discharge contribution to exceedances of applicable dissolved oxygen water quality standards in waters of the United States. Including summary of findings of the assessment required in Part 1.C.1.d.(i).</p> <p>(c) Conclusions drawn, including support for any determinations.</p> <p>(d) Activities undertaken to eliminate MS4 discharge contribution to exceedances of applicable dissolved oxygen water quality standards in waters of the United States.</p> <p>(e) Account of stakeholder involvement.</p> <p><u>Part 1.C.3.a.(i)</u> - The permittees shall submit a summary of findings and a summary of activities undertaken with each Annual Report. The SWMP submitted with the first and fourth annual reports must include a detailed description of controls implemented (or/and proposed control to be implemented) along with corresponding measurable goals. (Applicable to all permittees).</p>	<p><u>Part 1.C.1.d.(iv)</u> - AMAFCA completed the NDC project in 2016 to fill in and revegetate the NDC Embayment following the terms of the Final BO from the USFWS and Final Special Conditions from USACE. USFWS was consulted during this project and made aware of the revised strategy. The AMAFCA MS4 Annual Report and supporting documentation will be considered as the Progress Report. A separate progress report will not be submitted to EPA and USFWS. The MS4 Annual Report will include the Annual Incidental Take Report as an Attachment to the Annual Report.</p> <p><u>Part 1.C.3.a.(i)</u> - The Annual Report will include a summary of example activities undertaken to identify elements contributing to reduced dissolved oxygen in the receiving waters of the Rio Grande and changes or improvements to the Strategy for implementation of controls to eliminate exceedances of applicable water quality standards for dissolved oxygen in waters of the United States.</p>	<ul style="list-style-type: none"> <li>• AMAFCA completed the NDC Outfall Grade Control Structures Modification Project to fill in and revegetate the NDC Embayment following the terms of the Final BO from the USFWS and Final Special Conditions from USACE.</li> <li>• AMAFCA will complete the Incidental Take Report and follow the Incidental Take Reporting requirements and data submittal requirements.</li> <li>• AMAFCA will include a summary of example activities in each Annual Report. AMAFCA will incorporate documentation by reference into the Annual Report and plans to document progress on the AMAFCA website.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• Refer to ID #10 above for information related to the USACE Regional General Permit. AMAFCA received notification from USACE in FY 2023 documenting that the special conditions of the Regional General Permit relative to vegetation monitoring had been fully satisfied and monitoring was no longer required at the NDC Outfall.</li> <li>• AMAFCA completed the Annual Incidental Take analysis and this is included in the Dissolved Oxygen Program Summary for the Annual Report. AMAFCA followed a procedure for completing this Annual Incidental Take Report to ensure the current MS4 Permit requirements were met and that this report is consistently completed each year. This procedure is available upon request.</li> <li>• AMAFCA has completed this section of the Annual Report to serve as a progress report for this Permit element.</li> </ul>
Not Included in NOI	15	<p>According to the requirements in <u>Part 1.C.3.a.(ii)</u>, the permittees shall ensure that actions to reduce pollutants or remedial activities selected for the NDC Embayment and its watershed are implemented such that there is a reduction in frequency and magnitude of all low oxygen stormwater discharge events that occur in the Embayment or downstream in the MRG as indicated in Table 1.c. Actions to meet the year 3 measurable goals must be taken within 2 years from the effective date of the permit. Actions to meet the year 5 measurable goals must be taken within 4 years from the effective date of the permit.</p>	<p><u>Part 1.C.3.a.(ii)</u> - The result of removing the NDC Embayment and hydraulically disconnecting the NDC stormwater flows from the Rio Grande will minimize low DO conditions at this location. The Embayment has had historical issues with stagnate ponded water creating low DO conditions. The monitoring activities described above will be used to assess that the Embayment project functions as planned and that low DO conditions are reduced in both frequency and magnitude.</p>	<ul style="list-style-type: none"> <li>• AMAFCA will <b>obtain</b> DO monitoring results for "qualifying events" as defined by USFWS with the MS4 Permit measurable goals as listed in Table 1.c , using the table in Appendix G in the MS4 Permit.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• AMAFCA continued to use the MS4 Permit measurable goal analysis and reporting in the Annual Incidental Take Report, and this is included in the Dissolved Oxygen Program Summary for the Annual Report. In addition, AMAFCA followed the procedure for completing this analysis to ensure the current MS4 Permit requirements were met and that this report is consistently completed each year.</li> <li>• AMAFCA continued analyzing the Levellogger data in the NDC watershed and at the equipment crossing in comparison to the "qualifying events" as defined by USFWS.</li> <li>• From the AMAFCA FY 2023 In-Stream Water Quality Monitoring Memos, which report on the AMAFCA sonde data, the DO fell slightly below 5 mg/L related to storm events within the watershed; refer to the Dissolved Oxygen Program Summary for additional information.</li> <li>• In FY 2023, none of the 14 NDC qualifying events were found to be hypoxic or anoxic. The oxygen percent saturation for all data collected for the NDC qualifying events was greater than 54.3 percent.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
Not Included in NOI	16	<p>According to the requirements in <a href="#">Part I.C.3.a.(ii).(b)</a>, the permittees (COA and AMAFCA) shall provide:</p> <p>A. An Annual Incidental Take Report to EPA and the Service that includes the following information: beginning and end date of any qualifying stormwater events, DO values and water temperature in the NDC Embayment, DO values and water temperature at a downstream monitoring station in the MRG, flow rate in the NDC, mean daily flow rate in the MRG, evaluation of oxygen and temperature data as either anoxic or hypoxic using Table 2 of the BO, and estimate the number of silvery minnows taken based on Appendix A of the BO. Electronic copy of The Annual Incidental Take Report should be provided with the annual report required under Part III.B no later than December 1 for the proceeding calendar year.</p>	<p><a href="#">Part I.C.3.a.(ii).(b).A</a> - AMAFCA will complete the Incidental Take Report, which estimates the potential Rio Grande Silvery Minnow (RGSM) take using the method defined by USFWS for the BO (MRG Watershed Permit BO dated August 21, 2014 - Cons. #22420-2011-F-0024-R001). Using the BO procedure, AMAFCA will determine or measure, as technically feasible, the necessary data elements required for calculation of the predicted incidental takes during qualifying storm events. The definition of a qualifying storm event (for this Permit Activity) may be reassessed for NDC Outfall and Embayment area. This activity may require additional follow-up with the EPA and the USFWS. The Annual Incidental Take Report will be provided with each Annual Report.</p>	<p>• AMAFCA will complete the Annual Incidental Take Report.</p> <p>• AMAFCA will provide EPA and USFWS with a copy of the Annual Incidental Take Report with each Annual Report submitted no later than December 1st for the preceding calendar year, as required under Part III.B.</p>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• The Annual Incidental Take Report was completed to meet the Dec. 1, 2023 deadline for the Annual Report and is provided in the Dissolved Oxygen Program Summary.</li> </ul>
Not Included in NOI	17	<p>According to the requirements in <a href="#">Part I.C.3.a.(ii).(b)</a>, the permittees (COA and AMAFCA) shall provide:</p> <p>B. A summary of data and findings with each annual report to EPA and the FWS. All data collected (including provisional oxygen and water temperature data, and associated metadata), transferred, stored, summarized, and evaluated shall be included in the annual report. If additional data is requested by EPA or the FWS, COA and AMAFCA shall provide such information within two weeks upon request. The revised strategy required under <a href="#">Part I.C.3.a.(ii)</a>, the Annual Incidental Take Reports required under <a href="#">Part I.C.3.a.(ii).(b).A</a>, and annual reports required under Part III.B can be submitted to FWS via e-mail nmesfo@fws.gov and Joel.lusk@fws.gov, or by mail to the New Mexico Ecological Services field office, 2105 Osuna Road NE, Albuquerque, New Mexico 87113. [Note - as of July 2022, Debra Hill is the new contact at USFWS. add email]</p>	<p><a href="#">Part I.C.3.a.(ii).(b).B</a> - AMAFCA will provide EPA and USFWS with the necessary data elements required for calculation of the predicted incidental takes during qualifying storm events and the Annual Incidental Take Report, required under <a href="#">Part I.C.3.a.(ii).(b).A</a>. If additional data is requested by EPA or the USFWS, AMAFCA will provide requested information within two (2) weeks upon request.</p> <p>AMAFCA will assess the DO on the same time frame as the MS4 Permit requires for the Annual Report – July 1 to June 30. Each Annual Report will be submitted no later than December 1 for the preceding calendar year, as required under Part III.B.</p>	<p>• AMAFCA will provide EPA and USFWS the required data and information with each Annual Report submittal, required under Part III.B, no later than December 1 for the preceding calendar year.</p>	<p><b>Met FY 2023 Goal.</b></p> <ul style="list-style-type: none"> <li>• AMAFCA submitted AMAFCA's FY 2023 MS4 Annual Report with the Dissolved Oxygen Program Summary, the Incidental Take results, and applicable In-Stream Water Quality Monitoring (sonde) memos, as required under Part III.B.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
Not Included in NOI	18	<b>Compliance with Water Quality Standards – PCBs - Part I.C.1.e</b>			
Not Included in NOI	19	According to the requirements in Part I.C.1.e, the permittee shall address concerns regarding PCBs in channel drainage areas specified in Part I.C.1.e.(vi) by developing or continuing updating/revising and implementing a strategy to identify and eliminate controllable sources of PCBs that cause or contribute to exceedances of applicable water quality standards in waters of the United States. COA and AMAFCA shall submit a progress report with the first and with the subsequent annual reports.	Part I.C.1.e - The results from the 2012-2014 monitoring of the NDC watershed indicated the presence of PCBs at the Grantline and N. Camino Inlets. Based on the data, MS4 partners concluded that there are no "hot spots" in the municipal area that are continuing to produce PCBs with the possible exception of the Grantline and N. Camino watersheds. In 2014-2017, AMAFCA continued activities to identify and eliminate controllable sources of PCBs specific to these two channels. A water quality consultant was tasked with reviewing and assessing all past PCB data for the NDC, identifying commercial and industrial properties that may have contributed PCBs to the North Camino and the Grantline Channel, researching past PCB releases from PNM in these areas, and providing additional PCB monitoring activity recommendations. In addition, a Field Sampling Plan (FSP), Sampling Analysis Plan (SAP), and a Quality Assurance Project Plan (QAPP) for soil and sediment sampling were developed. Sediment sampling and analysis for PCBs in the North Camino and the Grantline Channel were provided to NMED for consultation and direction. Based on the data collection and analysis results from the first five (5) years of the MS4 Permit term (2014-2019), AMAFCA has met its goals and objectives related to the PCB investigation and no further PCB sampling by AMAFCA is anticipated. If future PCB sampling is needed, AMAFCA will utilize the developed FSP, SAP, and QAPP and coordinate with EPA, NMED, and other MS4s, as applicable.	Based on the data collection and analysis results from the first five (5) years of the MS4 Permit term (2014-2019), AMAFCA has met its goals and objectives related to the PCB investigation and no further PCB sampling by AMAFCA is anticipated. If future PCB sampling is needed, AMAFCA will utilize the developed FSP, SAP, and QAPP and coordinate with EPA, NMED, and other MS4s, as applicable.	<b>Met FY 2023 Goals.</b> As reported to EPA in 2018, after considering the analyses completed over the 5 year period (2014-2019), AMAFCA has met its goals and objectives related to the PCB investigation and no additional PCB sampling and analysis by AMAFCA, in the Grantline or North Camino Watersheds, was completed in FY 2019. If future PCB sampling is needed, AMAFCA will utilize the developed FSP, SAP, and QAPP and coordinate with EPA, NMED, and other MS4s, as applicable.
Not Included in NOI	20	Part I.C.1.e - The progress reports shall include: (i) Summary of data. (ii) Findings regarding controllable sources of PCBs in the channel drainages area specified in Part I.C.1.e.(vi) that cause or contribute to exceedances of applicable water quality standards in waters of the US via the discharge of municipal stormwater. (iii) Conclusions drawn, including supporting information for any determinations. (iv) Activities undertaken to eliminate controllable sources of PCBs in the drainage areas specified in Part I.C.1.e. (vi) that cause or contribute to exceedances of applicable water quality standards in waters of the US via the discharge of municipal stormwater including proposed activities that extend beyond the 5 year permit term. (v) Account of stakeholder involvement in the process. (vi) Channel Drainage Areas: The PCB strategy required in Part I.C.1.e is only applicable to: COA and AMAFCA Areas: San Jose Drain and North Diversion Channel. Bernalillo County Areas: Adobe Acres Drain, Alameda Outfall Channel, Paseo del Norte Outfall Channel, and Sanchez Farm Drainage Area.	Part I.C.1.e - Based on ownership responsibilities, COA will continue to take the lead regarding follow-up PCB permit activities on the SJD, and AMAFCA will continue to take the lead on follow-up PCB permit activities on the NDC. Bernalillo County will take the lead on Adobe Acres Drain, Alameda Outfall Channel, Paseo del Norte Outfall Channel, and Sanchez Farm Drainage Area, as assigned in the MS4 Permit. Based on the data collection and analysis results from the first five (5) years of the MS4 Permit term (2014-2019), AMAFCA has met its goals and objectives related to the PCB investigation and no further PCB sampling by AMAFCA is anticipated. Results from any continued study will be provided to NMED for consultation and direction. If future PCB sampling is needed, AMAFCA will utilize the developed FSP, SAP, and QAPP and coordinate with EPA, NMED, and other MS4s, as applicable. No additional Compliance Monitoring Cooperative (CMC) monitoring is required until a new MS4 Permit is issued. However, the CMC members will evaluate and may choose to continue sampling to support their MS4 program needs during administrative continuance. CMC monitoring would include collecting samples, and screening for PCBs, at two (2) locations within the Rio Grande - one upstream of the MS4 and one downstream of the MS4. This program uses Method 1668 for testing PCBs. Monitoring results obtained from AMAFCA's internal stormwater quality assessment monitoring program and any continued CMC stormwater quality monitoring are available upon request.	Based on the data collection and analysis results from the first five (5) years of the MS4 Permit term (2014-2019), AMAFCA has met its goals and objectives related to the PCB investigation and no further PCB sampling by AMAFCA is anticipated. If future PCB sampling is needed, AMAFCA will utilize the developed FSP, SAP, and QAPP and coordinate with EPA, NMED, and other MS4s, as applicable. Results from any continued study will be provided to NMED. The Annual Report will serve as the progress report for additional PCB findings, if applicable. AMAFCA will incorporate documentation by reference into the Annual Report and plans to document progress on the AMAFCA website.	<b>Met FY 2023 Goals.</b> For AMAFCA's internal stormwater quality monitoring program, during the FY 2023 wet season (July 2022 - October 2022), stormwater samples from ten (10) of the AMAFCA monitoring locations were screened for PCBs; all the PCB screening results were reported as not detected. AMAFCA's internal stormwater monitoring program also collected three (3) stormwater samples in the FY 2023 dry season (November 2022 to June 2023) that were screened for PCBs, and all sample results were reported as Not Detected (ND). The watershed screening utilized Method 608 with the understanding that if results are detected with the screening method, AMAFCA would then sample and test with Method 1668. The monitoring reports are available upon request.

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
Not Included in NOI	21	<p>Part 1.C.1.e.(vi) - A cooperative strategy to address PCBs in the COA, AMAFCA and Bernalillo County's drainage areas may be developed between Bernalillo County, AMAFCA, and COA. If a cooperative strategy is developed, the cooperative strategy shall be submitted to EPA within three (3) years from the effective date of the permit and submit a progress report with the fourth and with subsequent annual reports,</p> <p>Note: COA and AMAFCA must continue implementing the existing PCB strategy until a new Cooperative PCB Strategy is submitted to EPA.</p>	<p>Part 1.C.1.e.(vi) - An updated cooperative strategy, if warranted, will be discussed with COA, AMAFCA, and Bernalillo County through the cooperative MS4 Technical Advisory Group (MS4 TAG). If a cooperative strategy is agreed to, work will begin to develop an agreement and develop a cooperative strategy to submit to EPA.</p>	<ul style="list-style-type: none"> <li>AMAFCA will discuss the updated cooperative strategy option, if warranted, with COA and Bernalillo County through the cooperative MS4 TAG.</li> </ul>	<p><b>Met FY 2023 Goal.</b></p> <ul style="list-style-type: none"> <li>Given that AMAFCA has already met the required goals and objectives for compliance under the Permit, AMAFCA continued discussing the cooperative strategy option with COA and Bernalillo County through the cooperative MS4 TAG. PCB study plans and results within the watershed were discussed and shared between AMAFCA, COA, and Bernalillo County.</li> </ul>



NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
	22	<b>Compliance with Water Quality Standards – Temperature - Part I.C.1.f</b>			
Not Included in NOI	23	According to the requirements in <a href="#">Part I.C.1.f</a> , the permittees must continue assessing the potential effect of stormwater discharges in the Rio Grande by collecting and evaluating additional data. If the data indicates there is a potential of stormwater discharges contributing to exceedances of applicable temperature water quality standards in waters of the United States, within 30 days such as findings, the permittees must develop and implement a strategy to eliminate conditions that cause or contribute to these exceedances. If the data indicates there is a potential of stormwater discharges contributing to exceedances of applicable temperature water quality standards in waters of Rio Grande, within 30 days such as findings, the permittees must develop and implement a strategy to eliminate conditions that cause or contribute to these exceedances.	<a href="#">Part I.C.1.f</a> - AMAFCA and the original MS4 co-permittees (COA, NMDOT, and UNM) under MS4 Permit No. NMS000101 do not believe that stormwater discharges adversely affect temperature in the Rio Grande. In order to prove this assertion, temperature data from 1982 to 2012 was assembled and analyzed. This data analysis proved the assertion that the receiving waters of the Rio Grande are not adversely affected by the temperature of stormwater from the Albuquerque MS4. This data was presented in an initial report that was submitted to EPA on May 1, 2012. However, to meet the MS4 Permit requirements, AMAFCA continued assessing the potential effect of stormwater discharges in the Rio Grande by collecting and evaluating additional temperature data. From 2012 to 2017, temperature monitoring never showed a temperature exceedance at any of the monitoring locations in the watershed or in the river.	• AMAFCA's measurable goals for compliance with the Permit activities are described in the sections below.	See specific Permit activity below.
Not Included in NOI	24	The strategy must include: <a href="#">Part I.C.1.f.(i)</a> - Identify structural controls, post construction design standards, or pollutants contributing to raised temperatures in the receiving waters of the Rio Grande. Both dry and wet weather discharges shall be addressed. The Assessment may be made using available data or collecting additional data; <a href="#">Part I.C.1.f.(ii)</a> - Develop and implement controls to eliminate structural controls, post construction design standards, or the discharge of pollutants at levels that cause or contribute to exceedances of applicable water quality standards for temperature in waters of the United States; and	<a href="#">Part I.C.1.f.(i)</a> - AMAFCA has data supporting the fact that stormwater discharges do not adversely affect temperature in the Rio Grande. Assessment continues using temperature data collected in the Rio Grande using sondes (sondes are part of the Dissolved Oxygen - Compliance with Water Quality Standards and Endangered Species Act MS4 Permit program requirements). The sondes in the Rio Grande have real-time telemetry capabilities. The sonde locations throughout the length of the Rio Grande through the UA will assist AMAFCA with bracketing segments of the Rio Grande to better understand elements that may be contributing to high temperatures in the receiving waters of the Rio Grande. <a href="#">Part I.C.1.f.(ii)</a> - If the temperature data trends begins to indicate that stormwater discharges are adversely affecting temperature in the Rio Grande, AMAFCA will develop a strategy to understand the causes and contributions. If this occurs, AMAFCA will work with COA in developing this strategy as it relates to the watershed. It is anticipated that development of controls will be a part of the strategy. The 30 day timeline in the MS4 Permit is not long enough to develop and implement a watershed wide strategy; AMAFCA and COA will work with EPA, as needed, to develop a reasonable time frame.	• Temperature data will continue to be collected in the Rio Grande using sondes. The sonde data will be available upon request.	<b>Met FY 2023 Goals.</b> • In FY 2023, temperature data was collected in the Rio Grande using the four sondes that are described in the Dissolved Oxygen MS4 Permit program section of the Annual Report. In addition, temperature data was collected during Compliance Monitoring Cooperative (CMC) sampling, Wet Weather monitoring during AMAFCA's internal stormwater quality monitoring, and during the Citizen Science sampling. • In FY 2023, the sondes recorded sixteen (16) temperature exceedances of the 32.2 degrees C water quality standard in the Rio Grande related to precipitation within the watershed in July 2022 (FY 2023). In-stream monitoring memos discuss this data further and are available upon request. The temperature graphs from the sondes are provided in the Temperature Program Summary for this Annual Report.
Not Included in NOI	25	<a href="#">Part I.C.1.f.(iii)</a> - Provide a progress report with the first and with subsequent Annual Reports. The progress reports shall include: (a) Summary of data. (b) Activities undertaken to identify MS4 discharge contribution to exceedances of applicable temperature water quality standards in waters of the United States. (c) Conclusions drawn, including supporting information for any determinations. (d) Activities undertaken to reduce MS4 discharge contribution to exceedances of applicable temperature water quality standards in waters of the United States. (e) Accounting of stakeholder involvement.	<a href="#">Part I.C.1.f.(iii)</a> - AMAFCA will include progress regarding temperature impacts from stormwater to the Rio Grande that include adherence to schedule, activities undertaken, monitoring results, and conclusions drawn with Annual Reports, as applicable. AMAFCA will incorporate documentation by reference into the Annual Report and plans to document progress on the AMAFCA website.  AMAFCA has provided data from 1982 to 2017 showing that the Rio Grande is not adversely affected by the temperature of stormwater from the Albuquerque MS4. The temperature monitoring results do not show a temperature exceedance at any of the monitoring locations in the watershed or in the river.	• Any update of data, activities, and conclusions regarding temperature impacts from stormwater to the Rio Grande will be provided with each Annual Report, if applicable. AMAFCA will incorporate documentation by reference into the Annual Report and plans to document progress on the AMAFCA website.	<b>Met FY 2023 Goals.</b> • This Annual Report serves as a progress report to EPA. Temperature data collected in the Rio Grande during FY 2023 continues to show that temperature exceedances in the Rio Grande due to stormwater from the contributing Albuquerque watershed are not occurring. AMAFCA, through its Annual Reports and associated communication with EPA, has provided data from 1982 to 2023 showing that the Rio Grande is not adversely affected by the temperature of stormwater from the Albuquerque MS4. • In FY 2023, AMAFCA continued to operate real-time telemetry capabilities to these four sondes, allowing AMAFCA to be aware of sonde issues in real time resulting in less data gaps. Login information was shared with the Pueblo of Isleta so they could view the data in an effort to improve data sharing and coordination with watershed stakeholders.

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
	26	<b>Discharges to Impaired Waters With Approved TMDLs - Part I.C.2.b.(i) and TABLE 1.a - TMDL Bacteria Program- Part I.C.2.b.(iii)</b>			
Not Included in NOI	27	<p>According to the requirements in <a href="#">Part I.C.2.b.(i)</a>, if the permittee discharges to an impaired water body with an approved TMDL (see MS4 Permit, Appendix B), where stormwater has the potential to cause or contribute to the impairment, the permittee shall include in the SWMP controls targeting the pollutant(s) of concern along with any additional or modified controls required in the TMDL and this section. As stated in the Permit, Appendix B, a bacteria TMDL for the Middle Rio Grande was approved by the New Mexico Water Quality Control Commission on April 13, 2010, and by EPA on June 30, 2010. The new TMDL modifies: 1) the indicator parameter for bacteria from fecal coliform to E. coli, and 2) the way the WLAs are assigned</p> <p>The SWMP and required Annual Reports must include information on implementing any focused controls required to reduce the pollutant(s) of concern as described below:</p>	<p><a href="#">Part I.C.2.b.(i)</a> - A bacteria TMDL for the Middle Rio Grande was approved by the New Mexico Water Quality Control Commission on April 13, 2010, and by EPA on June 30, 2010. AMAFCA's proposed plans for compliance with the Permit activities are described in the sections below.</p>	<p>AMAFCA's measurable goals for compliance with the Permit activities are described in the sections below.</p>	<p>See specific Permit activity below.</p>
Not Included in NOI	28	<p><a href="#">Part I.C.2.b.(i).(a)</a>, Targeted Controls: The SWMP submitted with the first Annual Report must include a detailed description of all targeted controls to be implemented, such as identifying areas of focused effort or implementing additional BMPs that will be implemented to reduce the pollutant(s) of concern in the impaired waters. and <a href="#">Part I.C.2.b.(i).(b)</a>, Measurable Goals: For each targeted control, the SWMP must include a measurable goal and an implementation schedule describing BMPs to be implemented during each year of the permit term. Where the impairment is for bacteria, the permittee must, at minimum comply with the activities and schedules described in Table 1.a of Part I.C.2.b.(iii).</p> <p>As required in <a href="#">Part I.C.2.b.(i).(e)</a>, the permittee shall include focused BMPs addressing the five areas below:  <b>A. Sanitary Sewer Systems</b> - improve sanitary sewers; fix lift stations; identify and implement O&amp;M procedures; improve violation reporting; and prevent overflows;  <b>B. On-site Sewage Facilities</b> - address failing systems and inadequate maintenance of On-Site Sewage Facilities;</p>	<p><a href="#">Part I.C.2.b.(i).(a), (b), &amp; (e)</a> -AMAFCA's proposed plan for targeted controls and measurable goals (see column to right) for bacteria include:  <b>A. Sanitary Sewer Systems - Targeted Controls:</b> There are no sanitary sewer systems owned or operated by AMAFCA within AMAFCA owned property. Related to the Illicit Discharges and Improper Disposal Control Measure, AMAFCA will receive monthly DMRs of sanitary sewer overflows (SSO) from ABCWUA. These will be evaluated to ensure that the SSOs did not impact AMAFCA facilities.  <b>B. On-site Sewage Facilities - Targeted Controls:</b> There are no on-site sewage facilities owned or operated by AMAFCA within AMAFCA-owned property.</p>	<p><b>A. Sanitary Sewer Systems - Measurable Goals:</b>                      • There are no sanitary sewer systems owned or operated by AMAFCA within AMAFCA-owned property.                      • Through the IDDE Program, AMAFCA will continue coordination with ABCWUA, who will inform AMAFCA of any SSOs that potentially impact AMAFCA facilities. AMAFCA will receive monthly DMRs of SSOs from ABCWUA. These will be evaluated to ensure that the SSOs did not impact AMAFCA facilities. AMAFCA will continue to add these to GIS to improve tracking of the SSOs.  <b>B. On-site Sewage Facilities - Measurable Goals:</b>                      • Not applicable to AMAFCA</p>	<p><b>Met FY 2023 Goals.</b>  <b>A. Sanitary Sewer Systems:</b>                      • There are no sanitary sewer systems owned or operated by AMAFCA within AMAFCA owned property.                      • AMAFCA received and reviewed the monthly DMR forms from ABCWUA. AMAFCA also has entered these into GIS to improve tracking of the SSOs.                      • AMAFCA can and has accepted sanitary sewer flows, given emergency overflow conditions in the watershed, to help protect the Rio Grande water quality.                      • AMAFCA investigated applicable illicit discharge complaints received through the 311 call in program, as well as other complaints received directly by AMAFCA through e-mail or phone.  <b>B. On-site Sewage Facilities:</b>                      • Not applicable to AMAFCA</p>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
Not Included in NOI	29	Continuation of five areas in Part I.C.2.b.(i).(e) - <u>C. Illicit Discharges and Dumping</u> - effort to reduce waste sources of bacteria; for ex., septic systems, grease traps, and grit traps; <u>D. Animal Sources</u> - management programs to identify and target sources such as zoos, pet waste, and horse stables; <u>E. Residential Education</u> - bacteria from residential sites; fats, oils, and grease (FOG) clogging sanitary sewer lines and resulting overflows; decorative ponds; and pet waste.	<p><u>Part I.C.2.b.(i).(a), (b), &amp; (e)</u> - Continuation - AMAFCA's proposed plan for targeted controls and measurable goals (see column to right) for bacteria include:</p> <p><u>C. Illicit Discharges and Dumping - Targeted Controls:</u> AMAFCA has a robust IDDE Program. In the IDDE program, AMAFCA has focused on homeless camp cleanup and other efforts that target sources of bacteria. In addition, AMAFCA has manual and mechanical trash contracts to address IDDE cleanup. Refer to the Illicit Discharges and Improper Disposal Control Measure for additional information.</p> <p><u>D. Animal Sources - Targeted Controls:</u> AMAFCA will continue its focus on reducing pet waste through its Mutt Mitt Stations Program and its involvement with the MRGSQT educational outreach "Scoop the Poop" and/or "There is No Poop Fairy" campaigns.</p> <p><u>E. Residential Education - Targeted Controls:</u> AMAFCA will address this area through Public Education and Outreach and Public Involvement and Participation Control Measures through its involvement with the MRGSQT.</p>	<p>C. Illicit Discharges and Dumping - Measurable Goals:</p> <ul style="list-style-type: none"> <li>• AMAFCA will address the Illicit Discharge and Dumping through its IDDE Program; refer to the Illicit Discharges and Improper Disposal Control Measure for additional information. This IDDE program includes illicit discharge monitoring by AMAFCA staff and crew that often involves weekly discussion at staff meetings. Reports of discharge are cooperatively investigated by staff including, if appropriate, tracking and documentation procedures. An annual budget line item exists for contracts to address IDDE cleanup.</li> </ul> <p>D. Animal Sources - Measurable Goals:</p> <ul style="list-style-type: none"> <li>• AMAFCA will continue to provide Mutt Mitt Stations and bags in an effort to reduce pet waste reaching stormwater.</li> <li>• AMAFCA will continue to contribute and participate in the MRGSQT. Through the MRGSQT, pet waste will be targeted through the "Scoop the Poop" and/or "There is No Poop Fairy" campaigns and other programs.</li> <li>• As funding becomes available, AMAFCA will participate and/or conduct microbial source tracking (MST) studies in the Middle Rio Grande.</li> </ul> <p>E. Residential Education - Measurable Goals:</p> <ul style="list-style-type: none"> <li>• The MRGSQT Outcomes Report will summarize the activities and is available upon request and AMAFCA plans to share this document on its website.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <p><u>C. Illicit Discharges and Dumping:</u></p> <ul style="list-style-type: none"> <li>• Refer to the Illicit Discharges and Improper Disposal Control section of the Annual Report for FY 2023 performance and implementation status.</li> </ul> <p><u>D. Animal Sources:</u></p> <ul style="list-style-type: none"> <li>• AMAFCA has continued the Mutt Mitt Station program. Tracking procedures continued in FY 2023 for this program.</li> <li>• The MRGSQT Outcomes Report summarizes the educational and outreach programs for FY 2023. This report is provided as a Program Summary. Pet waste education is a large component of the cooperative MRGSQT outreach efforts.</li> </ul> <p><u>E. Residential Education:</u></p> <ul style="list-style-type: none"> <li>• The MRGSQT Outcomes Report summarizes the educational and outreach programs for FY 2023. This report is contained in the Program Summaries section of the Annual Report.</li> </ul>
	30	<p><u>Part I.C.2.b.(i).(c).B</u> - Identification of Measurable Goal: The SWMP must identify a measurable goal for the pollutant(s) of concern. The value of the measurable goal must be based on one of the following options in the Permit - AMAFCA is using Option B:</p> <p>B. Alternatively, if multiple permittees are discharging into the same impaired water body with an approved TMDL (which has an aggregate WLA for all permitted stormwater MS4s), the MS4s may combine or share efforts, in consultation with/and the approval of NMED, to determine an alternative sub-measurable goal derived from the WLA for the pollutant(s) of concern (e.g., bacteria) for their respective MS4. The SWMP must clearly define this alternative approach and must describe how the sub-measurable goals would cumulatively support the aggregate WLA. Where an aggregate WLA measurable goal has been broken into sub-measurable goals for individual MS4s, each permittee is only responsible for progress in meeting its WLA sub-measurable goal.</p>	<p><u>Part I.C.2.b.(i).(c).B</u> - AMAFCA identified in its NOI that it was seeking, as part of a group of MS4s, an alternative sub-measurable goal for TMDL control under this part of the Permit. NMED and EPA were informed of this decision and NMED has worked with the CMC to help establish the cooperative waste load allocation (WLA) values and methodology for calculating E. coli loading. AMAFCA will continue following the established methodology for applying this to the CMC monitoring results.</p>	<ul style="list-style-type: none"> <li>• AMAFCA, as part of the CMC, will use the analytical results obtained in the Rio Grande during the CMC sampling and calculate an E. coli loading to compare with the waste load allocation allotted for the cooperative portion for the two defined stream assessment units of the Rio Grande (Isleta to Alameda and Alameda to Angostura). These calculations will be provided in each Annual Report, if applicable, as part of the CMC monitoring memos. AMAFCA will incorporate documentation by reference into the Annual Report and plans to provide documentation on the AMAFCA website.</li> </ul>	<p><b>Met FY 2023 Goal.</b></p> <ul style="list-style-type: none"> <li>• The required CMC sampling for the MS4 Permit term in the Rio Grande (2016 to 2019) was completed in FY 2019. The MRG Watershed Based MS4 Permit entered into administrative continuance in Dec. 2019 when EPA Region 6 did not issue a new MS4 Permit before the current MS4 Permit expiration date. The MS4 TAG sent EPA an Administrative Continuance letter dated October 15, 2019. Until a new MS4 Permit is issued, there are no compliance monitoring requirements in the Rio Grande.</li> </ul> <p>There was one (1) qualifying storm event monitored by the CMC in FY 2023. E. coli loading calculations were completed in FY 2023. The CMC memo summarizing the FY 2023 CMC wet weather monitoring activity, results, and E. coli loading calculations is attached to this Annual Report.</p>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
Not Included in NOI	31	<p>According to the requirements in <a href="#">Part I.C.2.b.(i).(f)</a>, the permittee shall monitor or assess progress in achieving measurable goals and determining the effectiveness of BMPs, and shall include documentation of this monitoring or assessment in the SWMP and Annual Reports. In addition, the SWMP must include methods to be used. This program element may be coordinated with the monitoring required in Part III.A. The permittee may use the following methods either individually or in conjunction to evaluate progress towards the measurable goal and improvements in water quality as follows:</p> <p>A. Evaluating Program Implementation Measures or                      B. Assessing Improvements in Water Quality</p> <p>Progress towards achieving the measurable goal shall be reported in the Annual Report. Annual reports shall report the measurable goal and the year(s) during the permit term that the MS4 conducted additional sampling or other assessment activities.</p>	<p><a href="#">Part I.C.2.b.(i).(f)</a> - AMAFCA will assess and evaluate the program and progress in achieving the targeted controls and measurable goals listed above by tracking the number of educational outreach opportunities conducted and tracking the number of people reached through the educational outreach program. AMAFCA will incorporate documentation by reference into the Annual Report.</p> <p>AMAFCA is part of the Compliance Monitoring Cooperative (CMC) group, established in 2016, with 12 watershed partners cooperating for the Wet Weather Monitoring Program requirements.</p>	<ul style="list-style-type: none"> <li>The MRGSQT Outcomes Report will track the number of educational outreach opportunities conducted and list the number of people reached through the educational outreach program. This report is available upon request.</li> <li>AMAFCA will conduct stormwater monitoring in accordance with the Wet Weather Monitoring Program, Part III.A.1 as part of the CMC. The goals and plan for this program are described in the Wet Weather Monitoring Program portion of this SWMP.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>The MRGSQT Outcomes Report summarizes the educational and outreach programs for FY 2023. This report is contained in the attached Program Summary document.</li> <li>AMAFCA has continued involvement with the Compliance Monitoring Cooperative (CMC) group, established in 2016, with 12 watershed partners cooperating for the Wet Weather Monitoring Program requirements. At the end of FY 2019, the CMC members had met all Wet Weather sample collection requirements in the MS4 Permit. The MRG Watershed Based MS4 Permit entered into administrative continuance in Dec. 2019 when EPA Region 6 did not issue a new MS4 Permit before the current MS4 Permit expiration date. The MS4 TAG sent EPA an Administrative Continuance letter dated October 15, 2019. Until a new MS4 Permit is issued, there are no compliance monitoring requirements in the Rio Grande. There was one (1) qualifying storm event monitored by the CMC in FY 2023. If the CMC does continue wet weather compliance monitoring during administrative continuance of this MS4 Permit, AMAFCA will summarize, as applicable, any wet weather monitoring activity, results, and E. coli loading calculations in future Program Summaries.</li> </ul>
Not Included in NOI	32	<p><a href="#">Part I.C.2.b.(i).(g)</a> - If, by the end of the 3rd year from the effective date of the permit, the permittee observes no progress toward the measurable goal either from program implementation or water quality assessments, the permittee shall identify alternative focused BMPs that address new or increased efforts towards the measurable goal. As appropriate, the MS4 may develop a new approach to identify the most significant sources of the pollutant(s) of concern and shall develop alternative focused BMPs (this may also include information that identifies issues beyond the MS4's control). These revised BMPs must be included in the SWMP and subsequent Annual Reports. Where the permittee originally used a measurable goal based on an aggregated WLA, the permittee may combine or share efforts with other MS4s discharging to the same impaired stream segment to determine an alternative sub-measurable goal for the pollutant(s) of concern for their respective MS4s, as described in <a href="#">Part I.C.2.b.(i).(c).B</a> above. Permittees must document the proposed schedule for the development and subsequent adoption of alternative measurable goals for the pollutant(s) of concern for their respective MS4s and associated assessment of progress in meeting those individual goals.</p>	<p><a href="#">Part I.C.2.b.(i).(g)</a> - AMAFCA, in cooperation with the TAG, MRGSQT, and CMC has observed progress towards E. coli controls and measurable goals. However, the impairment for E. coli was re-listed in NMED's 2020-2022 State of New Mexico Clean Water Act Section 303(d)/Section 305(b) Integrated Report for 3 of the 4 assessment segments along the river within the Middle Rio Grande corridor; all 4 assessment segments in the Middle Rio Grande, from Isleta Pueblo Boundary to Angostura Diversion Dam, currently has an E. coli impairment. The CMC will continue to collect data during administrative continuance of the Permit to determine if the E. coli trend that previously de-listed the impairment or data that re-listed the impairment is the baseline.</p> <p>AMAFCA will annually assess and evaluate the program and progress in achieving the measurable goals listed in the sections above. In addition to the measurable goals listed above, Microbial Source Tracking (MST) studies may be a tool used for the assessment and evaluation of the program. AMAFCA will also continue to participate in regional water quality studies and plans, as opportunities become available, to continue to look for collaborative opportunities to improve this program.</p>	<ul style="list-style-type: none"> <li>AMAFCA will continue to annually assess and evaluate the program and progress in achieving the measurable goals listed above. In addition to the measurable goals listed above, Microbial Source Tracking (MST) studies may be a tool used for the assessment and evaluation of the program.</li> <li>AMAFCA will continue to participate in regional water quality studies and plans, as opportunities become available.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>The required CMC sampling for the MS4 Permit term in the Rio Grande (2016 to 2019) was completed in FY 2019. The MRG Watershed Based MS4 Permit entered into administrative continuance in Dec. 2019 when EPA Region 6 did not issue a new MS4 Permit before the current MS4 Permit expiration date. Additional details are provided above. The MRGSQT has funded dry weather E. coli data collection by students in the Bosque Ecosystem Monitoring Program (BEMP) program to better understand the baseline concentration of E. coli before storm events.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
Not Included in NOI	33	<p>Part 1.C.2.b.(iii) - Table 1.a, Identify potential significant sources of the pollutant of concern entering your MS4.</p>	<p>Part 1.C.2.b.(iii) - Table 1.a - In 2014-2015, AMAFCA contracted with a consultant to restudy the bacteria within the Middle Rio Grande, specifically to evaluate the bacteria data over the recent history to report the trend analysis and the impact to the Rio Grande. The report for this study, Middle Rio Grande Rio Grande E. coli Analysis and Research report for AMAFCA by water quality on-call engineer (CDM Smith), is available from AMAFCA upon request.</p> <p>AMAFCA, through the MRGSQT, has contracted with BEMP to study E. coli at various locations along the Rio Grande during dry weather in an effort to identify potential sources of E. coli.</p>	<ul style="list-style-type: none"> <li>AMAFCA, with its co-permittees from the 2012 MS4 Phase I Permit, have completed several studies related to identifying potential significant sources of the pollutant of concern entering the MRG Watershed MS4 area. The results of these studies will be used to guide the overall program plan and goals.</li> <li>AMAFCA, with the MRGSQT, has contracted with BEMP to study E. coli at various locations along the Rio Grande during dry weather in an effort to identify potential sources of E. coli.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>Plots of the AMAFCA collected E. coli data are included in AMAFCA's internal watershed stormwater quality monitoring reports, which are available upon request.</li> <li>AMAFCA, through the MRGSQT, has contracted with BEMP in calendar year 2023 to study E. coli at various locations along the Rio Grande during dry weather and after qualifying storm events in an effort to identify potential sources of E. coli. Results from this study are available upon request.</li> <li>The monitoring reports for FY 2023 for AMAFCA's internal watershed stormwater quality monitoring are available upon request.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
Not Included in NOI	34	From <a href="#">Part 1.C.2.b.(iii) - Table 1.a</a> , Develop (or modify an existing program- for prior permittees under NMS000101) and implement a public education program to reduce the discharge of bacteria in municipal stormwater contributed by (if applicable) by pets, recreational and exhibition livestock, and zoos.	<a href="#">Part 1.C.2.b.(iii) - Table 1.a</a> - As stated above, AMAFCA will continue its focus on reducing pet waste through providing Mutt Mitt Stations and through continued involvement with the MRGSQT educational outreach "Scoop the Poop" campaign.	<ul style="list-style-type: none"> <li>• AMAFCA will continue to provide Mutt Mitt Stations and bags.</li> <li>• AMAFCA will contribute and participate in the MRGSQT.</li> <li>• The MRGSQT Outcomes Report will summarize the activities related to targeting pet waste sources and residential education targeting bacteria sources. This report is available upon request.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• AMAFCA continued its focus on reducing pet waste through providing Mutt Mitt Stations. Mutt Mitt Station supporting data for FY 2023 is available upon request.</li> <li>• In FY 2023, AMAFCA continued to contribute to and participated in the MRGSQT, which included educational outreach for the "Scoop the Poop" and "There is no Poop Fairy" campaigns.</li> <li>• The MRGSQT Outcomes Report summarizes the educational and outreach programs for FY 2023. This report is included as a Program Summary.</li> </ul>
Not Included in NOI	35	From <a href="#">Part 1.C.2.b.(iii) - Table 1.a</a> , Develop (or modify an existing program- for prior permittees under NMS000101) and implement a program to reduce the discharge of bacteria in municipal stormwater contributed by areas within your MS4 served by on-site wastewater treatment systems.	<a href="#">Part 1.C.2.b.(iii) - Table 1.a</a> - As stated above, this is not applicable to AMAFCA. Through the IDDE Program, AMAFCA will continue coordination with ABCWUA, who will inform AMAFCA of any sanitary sewer overflows that impact AMAFCA facilities.	<ul style="list-style-type: none"> <li>• As stated above, this is not applicable to AMAFCA. Through the IDDE Program, AMAFCA will continue coordination with ABCWUA, who will inform AMAFCA of any sanitary sewer overflows that impact AMAFCA facilities.</li> </ul>	<p><b>Met FY 2023 Goal.</b></p> <ul style="list-style-type: none"> <li>• AMAFCA received and reviewed the monthly DMR forms from ABCWUA. These reports are available upon request. These have also been entered into GIS to improve tracking and identify potential trends of the SSOs.</li> </ul>
Not Included in NOI	36	From <a href="#">Part 1.C.2.b.(iii) - Table 1.a</a> , Review results to date from the Illicit Discharge Detection and Elimination program (see <a href="#">Part 1.D.5.e</a> ) and modify as necessary to prioritize the detection and elimination of discharges contributing bacteria to the MS4.	<a href="#">Part 1.C.2.b.(iii) - Table 1.a</a> - AMAFCA will incorporate this Permit requirement into the IDDE program, refer to the SWMP - Table 6: Illicit Discharges and Improper Disposal - for additional information.	<ul style="list-style-type: none"> <li>• AMAFCA will address this Permit activity in the IDDE Program, refer to the SWMP - Table 6: Illicit Discharges and Improper Disposal - for additional information.</li> </ul>	<p><b>Met FY 2023 Goal.</b></p> <ul style="list-style-type: none"> <li>• AMAFCA addresses this Permit activity in the Illicit Discharges and Improper Disposal Control Measure.</li> </ul>
Not Included in NOI	37	<a href="#">Part 1.C.2.b.(iii) - Table 1.a</a> - Develop (or modify an existing program- for prior permittees under NMS000101) and implement a program to reduce the discharge of bacteria in municipal stormwater contributed by other significant source identified in the Illicit Discharge Detection and Elimination program (see <a href="#">Part 1.D.5.e</a> ).	<a href="#">Part 1.C.2.b.(iii) - Table 1.a</a> - This requirement will be addressed in conjunction with AMAFCA's IDDE Program, refer to the SWMP Table 6: Illicit Discharges and Improper Disposal, for additional information. AMAFCA will review its IDDE Program results annually and identify illicit discharges (specific as well as general types of discharges and/or locations of discharges) that contributed bacteria to the MS4. Strategies will be developed to address these specific or general IDDEs. Development and implementation of strategies will depend on the IDDE program results.	<ul style="list-style-type: none"> <li>• AMAFCA will review its IDDE Program results annually.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• AMAFCA addresses this Permit activity in the Illicit Discharges and Improper Disposal Control Measure.</li> </ul>
Not Included in NOI	38	Include in the Annual Reports progress on program implementation and reducing the bacteria and updates their measurable goals as necessary. As required in <a href="#">Part 1.C.2.b.(i),(d)</a> , the Annual Report must include an analysis of how the selected BMPs have been effective in contributing to achieving the measurable goal and shall include graphic representation of pollutant trends, along with computations of annual percent reductions achieved from the baseline loads and comparisons with the target loads.	<a href="#">Part 1.C.2.b.(i),(d)</a> - The MRGSQT Outcomes Report will track the number of educational outreach opportunities conducted, list the number of people reached through the educational outreach program, and summarize the activities related to targeting pet waste sources as well as residential education targeting bacteria sources. This report is available upon request. In addition, if strategies are developed to address IDDEs found to contribute bacteria to the MS4, these will be reported in subsequent Annual Reports. AMAFCA will report annually on compliance monitoring to monitor and test for E. coli. This reporting will be done in accordance with Part III.A (Wet Weather Monitoring Program) of the MS4 Permit.	<ul style="list-style-type: none"> <li>• The MRGSQT Outcomes Report is available upon request.</li> <li>• AMAFCA will report annually on compliance monitoring to monitor and test for E. coli. This reporting will be done in accordance with Part III.A (Wet Weather Monitoring Program) of the MS4 Permit.</li> <li>• Graphical representation of E. coli trends will also be completed annually.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• The MRGSQT Outcomes Report summarizes the educational and outreach programs for FY 2023. This report is included as a Program Summary.</li> <li>• Plots of the AMAFCA collected E. coli data are included in AMAFCA's internal watershed stormwater quality monitoring reports, which are available upon request and also provided in the Program Summary.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
	39	<b>Discharges to Impaired Waters Without Approved TMDLs - Part I.C.2.b.(ii)</b>			
Not Included in NOI	40	<p>According to the requirements in <a href="#">Part I.C.2.b.(ii)</a>, if the permittee discharges directly into an impaired water body without an approved TMDL, the permittee shall perform the following activities (described in sections below).</p>	<p><a href="#">Part I.C.2.b.(ii)</a> - The Rio Grande impairments are listed on the EPA Annual Report Summary Form, pages 1-2.</p> <p>The Tijeras Arroyo upstream of the Four Hills Bridge is impaired for nutrient/eutrophication. The Tijeras Arroyo upstream of the Four Hills Bridge is all privately owned land. AMAFCA's operation and maintenance authority and access to the Tijeras Arroyo terminate at the Four Hills Bridge. Therefore, there are no requirements in this SWMP to comply with the activities and schedules related to Impairment for Nutrients in Table 1.b in <a href="#">Part I.C.2.b.(iii)</a>. AMAFCA does monitor for nutrients through its Wet Weather Monitoring Program, see Table 10 of the SWMP.</p>	<ul style="list-style-type: none"> <li>Impairment for Dissolved Oxygen is addressed in the Endangered Species Act (ESA) section - Part I.C.3. The SWMP section for Part I.C.3 describes the proposed plan and measurable goals.</li> <li>Impairment for PCBs is addressed in Compliance with Water Quality Standards - PCBs - Part I.C.1.e. The SWMP section for Part I.C.1.e describes the proposed plan and measurable goals.</li> <li>Impairment for Temperature is addressed in Compliance with Water Quality Standards - Temperature - Part I.C.1.f. The SWMP section for Part I.C.1.f describes the proposed plan and measurable goals.</li> <li>Compliance monitoring (Part III.A) includes Gross Alpha testing. Future assessment related to the impairment will be based on results of those samples.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>AMAFCA addresses this Permit activity in other Permit sections - please refer to these sections of the Annual Report for the FY 2023 status of implementation and performance assessment.</li> <li>Dissolved Oxygen is addressed in the Endangered Species Act (ESA) section - Part I.C.3.a.</li> <li>PCBs are addressed in Compliance with Water Quality Standards - PCBs - Part I.C.1.e.</li> <li>Temperature is addressed in Compliance with Water Quality Standards - Temperature - Part I.C.1.f.</li> <li>Gross Alpha is part of the Wet Weather Monitoring - Part III.A.</li> </ul>
Not Included in NOI	41	<p><a href="#">Part I.C.2.b.(ii).(a)</a> - The permittee shall:</p> <p>A. Determine whether the MS4 may be a source of the pollutant(s) of concern by referring to the CWA §303(d) list and then determining if discharges from the MS4 would be likely to contain the pollutant(s) of concern at levels of concern. The evaluation of CWA §303(d) list parameters should be carried out based on an analysis of existing data (e.g., IDDE Program) conducted within the permittee's jurisdiction.</p> <p>B. Ensure that the SWMP includes focused BMPs, and corresponding measurable goals, that the permittee will implement, to reduce, the discharge of pollutant(s) of concern that contribute to the impairment of the water body. Only applicable if the permittee determines that the MS4 may discharge the pollutant(s) of concern to an impaired water body without a TMDL. The SWMP submitted with the first Annual Report must include a detailed description of proposed controls to be implemented along with measurable goals.</p> <p>C. Amend the SWMP to include any BMPs to address the pollutant(s) of concern.</p>	<p><a href="#">Part I.C.2.b.(ii).(a)</a> - Most of the impaired pollutants of concern are specifically addressed in other sections of the MS4 Program and therefore in other sections of the SWMP. Please refer to: Dissolved Oxygen and Endangered Species Act (ESA) section - Part I.C.3; PCBs are addressed in Compliance with Water Quality Standards - PCBs - Part I.C.1.e; and Temperature is addressed in Compliance with Water Quality Standards - Temperature - Part I.C.1.f.</p> <p>Compliance monitoring (Part III.A) includes Gross Alpha testing. The testing will allow the CMC to determine the background level relative to stormwater discharges. Future assessment related to this impairment will be based on results of those samples.</p>	<p>Refer to other SWMP sections for:</p> <ul style="list-style-type: none"> <li>Dissolved Oxygen is addressed in the Endangered Species Act (ESA) section - Part I.C.3.</li> <li>PCBs are addressed in Compliance with Water Quality Standards - PCBs - Part I.C.1.e.</li> <li>Temperature is addressed in Compliance with Water Quality Standards - Temperature - Part I.C.1.f.</li> <li>Compliance monitoring (Part III.A) includes Gross Alpha testing. Future assessment and strategies related to this impairment will be based on results of the stormwater samples.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>AMAFCA addresses this Permit activity in other Permit sections. Please refer to these sections of the Annual Report for the FY 2023 status of implementation and performance assessment.</li> <li>Dissolved Oxygen is addressed in the Endangered Species Act (ESA) section - Part I.C.3.a.</li> <li>PCBs are addressed in Compliance with Water Quality Standards - PCBs - Part I.C.1.e.</li> <li>Temperature is addressed in Compliance with Water Quality Standards - Temperature - Part I.C.1.f.</li> <li>Gross Alpha is addressed in the Wet Weather Monitoring - Part III.A.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
	42	<b>Endangered Species Act (ESA) Requirements - Sediment Pollutant Load Reduction Strategy - Part I.C.3.b</b>			
Not Included in NOI	43	According to the requirements in <a href="#">Part I.C.3.b</a> , the permittee must develop, implement, and evaluate a sediment pollutant load reduction strategy to assess and reduce pollutant loads associated with sediment (e.g., metals, etc. adsorbed to or traveling with sediment, as opposed to clean sediment) into the receiving waters of the Rio Grande. The strategy must include the following elements (see sections below):	<a href="#">Part I.C.3.b</a> - AMAFCA's proposed plan for compliance with the Permit activities are described in the sections below.	AMAFCA's measurable goals for compliance with the Permit activities are described in the sections below.	See specific Permit activity below.
Not Included in NOI	44	<a href="#">Part I.C.3.b.(i)</a> - Sediment Assessment: The permittee must identify and investigate areas within its jurisdiction that may be contributing excessive levels (e.g., levels that may contribute to exceedance of applicable Water Quality Standards) of pollutants in sediments to the receiving waters of the Rio Grande as a result of stormwater discharges. The permittee must identify structural elements, natural or man-made topo-graphical and geographical formations, MS4 operations activities, and areas indicated as potential sources of sediments and pollutants in the receiving waters of the Rio Grande. At the time of assessment, the permittee shall record any observed erosion of soil or sediment along ephemeral channels, arroyos, or stream banks, noting the scouring or sedimentation in streams. The assessment should be made using available data from federal, state, or local studies supplemented as necessary with collection of additional data. The permittee must describe, in the first Annual Report, all standard operating procedures, quality assurance plans to assure that accurate data are collected, summarized, evaluated and reported.	<a href="#">Part I.C.3.b.(i)</a> - All AMAFCA projects are regional flood control or water quality projects. Stormwater runoff from other MS4s enter AMAFCA facilities, which function as regional flood control facilities and also function as BMPs to capture sediment from stormwater before the stormwater continues to the Rio Grande. In the MRG MS4, AMAFCA is not adversely contributing to the sediment pollutant load, but rather functioning to capture the sediment pollutant load generated throughout the watershed by MS4s contributing runoff to AMAFCA facilities. A large portion of AMAFCA's routine activities include sediment removal from its facilities. AMAFCA has implemented a crew tracking system to measure the sediment removal quantities at all of its facilities. The data collected will be used by AMAFCA for the required MS4 Sediment Assessment. As part of AMAFCA's regular O&M activities, AMAFCA will continue the sediment assessment phase by tracking and estimating the volume of sediment removed from their stormwater facilities annually. The tracking of this data will continue and will be valuable to AMAFCA as it applies to this program and to future planning activities.  In addition, AMAFCA will continue a rainfall and runoff monitoring program to quantitatively relate sediment removal to rainfall quantity, location, and runoff volume. AMAFCA has standard operating procedures (SOPs) related to operation and maintenance and a scheduling spreadsheet for inspections. These SOPs and procedures ensure that AMAFCA has accurate data related to sediment removal activities.	<ul style="list-style-type: none"> <li>AMAFCA's facilities function as BMPs for sediment removal. AMAFCA's O&amp;M activities, which include sediment removal, will be scheduled, tracked, and evaluated for the Sediment Assessment requirement for this Permit activity.</li> <li>AMAFCA will continue using a crew tracking system to measure the sediment removal quantities at all of its facilities and use this information for the Sediment Assessment.</li> <li>AMAFCA will continue with a rainfall and runoff monitoring program to continue to quantitatively relate sediment removal to rainfall quantity, location, and runoff volume.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>In FY 2023, AMAFCA adhered to its current established procedures in the "AMAFCA O&amp;M Manual for Dams" and the "AMAFCA O&amp;M Repair Replacement and Rehabilitation Manual" for sediment removal activities. Refer to the Pollution Retention/Good Housekeeping Control Measure for additional information.</li> <li>AMAFCA's crew tracking system and database lists each of its stormwater quality facilities by drainage basin. These facilities are also shown on the AMAFCA Maintenance Map, available online: <a href="http://www.amafca.org/maps-2/">http://www.amafca.org/maps-2/</a>.</li> <li>In FY 2023, AMAFCA continued to operate and analyze data from 14 Levelloggers located at the channelized inlets to the NDC on AMAFCA ROW. This project is the initial runoff monitoring phase and AMAFCA started utilizing this data to quantitatively relate sediment removal to rainfall quantity, location, and runoff volume. Additional information is available upon request.</li> </ul>



NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
Not Included in NOI	45	<p>Part 1.C.3.b.(ii) - Estimate Baseline Loading: Based on the results of the sediment pollutants assessment required in Part 1.C.3.b.(i) above, the permittee must provide estimates of baseline total sediment loading and relative potential for contamination of those sediments by urban activities for drainage areas, sub-watersheds, Impervious Areas (IAs), and/or Directly Connected Impervious Area (DCIAs) draining directly to a surface waterbody or other feature used to convey waters of the United States. Sediment loads may be provided for targeted areas in the entire Middle Rio Grande Watershed using an individual or cooperative approach. Any data available and/or preliminary numeric modeling results may be used in estimating loads.</p>	<p>Part 1.C.3.b.(ii) - In 2016, the COA, with cooperation from AMAFCA and area MS4s, completed an initial sediment assessment, "City of Albuquerque 2016 Sediment Assessment". This initial study assisted in establishing the baseline for the sediment assessment. In FY 2019, AMAFCA cooperated with Bernalillo County, who led the effort for the watershed to complete the estimated baseline sediment loading evaluation. Sediment loads are provided for targeted areas in the entire Middle Rio Grande Watershed using a cooperative approach. The "Progress Evaluation Report for the Sediment Pollutant Load Reduction Strategy" report, June 25, 2019 summarizes the sediment loading evaluation at five main outfalls into the Rio Grande. The data AMAFCA collected in the Sediment Assessment was used for estimating baseline sediment loading to its facilities. AMAFCA will review the "Progress Evaluation Report for the Sediment Pollutant Load Reduction Strategy" report and discuss the findings with the watershed MS4s. The results of this study may be used to guide the overall program plans and goals.</p>	<p>• AMAFCA will review the "Progress Evaluation Report for the Sediment Pollutant Load Reduction Strategy" report and discuss the findings with the watershed MS4s. The results of this study may be used to guide the overall program plans and goals. Updates to the Sediment Pollutant Load Reduction Strategy will be implemented, as applicable.</p>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• AMAFCA has reviewed the "Progress Evaluation Report for the Sediment Pollutant Load Reduction Strategy" report, June 25, 2019 which summarizes the sediment loading evaluation at five main outfalls into the Rio Grande. In FY 2023, there were no updates to report.</li> <li>• In FY 2023, AMAFCA continued to operate and analyze data from 14 Levelloggers located at the channelized inlets to the NDC on AMAFCA ROW. Additional information is available upon request.</li> </ul>
Not Included in NOI	46	<p>Part 1.C.3.b.(iii) - Targeted Controls: Include a detailed description of all proposed targeted controls and BMPs that will be implemented to reduce sediment pollutant loads, calculated in Part 1.C.3.b.(ii) above, during the next ten (10) years of permit issuance. For each targeted control, the permittee must include interim measurable goals (e.g., interim sediment pollutant load reductions) and an implementation and maintenance schedule, including interim milestones, for each control measure, and as appropriate, the months and years in which the MS4 will undertake the required actions. Any data available and/or preliminary numeric modeling results may be used in establishing the targeted controls, BMPs, and interim measurable goals. The permittee must prioritize pollutant load reduction efforts and target areas (e. g. drainage areas, sub watersheds, IAs, DCIAs) that generate the highest annual average pollutant loads.</p>	<p>Part 1.C.3.b.(iii) - AMAFCA facilities function as regional flood control facilities as well as BMPs to remove sediment from stormwater before the stormwater reaches the Rio Grande. In the MRG MS4, AMAFCA is not adversely contributing to the sediment pollutant load, but rather functioning to capture the sediment pollutant load generated throughout the watershed by MS4s contributing runoff to AMAFCA facilities. As such, AMAFCA does not want to reduce the sediment loads but rather implement targeted controls to increase the capture of sediment in its facilities.</p> <p>The completed analysis of the Sediment Assessment and Estimated Baseline Loading will be used by AMAFCA to improve their program to target and prioritize sediment removal throughout the watershed. AMAFCA will continue to estimate the annual volume of sediment removed from each control facility. The AMAFCA operations and maintenance crew and subcontractors track the volume of floatables, sediment, trash, and debris removed from AMAFCA facilities on a daily basis. This tracking procedure includes the location of removal by facility and watershed. AMAFCA will continue to utilize the 2017 updated, cooperative waste characterization study, updating the "AMAFCA/Albuquerque MS4 Floatable and Gross Pollutant Study" conducted in 2005, to assist with determining needed controls and BMPs that may be implemented to reduce sediment pollutant loads. AMAFCA will continue analyzing, planning, and constructing needed sediment control BMPs. The AMAFCA Project Schedule process may be utilized in part for identifying, ranking, and planning area BMPs. AMAFCA's Mutt Mitt stations program will continue as a targeted BMP to reduce pollutants (specifically E. coli) present in sediment within the MS4.</p>	<p>• AMAFCA will review the "Progress Evaluation Report for the Sediment Pollutant Load Reduction Strategy" report and discuss the findings with the watershed MS4s. The results of this study may be used to guide the overall program plans and goals. Updates to the Sediment Pollutant Load Reduction Strategy will be implemented, as applicable.</p> <ul style="list-style-type: none"> <li>• AMAFCA will continue to estimate the annual volume of sediment removed from each control facility. The AMAFCA operations and maintenance crew and subcontractors track the volume of floatables, sediment, trash, and debris removed from AMAFCA facilities on a daily basis. This tracking procedure includes the location of removal by facility and watershed.</li> <li>• AMAFCA will continue utilizing the updated, cooperative waste characterization study in the watershed to assist with determining needed controls and BMPs that may be implemented to reduce sediment pollutant loads.</li> <li>• AMAFCA will continue analyzing, planning, and constructing needed sediment control BMPs. The AMAFCA Project Schedule process may be utilized in part for identifying, ranking, and planning area BMPs.</li> <li>• AMAFCA will continue its Mutt Mitt program focusing on reducing pollutants (specifically E. coli) present in sediment within the MS4.</li> </ul>	<p><b>No Goals Required for FY 2023.</b></p> <ul style="list-style-type: none"> <li>• The "Progress Evaluation Report for the Sediment Pollutant Load Reduction Strategy" report was completed at the end of FY 2019. An important element of the Strategy is the use of targeted controls and BMPs to reduce sediment transport by stormwater into the receiving water of the Rio Grande. In FY 2023, AMAFCA continued to maintain, design, and construct BMPs throughout its jurisdiction to reduce sediment transport by stormwater into the receiving water of the Rio Grande.</li> <li>• In FY 2023, AMAFCA continued use of the crew tracking system and database to estimate the volume of trash, homeless debris, sediment, and vegetation removed from its water quality facilities. Summary information is provided in the Program Summary and additional details are available upon request.</li> <li>• In FY 2023, AMAFCA continued its Mutt Mitt Station Program. Summary information for the Mutt Mitt Stations and bags is provided in the Program Summary and additional details are available upon request.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
Not Included in NOI	47	<p>Part I.C.3.b.(iv) - Monitoring and Interim Reporting: The permittee shall monitor or assess progress in achieving interim measurable goals and determining the effectiveness of BMPs, and shall include documentation of this monitoring or assessment in the SWMP and Annual Reports. In addition, the SWMP must include methods to be used. This program element may be coordinated with the monitoring required in Part III.A.</p>	<p>Part I.C.3.b.(iv) - AMAFCA will annually assess progress for this program. AMAFCA will monitor the volume of sediment captured by each of its facilities by measuring the volume of sediment removed from each facility. Documentation of this monitoring will be done using the tracking spreadsheet and procedure. AMAFCA will incorporate documentation by reference into the Annual Report. In addition, as mentioned above, AMAFCA will use the "Progress Evaluation Report for the Sediment Pollutant Load Reduction Strategy" report to guide the overall program plans and goals. Related monitoring also occurs through the Levellogger program, monitoring rainfall events and generated runoff. Monitoring and assessment will be considered during the development of future program plans and goals.</p>	<ul style="list-style-type: none"> <li>• AMAFCA will incorporate documentation by reference into the Annual Report.</li> <li>• Documentation of volume of sediment removed will continue to be done using the crew tracking spreadsheet and procedure.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• In FY 2023, AMAFCA continued utilizing the crew tracking system and database for sediment assessment and estimating baseline loading. Additional information is available upon request.</li> <li>• In FY 2023, AMAFCA continued to operate and analyze data from 14 Levelloggers located at the channelized inlets to the NDC on AMAFCA ROW. Additional information is available upon request.</li> </ul>
Not Included in NOI	48	<p>Part I.C.3.b.(v) - Progress Evaluation and Reporting: The permittee must assess the overall success of the Sediment Pollutant Load Reduction Strategy and document both direct and indirect measurements of program effectiveness in a Progress Report to be submitted with the fifth Annual Report. Data must be analyzed, interpreted, and reported so that results can be applied to such purposes as documenting effectiveness of the BMPs and compliance with the ESA requirements specified in Part I.C.3.b. The Progress Report must include:</p> <p>(a) A list of species likely to be within the action area;</p> <p>(b) Type and number of structural BMPs installed;</p> <p>(c) Evaluation of pollutant source reduction effects;</p> <p>(d) Any recommendation based on program evaluation;</p> <p>(e) Description of how the interim sediment load reduction goals established in Part I.C.3.b.(iii) were achieved; and</p> <p>(f) Future planning activities needed to achieve increase of sediment load reduction required in Part I.C.3.d.(iii).</p>	<p>Part I.C.3.b.(v) - AMAFCA facilities function as regional flood control facilities as well as BMPs to remove sediment from stormwater before the stormwater reaches the Rio Grande. In the MRG MS4, AMAFCA is not adversely contributing to the sediment pollutant load, but rather functioning to capture the sediment pollutant load generated throughout the watershed by MS4s contributing runoff to AMAFCA facilities. AMAFCA's goal is to implement targeted controls to increase the capture of sediment in its facilities rather than reducing sediment loads. AMAFCA worked cooperatively with Bernalillo County, City of Albuquerque, and SSCAFCA to complete this MS4 Permit requirement. The Progress Report on the Sediment Pollutant Load Reduction Strategy. This Progress report meets the MS4 Permit requirements, including:</p> <p>(a) A list of species likely to be within the action area;</p> <p>(b) Type and number of structural BMPs installed;</p> <p>(c) Evaluation of pollutant source reduction effects;</p> <p>(d) Any recommendation based on program evaluation;</p> <p>(e) Description of how the interim sediment load reduction goals established in Part I.C.3.b.(iii) were achieved; and</p> <p>(f) Future planning activities needed to achieve increase of sediment load reduction required in Part I.C.3.d.(iii).</p> <p>Related to the elements required by this Progress report, AMAFCA will continue to 1) maintain a cumulative list of AMAFCA's retrofit BMPs and 2) may utilize the AMAFCA Project Schedule process in part for identifying, ranking, and planning area BMPs to meet recommendations from this program evaluation.</p>	<ul style="list-style-type: none"> <li>• AMAFCA has completed this report and provided this to EPA with the FY 2019 Annual Report, December 1, 2019, a Progress Report on the Sediment Pollutant Load Reduction Strategy. AMAFCA cooperated with Bernalillo County, who led the effort for the watershed to complete the estimated baseline sediment loading. The City of Albuquerque and SSCAFCA also cooperated on this watershed wide strategy.</li> <li>• Related to requirement (c), AMAFCA will continue to maintain a cumulative list of AMAFCA's retrofit BMPs. AMAFCA will incorporate documentation by reference into the Annual Report and plans to document progress on the AMAFCA website.</li> <li>• Related to requirement (d) AMAFCA's Project Schedule process may be utilized in part for identifying, ranking, and planning area BMPs to meet recommendations from this program evaluation.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• The submission of the "Progress Evaluation Report for the Sediment Pollutant Load Reduction Strategy" report, June 25, 2019, with the FY 2019 Annual Report completes and meets the MS4 Permit requirements. Moving forward, future activities (planned, as well as implemented) determined to be needed to achieve improved sediment load reduction will be summarized in the Annual Reports. In FY 2023, there were no updates to report.</li> <li>• A cumulative list of AMAFCA's retrofit BMPs is available in upon request.</li> <li>• Related to requirement (c), the program elements above describe AMAFCA's methods for evaluation of pollutant source reduction effects.</li> <li>• Related to requirement (d), AMAFCA utilized the 2022 AMAFCA Project Schedule to focus on project priority BMPs for the community.</li> </ul>
Not Included in NOI	49	<p>Part I.C.3.b.(vi) - Critical Habitat: Verify that the installation of stormwater BMPs will not occur in or adversely affect currently listed endangered or threatened species critical habitat by reviewing the activities and locations of stormwater BMP installation within the location of critical habitat of currently listed endangered or threatened species at the FWS website <a href="http://criticalhabitat.fws.gov/crithab/">http://criticalhabitat.fws.gov/crithab/</a>.</p>	<p>Part I.C.3.b.(vi) - AMAFCA considers critical habitat for all of its projects, working closely with the USFWS and USACE, as required, and will continue this practice related to any BMPs installed related to sediment capture and removal.</p>	<ul style="list-style-type: none"> <li>• AMAFCA will continue its practice of coordination with the USFWS and USACE, as required, related to AMAFCA's facility construction projects.</li> </ul>	<p><b>Met FY 2023 Goal.</b></p> <ul style="list-style-type: none"> <li>• In FY 2023, USACE provided a letter releasing AMAFCA from any further revegetation monitoring requirements at the NDC outfall related to the special conditions of the USACE Regional General Permit. USACE determined that the site has met the revegetation performance goals. AMAFCA received notification from USACE in FY 2023 documenting that the Special Conditions of the Regional General Permit relative to vegetation monitoring had been fully satisfied and monitoring was no longer required at the NDC Outfall.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
	50	<b>Part I.D.5 - Stormwater Management Plan (SWMP) Control Measures</b>			
	51	<b>TABLE 2: Construction Site Stormwater Runoff Control - Part I.D.5.a</b>			
See NOI Sections Below	52	<p><u>Part I.D.5.a.(i)</u> The permittee shall develop, revise, implement, and enforce a program to reduce pollutants in any stormwater runoff to the MS4 from construction activities that result in a land disturbance of greater than or equal to one acre. Reduction of stormwater discharges from construction activity disturbing less than one acre must be included in the program if that construction activity is part of a larger common plan of development or sale that would disturb one acre or more. Permittees previously covered under permit NMS000101 or NMR040000 must continue existing programs, updating as necessary, to comply with the requirements of this permit. (Note: Highway Departments and Flood Control Authorities may only apply the construction site stormwater management program to the permittee's own construction projects).</p>	<p><u>Part I.D.5.a.(i)</u> - AMAFCA does not have jurisdiction over COA or Bernalillo County departments responsible for planning, review, permitting, or approval of public and private construction activities. However, AMAFCA does have jurisdiction over AMAFCA construction projects. Therefore, AMAFCA's Construction Site Stormwater Runoff Control Program addresses stormwater management during construction of AMAFCA projects that result in a land disturbance of greater than or equal to one acre, specifically when the construction contract is under.</p>	<ul style="list-style-type: none"> <li>Coordinate the Construction Site Stormwater Runoff Control Program requirements (as detailed in the Program and in sections below) for qualifying AMAFCA construction projects, as required under the Construction General Permit (CGP).</li> </ul>	<p><b>Met FY 2023 Goal.</b></p> <ul style="list-style-type: none"> <li>AMAFCA construction projects and activities were discussed at staff meetings and at monthly AMAFCA Board meetings, allowing coordination among AMAFCA staff to ensure that the MS4 program controls are followed for active and upcoming qualifying AMAFCA construction projects.</li> <li>AMAFCA continued to follow its Construction Site Stormwater Runoff Control Program.</li> </ul>
1.1	53	<p>Development of an ordinance or other regulatory mechanism as required in <u>Part I.D.5.a.(ii)(a)</u>.</p>	<p><u>Part I.D.5.a.(ii)(a)</u> - To the extent permitted by law, AMAFCA will comply with the requirements of this section. As applicable, AMAFCA will begin inserting MS4 Permit elements into construction contracts to provide AMAFCA with an enforceable contract mechanism. AMAFCA will also continue to work with the cooperative MS4 Technical Advisory Group (TAG) and other agencies to discuss and help develop regulatory mechanisms. Except for special circumstances, AMAFCA's regular maintenance activities do not disturb more than 5 acres at a time.</p>	<ul style="list-style-type: none"> <li>AMAFCA will begin inserting MS4 Permit elements into construction contracts to provide AMAFCA with an improved enforceable contract mechanism.</li> <li>AMAFCA will continue to work with the MS4 TAG and other agencies to discuss and help develop regulatory mechanisms.</li> <li>Except for special circumstances, AMAFCA's regular maintenance activities will not disturb more than 5 acres at a time.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>AMAFCA contractually requires NPDES compliance with the CGP for qualifying projects, which are construction sites greater than one (1) acre in size located on AMAFCA property for which AMAFCA holds the construction contract.</li> <li>AMAFCA continued to be involved in the MS4 TAG, facilitating cooperation and coordination with other MS4s in the Middle Rio Grande.</li> <li>In FY 2023, AMAFCA staff did not report any regular maintenance activities that disturbed more than five (5) acres at a time.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
1.2	54	<p>Develop requirements and procedures as required in Part I.D.5.a.(ii)(b) through Part I.D.5.a.(ii)(h). These Permit sections include requirements for AMAFCA to implement and enforce requirements for construction site operators to:</p> <p><u>Part I.D.5.a.(ii)(b)</u> - implement appropriate erosion and sediment control BMPs;  <u>Part I.D.5.a.(ii)(c)</u> - control waste at the construction site that may cause adverse impacts to water quality;  <u>Part I.D.5.a.(ii)(d)</u> - Procedures for site plan review which incorporate consideration of potential water quality impacts;  <u>Part I.D.5.a.(ii)(e)</u> - Procedures for receipt and consideration of information submitted by the public;  <u>Part I.D.5.a.(ii)(f)</u> - Procedures for site inspection (during construction) and enforcement of control measures, including provisions to ensure proper construction, operation, maintenance, and repair.</p>	<p><u>Part I.D.5.a.(ii)(b)</u> - As part of AMAFCA's Program, AMAFCA engineers will continue to review all site plans and the SWPPPs to ensure implementation of appropriate BMPs and consistency with federal, state, and local sediment and erosion control requirements for AMAFCA projects. Pre-construction meetings will be held prior to beginning construction and SWPPP BMPs will be reviewed and discussed.</p> <p><u>Part I.D.5.a.(ii)(c)</u> - AMAFCA ensures control of waste at construction sites during the SWPPP review, in accordance with the MS4 and CGP requirements.</p> <p><u>Part I.D.5.a.(ii)(d)</u> - In a cooperative effort with COA and Bernalillo County, AMAFCA reviews private development that has a connection to AMAFCA facilities for projects disturbing at least one (1) acre. This review includes stormwater conveyance, water quality, and erosion control. In addition, AMAFCA staff performs and will continue to perform incremental reviews of all AMAFCA projects during design to assure quality control and design efficiency.</p> <p><u>Part I.D.5.a.(ii)(e)</u> - AMAFCA will post a contact phone number at all required construction sites to ensure the public can contact AMAFCA with information.</p> <p><u>Part I.D.5.a.(ii)(f)</u> - AMAFCA has procedures for construction site inspections of control measures to ensure compliance with the Construction General Permit (CGP). AMAFCA also has procedures in place to ensure site stabilization after NOT is filed.</p>	<ul style="list-style-type: none"> <li>Review site plans and the SWPPPs (using the EPA SWPPP checklist) for AMAFCA projects disturbing at least one (1) acre in order to consider potential water quality impacts and ensure consistency with federal, state, and local sediment and erosion control requirements.</li> <li>Conduct pre-construction meetings on AMAFCA construction projects disturbing at least one (1) acre prior to beginning earth-disturbing activities in order to discuss the SWPPP and BMPs.</li> <li>SWPPP review will include ensuring the plans addresses control of waste at construction sites for AMAFCA projects.</li> <li>In a cooperative effort with COA and Bernalillo County, AMAFCA will review submitted private development that has a connection to AMAFCA facilities for projects disturbing at least one (1) acre. Review may include stormwater conveyance, water quality, and erosion control.</li> <li>AMAFCA will post a contact phone number at all required construction sites.</li> <li>AMAFCA will continue to utilize construction inspection procedures for control measures to ensure compliance with the Construction General Permit (CGP).</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>AMAFCA continued to follow its Construction Site Stormwater Runoff Control Program.</li> <li>AMAFCA reviewed 100% of the AMAFCA project SWPPPs using the most recent EPA CGP SWPPP checklist/template to guide the reviews. NOIs were submitted for 100% of the FY 2023 CGP qualifying AMAFCA projects.</li> <li>AMAFCA conducted pre-construction meetings for all qualifying AMAFCA construction projects prior to beginning earth-disturbing activities.</li> <li>AMAFCA's SWPPP reviews included ensuring the plan addresses control of waste at construction sites.</li> <li>AMAFCA reviewed private development that had a connection to AMAFCA facilities for projects disturbing at least one (1) acre. Review included stormwater conveyance, water quality, and erosion control.</li> <li>AMAFCA verified that the Contractors posted an AMAFCA contact phone number, as required, at AMAFCA construction sites.</li> <li>AMAFCA continued to utilize construction inspection procedures for control measures to ensure compliance with the CGP.</li> </ul>
	55	<p>Continued...Develop requirements and procedures as required in Part I.D.5.a.(ii)(b) through Part I.D.5.a.(ii)(h).</p> <p><u>Part I.D.5.a.(ii)(g)</u> - to educate and train permittee personnel and developers, construction site operators, contractors and supporting personnel; and</p> <p><u>Part I.D.5.a.(ii)(h)</u> - for keeping records of and tracking all regulated construction activities within the MS4 - site reviews, inspections, inspection reports, warning letters and other enforcement documents. A summary of the number and frequency of site reviews, inspections (including inspector's checklist for oversight of sediment and erosion controls and proper disposal of construction wastes) and enforcement activities that are conducted annually and cumulatively during the permit term shall be included in each Annual Report</p>	<p><u>Part I.D.5.a.(ii)(g)</u> - AMAFCA will provide MS4 construction site inspection training for its staff and invite other agencies to attend trainings, when possible. In addition, construction site SWPPPs will continue to be discussed regularly by AMAFCA personnel.</p> <p><u>Part I.D.5.a.(ii)(h)</u> - AMAFCA will maintain records of all AMAFCA-led projects disturbing at least one (1) acre within its rights-of-way. This will include AMAFCA's Construction Site Stormwater Runoff Control Program records, including NOIs, NOI tracking, inspection reports, non-conformance documents, and training documents. AMAFCA's license agreements relative to CGP compliance for non-AMAFCA projects that occur within its rights-of-way are the responsibility of the licensee.</p>	<ul style="list-style-type: none"> <li>AMAFCA will continue to provide MS4 construction site inspection training for its staff and invite other agencies responsible for construction projects. In addition, construction site SWPPPs will continue to be discussed at weekly staff meetings, included in daily reports by field personnel, and discussed at AMAFCA Board meetings.</li> <li>AMAFCA will maintain records of all construction projects disturbing at least one (1) acre within its rights-of-way that do not qualify for a Low Erosivity Waiver (LEW).</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>AMAFCA continued to maintain all construction project records disturbing at least one (1) acre within its rights-of-way.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
1.3	56	<p><u>Part I.D.5.a.(iii)</u>. Annually conduct site inspections of 100 percent of all construction projects cumulatively disturbing one (1) or more acres as required in Part I.D.5.a.(iii).</p>	<p><u>Part I.D.5.a.(iii)</u> - As part of AMAFCA's Program, AMAFCA staff will continue to perform field inspections of AMAFCA construction projects which disturb at least one (1) acre. At a minimum, each project will be inspected once after filing the NOI (including follow-up inspections for any nonconformances) and at the NOT. An inspection form has been developed and will be used for all inspections. Should the contractor fail to operate, maintain and repair the BMPs and control measures, AMAFCA staff have the contractual authority to temporarily suspend work, withhold/stop payment, or terminate the contract should such issues go uncorrected. AMAFCA's license agreements for non-AMAFCA projects that occur within its rights-of-way are not inspected by AMAFCA and are the responsibility of the licensee. As AMAFCA partners with other MS4s, such as COA, UNM, or ExpoNM on construction projects, AMAFCA will continue to coordinate with those cooperating MS4s in order to assign responsibility of conducting site inspections.</p>	<ul style="list-style-type: none"> <li>• AMAFCA will complete the inspections per the Construction Site Stormwater Runoff Control Program Plan for 100% of the active construction sites under contract by AMAFCA which disturb at least one (1) acre.</li> <li>• AMAFCA will maintain copies of the completed MS4 construction inspection forms.</li> <li>• AMAFCA will continue membership and involvement in the cooperative MS4 TAG, which will facilitate cooperation and coordination with other MS4s in the Middle Rio Grande.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• For qualifying projects - construction sites greater than one (1) acre in size for which AMAFCA holds the construction contract - AMAFCA conducted site inspections for 100% of the projects in accordance with this MS4 Permit in FY 2023. In FY 2023, there was no need to suspend work.</li> <li>• AMAFCA continued to track all AMAFCA projects disturbing at least one (1) acre, including the NOI and NOT filing and MS4 inspections.</li> <li>• AMAFCA maintains copies of all MS4 construction inspection forms.</li> <li>• AMAFCA continued to be involved in the MS4 TAG, facilitating cooperation and coordination with other MS4s in the Middle Rio Grande.</li> </ul>
1.4	57	<p><u>Part I.D.5.a.(iv)</u>. Coordinate with all departments and boards with jurisdiction over the planning, review, permitting, or approval of public and private construction projects/activities within the permit area as required in Part I.D.5.a.(iv). Planning documents include, but are not limited to: comprehensive or master plans, subdivision ordinances, general land use plan, zoning code, transportation master plan, specific area plans, such as sector plan, site area plans, corridor plans, or unified development ordinances.</p>	<p><u>Part I.D.5.a.(iv)</u> - AMAFCA does not have jurisdiction over the planning, review, permitting, or approval of non-AMAFCA public and private construction activities. Therefore, AMAFCA's program is limited to AMAFCA-owned properties. Regular coordination among AMAFCA staff, as well as with Board members, occurs and will continue.</p> <p>In a cooperative effort with COA and Bernalillo County, AMAFCA will continue to coordinate with and to review public and private development that has a connection to AMAFCA facilities for projects disturbing at least one (1) acre.</p>	<ul style="list-style-type: none"> <li>• AMAFCA will continue regular coordination amongst AMAFCA engineering staff and Board members to verify that BMPs are in place to control erosion during construction on AMAFCA-owned properties.</li> <li>• AMAFCA will continue to meet monthly with the Board and will continue to seek Board approval for jointly funded water quality projects.</li> <li>• In a cooperative effort with COA and Bernalillo County, AMAFCA reviews submitted public and private development that has a connection to AMAFCA facilities for projects disturbing at least one (1) acre. These reviews may include stormwater conveyance, water quality, and erosion control.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• AMAFCA construction projects and activities were discussed weekly in the AMAFCA staff meeting.</li> <li>• AMAFCA Board meetings typically occurred monthly during this reporting period. Board agendas and meeting minutes are available online: <a href="https://amafca.org/amafca-board-of-directors/">https://amafca.org/amafca-board-of-directors/</a></li> <li>• In addition, AMAFCA reviewed all public and private development that has a connection to AMAFCA facilities. These reviews included stormwater conveyance, water quality, and erosion control considerations.</li> </ul>
1.5	58	<p>Evaluation of GI/LID/Sustainable practices in site plan reviews as required in <u>Part I.D.5.a.(v)</u>. The site plan review must include an evaluation of opportunities for use of GI/LID/ Sustainable practices and when the opportunity exists, encourage project proponents to incorporate such practices into the site design to mimic the pre-development hydrology of the previously undeveloped site. For purposes of this permit, pre-development hydrology shall be met according to Part I.D.5.b of this Permit (consistent with any limitations on that capture). Include a reporting requirement of the number of plans that had opportunities to implement these practices and how many incorporated these practices.</p>	<p><u>Part I.D.5.a.(v)</u> - AMAFCA does not have jurisdiction over site plan reviews of public and private construction activities, and AMAFCA does not program any private development type projects. AMAFCA ultimately has no authority to accept or reject public and private development projects.</p> <p>AMAFCA will continue to encourage use of sustainable practices during the review phase of projects within AMAFCA's rights-of-way and turn-key projects that AMAFCA will take over for operation and maintenance after construction. AMAFCA will encourage an evaluation of sustainable GI/LID practice opportunities within the watershed.</p> <p>The reporting requirement for the number of plans that AMAFCA reviews, typically because of a connection to an AMAFCA facility, that had opportunities to implement these practices will be reported annually. Because of lack of jurisdictional authority, AMAFCA is typically not told how many improvements were implemented. Therefore the number of improvements implemented will not be reported in the AMAFCA MS4 Annual Report.</p>	<ul style="list-style-type: none"> <li>• AMAFCA will continue to encourage use of sustainable practices during the review phase of projects.</li> <li>• AMAFCA will annually report the number of plans that were reviewed within AMAFCA's rights-of-way and turn-key projects that AMAFCA will take over for operation and maintenance after construction that had opportunities to implement GI/LID/Sustainable practices.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• AMAFCA continued to encourage use of sustainable practices during the review phase of projects.</li> <li>• AMAFCA's Development Review Engineer reviewed private development that has a connection to AMAFCA facilities. In FY 2023, 198 plans were reviewed by the AMAFCA Development Review Engineer; opportunities to potentially implement GI/LID/ Sustainable practices were considered, as appropriate, during these reviews. A copy of the Development Review Engineer's tracking list is available upon request.</li> <li>• AMAFCA continued to collaborate with Ciudad Soil and Water Conservation District to assist with water quality focused subdivision plan reviews, which are required for developments greater than five (5) acres.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
Not Included in NOI	59	Update the SWMP document and annual report as required in Part I.D.5.a.(vi) and in Part I.D.5.a.(vii). <u>Part I.D.5.a.(vi)</u> The permittee must include in the SWMP a description of the mechanism(s) that will be utilized to comply with each of the elements required in Part I.D.5.a.(i) throughout Part I.D.5.a.(v), including description of each individual BMP (both structural or non-structural) or source control measures and its corresponding measurable goal.	<u>Part I.D.5.a.(vi)</u> - The above sections of the SWMP describe the mechanism(s) AMAFCA utilizes to comply with each of the elements required in Part I.D.5.a.(i) throughout Part I.D.5.a.(v) and the corresponding measurable goal(s). AMAFCA will annually evaluate and revise the Construction Site Stormwater Runoff Control Program elements, as necessary, to ensure that AMAFCA's Program meets the MS4 Permit requirements.	<ul style="list-style-type: none"> <li>Evaluate and revise the Construction Site Stormwater Runoff Control Program, as necessary, to ensure that AMAFCA's Program meets the MS4 Permit requirements.</li> <li>Update the SWMP, as necessary.</li> </ul>	<p><b>Met FY 2023 Goal.</b></p> <ul style="list-style-type: none"> <li>AMAFCA's Program was reviewed by the Storm Water Quality Engineer for this reporting period. The program was reviewed as part of this Annual Report.</li> </ul>
Not Included in NOI	60	Update the SWMP document and annual report as required in Part I.D.5.a.(vi) and in Part I.D.5.a.(vii). <u>Part I.D.5.a.(vii)</u> - The permittee shall assess the overall success of the program, and document the program effectiveness in the Annual Report. The permittee must include in each Annual Report: <u>Part I.D.5.a.(vii).(a)</u> - A summary of the frequency of site reviews, inspections and enforcement activities that are conducted annually and cumulatively during the permit term. <u>Part I.D.5.a.(vii).(b)</u> - The number of plans that had the opportunity to implement GI/LID/Sustainable practices and how many incorporated the practices.	<p><u>Part I.D.5.a.(vii)</u> - AMAFCA will assess the overall success of the program, and document the program effectiveness in the Annual Report.</p> <p><u>Part I.D.5.a.(vii).(a)</u> - AMAFCA will include in each Annual Report a summary of the number and frequency of site reviews and inspections activities that are conducted annually and cumulatively during the permit term.</p> <p><u>Part I.D.5.a.(vii).(b)</u> - AMAFCA will include the number of plans that had the opportunity to implement GI/LID/Sustainable practices from the plans that were reviewed within AMAFCA's rights-of-way and turn-key projects that AMAFCA will take over for operation and maintenance after construction. AMAFCA ultimately lacks jurisdictional authority to accept public and private development projects.</p>	<ul style="list-style-type: none"> <li>Included in each Annual Report will be a summary of the number and frequency of construction site reviews and inspection activities that are conducted annually and cumulatively during the Permit term.</li> <li>Included in each Annual Report will be a summary of the plans that had the opportunity to implement GI/LID/Sustainable practices from the plans that were reviewed within AMAFCA's rights-of-way and turn-key projects that AMAFCA will take over for operation and maintenance after construction. This documentation is included above.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>This Annual Report documents the program effectiveness and program success in the status of implementation and performance assessment for each MS4 Permit requirements.</li> <li>There were 5 active AMAFCA construction projects in FY 2023.</li> <li>The number of plans reviewed by the AMAFCA Development Review Engineer is reported above; opportunities to potentially implement GI/LID/ Sustainable practices were considered, as appropriate, during these reviews.</li> </ul>
1.6	61	Enhance the program to include the elements in Part I.D.5.a.(viii) through Part I.D.5.a.(x). These include: <u>Part I.D.5.a.(viii)</u> - Use of stormwater educational materials; <u>Part I.D.5.a.(ix)</u> - Develop or update existing construction handbooks; and <u>Part I.D.5.a.(x)</u> - construction inspections may be carried out in conjunction with other inspections and use a screening prioritization process.	<p><u>Part I.D.5.a.(viii)</u> - AMAFCA will continue to use stormwater educational materials, either developed locally or provided by EPA, NMED, environmental groups, public interest groups, trade organizations, and/or other MS4s. AMAFCA will continue to host training cooperative sessions with the watershed MS4s.</p> <p><u>Part I.D.5.a.(ix)</u> - AMAFCA, along with other MS4s, provided external review to NMDOT on their 2020 update of the National Pollutant Discharge Elimination System Manual, Stormwater Management Guidelines for Construction, MS4 and Industrial Activities.</p> <p><u>Part I.D.5.a.(x)</u> - AMAFCA will continue to incorporate a screening prioritization process for construction inspections relative to regular operational inspections.</p>	<ul style="list-style-type: none"> <li>The MRGSQT Outcomes Report will summarize the activities where educational materials were dispersed and shared with the public. This report is available upon request and AMAFCA plans to share this document on its website.</li> <li>AMAFCA will explore opportunities for training cooperative sessions held with the watershed MS4s during the reporting period.</li> <li>AMAFCA will follow procedures, as applicable, outlined in the 2020 update of the National Pollutant Discharge Elimination System Manual, Stormwater Management Guidelines for Construction, MS4 and Industrial Activities.</li> <li>AMAFCA will continue to incorporate a screening prioritization process for construction inspections relative to regular operational inspections.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>AMAFCA's educational efforts are summarized and included in the MRGSQT Outcomes Report. This is attached to this Annual Report.</li> <li>AMAFCA continued to utilize the most recent EPA CGP SWPPP checklist/template to guide the reviews of SWPPP documents.</li> <li>AMAFCA conducted site inspections for 100% of the AMAFCA construction projects in accordance with this MS4 Permit in FY 2023.</li> </ul>
1.7	62	Item from MS4 Permit NOI. Describe other proposed activities to address the Construction Stormwater Management in New Development and Redevelopment Measure.	AMAFCA will continue to utilize the Annual Report and SWMP revision process as a means to perform a self-audit with the goal to improve its MS4 Programs.	AMAFCA will document progress made, if any, related to the Annual Report and SWMP revision process as a means to perform a self-audit on the MS4 Program elements.	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>AMAFCA continued to utilize the Annual Report process as a means to perform a self-audit on the MS4 Program elements.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
	63	<b>TABLE 3: Post-Construction Stormwater Management in New Development and Redevelopment- Part I.D.5.b</b>			
See NOI Sections Below	64	Part I.D.5.b.(i) The permittee must develop, revise, implement, and enforce a program to address stormwater runoff from new development and redevelopment projects that disturb greater than or equal to one acre, including projects less than one acre that are part of a larger common plan of development or sale, that discharge into the MS4. The program must ensure that controls are in place that would prevent or minimize water quality impacts. Permittees previously covered under NMS000101 or NMR040000 must continue existing programs, updating as necessary, to comply with the requirements of this permit. (Note: Highway Departments and Flood Control Authorities may only apply the post-construction stormwater management program to the permittee's own construction projects).	Part I.D.5.b.(i) - All AMAFCA projects are regional flood control or water quality projects. AMAFCA does not have jurisdiction over private or public (non-AMAFCA) development or redevelopment projects - this responsibility lies with COA, NMDOT, or Bernalillo County. AMAFCA facilities receive stormwater after it flows through new development and redevelopment. As a result, some permit activities in this section do not apply to AMAFCA.  AMAFCA's routine operation & maintenance (O&M) activities address post-construction stormwater management at all AMAFCA facilities.	• Coordinate O&M activities at AMAFCA's weekly staff meetings.	<b>Met FY 2023 Goal.</b> •AMAFCO O&M activities continued to be discussed and coordinated weekly in the AMAFCA staff meeting.
2.1	65	Development of strategies as required in Part I.D.5.b.(ii).(a). Strategies which include a combination of structural and/or non-structural BMPs to control pollutants in stormwater runoff.	Part I.D.5.b.(ii).(a) - All AMAFCA projects are regional flood control or stormwater quality projects - functioning as BMPs. AMAFCA will continue to include both structural and non-structural BMPs to control pollutants in stormwater runoff from AMAFCA owned facilities.  AMAFCA may continue to coordinate with watershed MS4s and other entities within its jurisdiction to discuss areas requiring drainage and water quality improvements, project priorities, and multi-agency funding opportunities. As part of the development of the AMAFCA Project Schedule, a system review will be completed. AMAFCA will publish projects, including schedule and cost sharing, in the AMAFCA Project Schedule.  AMAFCA will continue development of this program element in its MS4 Strategies and Procedures Notebook for this Program.	• AMAFCA will continue to include both structural and non-structural BMPs to control pollutants in stormwater runoff from AMAFCA owned facilities. • AMAFCA may coordinate with watershed MS4s as well as other entities within its jurisdiction during project review, complete a system review, and publish projects, including schedule and cost sharing, in the AMAFCA Project Schedule.	<b>Met FY 2023 Goals.</b> • AMAFCA continued to include both structural and non-structural BMPs to control pollutants in stormwater runoff from AMAFCA owned facilities. In addition, several structural BMPs have been constructed under the Agency and Area-Wide (A&AW) contract and Miscellaneous contract maintenance activities during the Permit term. A complete list of A&AW by FY can be provided upon request. • AMAFCA continued to work with the watershed MS4s, cooperative MS4 TAG, and other agencies to discuss and help develop strategies, where feasible, to contractually require and/or suggest BMPs on projects that AMAFCA may take over for operation and maintenance after construction. • In FY 2023, AMAFCA worked on the 2024 Project Schedule which covers a six-year planning horizon (2024-2029). The 2024 Project schedule will be finalized in 2024. Coordination meetings with watershed MS4s, TAG members, and other entities occurred during the development of this Project Schedule and included the ranking of stormwater quality projects. • In FY 2023, the MRGSQT members continued discussions and agency implementation related to the Post-Construction Stormwater Quality Design Standards in the Middle Rio Grande Watershed study.
2.2	66	Development of an ordinance or other regulatory mechanism as required in Part I.D.5.b.(ii).(b).	Part I.D.5.b.(ii).(b) - It is not within AMAFCA's jurisdiction to enact ordinances or other legal authority mechanisms. AMAFCA is unable to develop, implement, or enforce any ordinances or regulatory mechanisms required in this section.	• AMAFCA will continue to work with the cooperative MS4 TAG and other agencies to discuss and help develop regulatory mechanisms.	<b>Met FY 2023 Goal.</b> • AMAFCA continued to be involved in the MS4 TAG, facilitating cooperation and coordination with other MS4s in the Middle Rio Grande.
2.3	67	Implementation and enforcement, via the ordinance or other regulatory mechanism of site design standards as required in Part I.D.5.b.(ii).(b).	Part I.D.5.b.(ii).(b) - It is not within AMAFCA's jurisdiction to enact ordinances or other legal authority mechanisms. AMAFCA is unable to develop, implement, or enforce any ordinances or regulatory mechanisms required in this section.	• AMAFCA will continue to work with the cooperative MS4 TAG and other agencies to discuss and help develop regulatory mechanisms.	<b>Met FY 2023 Goal.</b> • AMAFCA continued to work with the MS4 TAG and other agencies to discuss and help develop strategies, where feasible, to contractually require post-construction BMPs on projects that AMAFCA will take over for operation and maintenance after construction.



NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
2.4	68	Ensure appropriate implementation of post-construction structural controls as required in <a href="#">Part 1.D.5.b.(ii).(c)</a> and <a href="#">Part 1.D.5.b.(ii).(d)</a> .	<p><a href="#">Part 1.D.5.b.(ii).(c)</a> - AMAFCA will continue to ensure the appropriate implementation of structural BMPs on AMAFCA owned projects through pre-construction design review (see Construction Site Stormwater Runoff Control Measure). For watershed cooperative elements, AMAFCA occasionally partners with other MS4s, such as the COA, UNM, and ExpoNM, on construction of structural BMPs. AMAFCA is also a member of the MS4 TAG.</p> <p><a href="#">Part 1.D.5.b.(ii).(d)</a> - AMAFCA will conduct inspections at the beginning and end of construction, (see Construction Site Stormwater Runoff Control Measure), conduct Post-Construction inspection and maintenance (AMAFCA's routine O&amp;M activities address post-construction stormwater management), and enforce contractual penalty provisions for noncompliance by the Operator during construction.</p>	<ul style="list-style-type: none"> <li>• AMAFCA will ensure the appropriate implementation of structural BMPs on AMAFCA owned projects through pre-construction design review (see Construction Site Stormwater Runoff Control Measure).</li> <li>• AMAFCA will continue to work with the watershed MS4s, TAG, and other agencies to discuss cooperative implementation of structural BMPs.</li> <li>• AMAFCA will conduct inspections as required during construction, (see Construction Site Stormwater Runoff Control Measure).</li> <li>• AMAFCA's Post-Construction inspections and maintenance will be through the AMAFCA O&amp;M activities (see Pollution Prevention /Good Housekeeping Control Measure).</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• See the Construction Site Stormwater Runoff Control Measure for pre-construction design review and inspections during construction.</li> <li>• AMAFCA continued to be involved in the MS4 TAG, facilitating cooperation and coordination with other MS4s in the Middle Rio Grande.</li> <li>• See the Pollution Prevention/Good Housekeeping Control Measure for post-construction inspections and maintenance, which are part of AMAFCA O&amp;M activities. These inspections and maintenance continued to be discussed in the AMAFCA staff meetings.</li> <li>• In FY 2023, the MRGSQT members continued discussions and agency implementation related to the Post-Construction Stormwater Quality Design Standards in the Middle Rio Grande Watershed study.</li> </ul>
2.5	69	<p>Develop procedures as required in <a href="#">Part 1.D.5.b.(ii).(e)</a>. Procedure to develop and implement an educational program for project developers regarding designs to control water quality effects from stormwater, and a training program for plan review staff regarding stormwater standards, site design techniques and controls, including training regarding GI/LID/ Sustainability practices. Training may be developed independently or obtained from outside resources;</p> <p><a href="#">Part 1.D.5.b.(ii).(f)</a> - Procedures for site inspection and enforcement to ensure proper long-term operation, maintenance, and repair of storm water management practices that are put into place as part of construction projects/activities;</p> <p><a href="#">Part 1.D.5.b.(ii).(g)</a> - Procedures to control the discharge of pollutants related to commercial application and distribution of pesticides, herbicides, and fertilizers; and</p> <p><a href="#">Part 1.D.5.b.(ii).(h)</a> - Procedure or system to review and update, as necessary, the existing program to ensure that storm water controls or management practices for new development and redevelopment projects/ activities continue to meet the requirements and objectives of the</p>	<p><a href="#">Part 1.D.5.b.(ii).(e)</a> - As a cooperative program, AMAFCA contributes to the Mid Rio Grande Stormwater Quality Team (MRGSQT), which includes training on GI/LID and sustainability practices. This is achieved by sponsoring conferences featuring GI/LID lectures, such as the annual Land and Water Summit. Reporting on the MRGSQT activities will be part of Public Education and Outreach on Stormwater Impacts Control Measure.</p> <p><a href="#">Part 1.D.5.b.(ii).(f)</a> - AMAFCA is responsible for all long term inspection, operation, maintenance, and repair of its own facilities. AMAFCA will perform inspections, maintenance and repair in accordance with the established procedures in the "AMAFCA O&amp;M Manual for Dams", the "AMAFCA O&amp;M Repair Replacement and Rehabilitation Manual", and Project O&amp;M Plan (Plan No. 7). This is covered in the Pollution Prevention/Good Housekeeping Control Measure.</p> <p><a href="#">Part 1.D.5.b.(ii).(g)</a> - AMAFCA will only allow licensed staff or professionally licensed contractors to apply herbicides and pesticides within AMAFCA rights-of-way (AMAFCA does not apply fertilizers in its operations). This is covered in the Pollution Prevention/Good Housekeeping Control Measure.</p> <p><a href="#">Part 1.D.5.b.(ii).(h)</a> - AMAFCA's routine O&amp;M activities address post-construction stormwater management at all AMAFCA facilities.</p>	<ul style="list-style-type: none"> <li>• As a cooperative program, AMAFCA contributes to the MRGSQT. AMAFCA's educational efforts are included in the MRGSQT Outcomes Report which will summarize, if applicable, the activities where educational materials were dispersed and shared with project developers. This report is available upon request and.</li> <li>• AMAFCA will provide MS4 training for its staff and invite other agencies responsible for construction projects. AMAFCA may participate in other agencies' MS4 trainings.</li> <li>• AMAFCA's Post-Construction inspections and maintenance are conducted following the AMAFCA O&amp;M procedures (see Pollution Prevention /Good Housekeeping Control Measure).</li> <li>• AMAFCA will only allow licensed staff or professionally licensed contractors to apply herbicides and pesticides within AMAFCA rights-of-way (AMAFCA does not apply fertilizers in its operations).</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• AMAFCA only allows certified staff or professionally licensed contractors to apply herbicides and pesticides within AMAFCA right-of-way. This is also discussed in Pollution Prevention/Good Housekeeping and Public Education and Outreach Control Measures of this Annual Report.</li> </ul>
2.6	70	Coordinate internally with all departments and boards with jurisdiction over the planning, review, permitting, or approval of public and private construction projects/ activities within the permit area as required in <a href="#">Part 1.D.5.b.(iii)</a> related to developed hydrology mimicking pre-development hydrology.	<p><a href="#">Part 1.D.5.b.(iii)</a> - AMAFCA does not have any internal departments or boards with jurisdiction. AMAFCA will coordinate with all entities as necessary. AMAFCA will coordinate internally and, to the extent possible and applicable, design AMAFCA facilities for compliance with developed hydrology mimicking pre-development hydrology. For AMAFCA led DMPs, Sediment Studies, Facility Plans, and WQ studies, AMAFCA will require, to the extent possible and applicable, that developed hydrology mimic pre-development hydrology. The NM OSE regulates the water delivery to the Rio Grande in order to meet water delivery requirements to Texas; therefore, AMAFCA's objective is to design its facilities to drain within 96 hours per the OSE requirements.</p>	<ul style="list-style-type: none"> <li>• AMAFCA will coordinate internally on studies and projects for MS4 Permit compliance with developed hydrology mimicking pre-development hydrology. AMAFCA will abide by the NM OSE rule and plan/design its facilities to drain within 96 hours per the OSE requirements.</li> <li>• AMAFCA will continue to follow the standard practice for Drainage Master Plans (DMPs) options development and consider two options for developed condition hydrology flowrates and volumes: 1) determine pond locations and volumes required on a sub-basin by sub-basin basis to mimic pre-development hydrology and, 2) determine pond locations and volumes required on a regional approach basis to mimic pre-development hydrology.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• AMAFCA continued to coordinate internally related to developed hydrology mimicking pre-development hydrology. All active AMAFCA Drainage Management and Water Quality Plans considered the MS4 Permit stormwater quality design standard defined in Part 1.D.5.b.(ii)(b).</li> <li>• In FY 2023, the MRGSQT members continued discussions and agency implementation related to the Post-Construction Stormwater Quality Design Standards in the Middle Rio Grande Watershed study.</li> </ul>



NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
2.7	71	As required in <u>Part I.D.5.b.(iv)</u> , the permittee must assess all existing codes, ordinances, planning documents and other applicable regulations, for impediments to the use of GI/LID/Sustainable practices.	<p><u>Part I.D.5.b.(iv)</u> - AMAFCA does not have jurisdictional authority pertaining to codes, ordinances, planning documents and other applicable regulations, for impediments to the use of GI/LID/Sustainable practices.</p> <p>AMAFCA will provide information, as requested, and coordinate with other watershed MS4s for assessment of existing codes, ordinances, planning documents and other applicable regulations for impediments to the use of GI/LID/Sustainable practices.</p> <p>The NM OSE regulates the water delivery to the Rio Grande in order to meet water delivery requirements to Texas; therefore, AMAFCA's objective is to design its facilities to drain within 96 hours per the OSE requirements.</p>	<ul style="list-style-type: none"> <li>AMAFCA will provide information, as requested, and coordinate and cooperate with other watershed MS4s for the assessment of existing codes, ordinances, planning documents, and other applicable regulations for impediments to the use of GI/LID/Sustainable practices.</li> </ul>	<p><b>Met FY 2023 Goal.</b></p> <ul style="list-style-type: none"> <li>This Permit activity was conducted cooperatively with Bernalillo County in FY 2018. FY 2023 continued to focus on understanding the impediments and beginning discussions to address the findings.</li> <li>AMAFCA participated as a review partner for the Bernalillo County's updated technical standards, which includes the Green Stormwater Infrastructure/Low Impact Development (GSI/LID) Standards document. During FY 2023, Bernalillo County continued the process of updating its Technical Standards. Integration of GSI/LID into the Technical Standards and review process was a key focus of this update. As a part of this update, the County developed a stand-alone GSI/LID Standards document that identifies GSI/LID best management practices (BMPs) that are arid-appropriate and support Bernalillo County's Stormwater Quality Ordinance, representing an increased commitment from the County toward the goal of broad implementation of GSI/LID in the MRG watershed.</li> </ul>
2.8	72	As required in <u>Part I.D.5.b.(iv)</u> , develop and submit a report of the assessment findings on GI/LID/Sustainable practices.	<p><u>Part I.D.5.b.(iv)</u> - AMAFCA does not have jurisdictional authority pertaining to codes, ordinances, planning documents and other applicable regulations, for impediments to the use of GI/LID/Sustainable practices. However, to the extent permitted by law, AMAFCA will comply with the requirements of this section. AMAFCA will provide information, as requested, and coordinate with other watershed MS4s for assessment of existing codes, ordinances, planning documents and other applicable regulations for impediments to the use of GI/LID/Sustainable practices.</p>	<p><b>Met Permit Requirement - Activity is Complete. No additional measurable goals.</b></p> <ul style="list-style-type: none"> <li>AMAFCA provided information, as requested, and coordinated and cooperated with other watershed MS4s for the development of a report of the assessment of finding from Part I.D.5.b.(iv). This was completed in March 2017 and was submitted to the EPA with the Annual Report, due Dec. 1, 2017.</li> </ul>	<p><b>No Goals Required for FY 2023.</b></p> <p><b>Met Permit Requirement - Activity is Complete.</b></p> <ul style="list-style-type: none"> <li>This Permit activity was conducted cooperatively with Bernalillo County in FY 2017 and this activity is complete.</li> </ul>
Not Included in NOI	73	<p>As required in <u>Part I.D.5.b.(v)</u>, Alternative compliance for infeasibility due to Site Constraints. <u>Part I.D.5.b.(v).(a)</u> - Infeasibility to manage the design standard volume specified in Part I.D.5.b.(ii).(b), or a portion of the design standard volume, onsite may result from site constraints including:</p> <p><u>A.</u> too small a lot outside of the building footprint to create the necessary infiltrative capacity even with amended soils;</p> <p><u>B.</u> soil instability as documented by a thorough geotechnical analysis;</p> <p><u>C.</u> a site use that is inconsistent with capture and reuse of storm water;</p> <p><u>D.</u> other physical conditions; or,</p> <p><u>E.</u> to comply with applicable requirements for on-site flood control structures leaves insufficient area to meet the standard.</p> <p><u>Part I.D.5.b.(v).(b)</u> - A determination that it is infeasible to manage the design standard volume specified in Part I.D.5.b.(ii).(b), or a portion of the design standard volume, on site may not be based solely on the difficulty or cost of implementing onsite control measures, but must include multiple criteria that rule out an adequate combination of the practices set forth in Part I.D.5.b.(v).</p>	<p><u>Part I.D.5.b.(v).(a) and (b)</u> - As previously mentioned, all AMAFCA projects are regional flood control or stormwater quality projects that function as BMPs, and AMAFCA does not have jurisdictional authority pertaining to new development or redevelopment activities. Therefore, AMAFCA itself will likely not have requirements for alternative compliance regarding infeasibility to manage the post construction design standard volume. However, AMAFCA's regional facilities may offer other MS4s an option for alternative compliance to manage the post-construction stormwater quality volume. The on-site stormwater management decisions and feasibility will typically be determined during development by other agencies (COA, Bernalillo County, etc.). AMAFCA will continue coordination with and support these agency decisions, as appropriate. AMAFCA's involvement will typically occur during the development review or stake-holder review.</p>	<ul style="list-style-type: none"> <li>AMAFCA will continue to coordinate with and support these agency decisions, as appropriate, related to on-site stormwater management decisions and feasibility. AMAFCA's involvement will typically occur during the development review or stake-holder review. AMAFCA's regional facilities may offer other MS4s an option for alternative compliance to manage the post-construction stormwater quality volume.</li> </ul>	<p><b>Met FY 2023 Goal.</b></p> <ul style="list-style-type: none"> <li>AMAFCA coordinated with and supported community agency decisions, as appropriate, related to on-site stormwater management decisions and feasibility. AMAFCA's involvement typically occurred during the development review or stake-holder review.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
Not Included in NOI	74	<p>Part I.D.5.b.(v) continued -</p> <p>Part I.D.5.b.(v).(c) - This permit does not prevent imposition of more stringent requirements related to flood control. Where both the permittee's site design standard ordinance or policy and local flood control requirements on site cannot be met due to site conditions, the standard may be met through a combination of on-site and off-site controls.</p> <p>Part I.D.5.b.(v).(d) - Where applicable New Mexico water law limits the ability to fully manage the design standard volume on site, measures to minimize increased discharge consistent with requirements under New Mexico water law must still be implemented.</p> <p>Part I.D.5.b.(v).(e) - In instances where an alternative to compliance with the standard on-site is chosen, technical justification as to the infeasibility of on-site management of the entire design standard volume, or a portion of the design standard volume, is required to be documented by submitting to the permittee a site-specific hydrologic and/or design analysis conducted and endorsed by a registered professional engineer, geologist, architect, and/or landscape architect.</p>	<p>Part I.D.5.b.(v).(c) - AMAFCA's primary function is to provide regional flood control; this includes stormwater quality projects that function as BMPs. Flood control requirements will continue to be required.</p> <p>Part I.D.5.b.(v).(d) - The NM ISC/OSE regulates the water delivery to the Rio Grande in order to meet water delivery requirements to Texas; therefore, AMAFCA's objective is to design its facilities to drain within 96 hours per the OSE requirements. Using AMAFCA facilities for off-site mitigation would assure the community that New Mexico water law limits are being met at the AMAFCA facilities.</p> <p>Part I.D.5.b.(v).(e) - Alternatives to compliance for on-site requirements are discussed below. AMAFCA itself will likely not have requirements for alternative compliance regarding infeasibility to manage the post construction stormwater quality volume. However, AMAFCA's regional facilities may offer other MS4s an option for alternative compliance to manage the post construction stormwater quality volume.</p>	<ul style="list-style-type: none"> <li>AMAFCA will continue its primary function is to provide regional flood control; this includes stormwater quality projects that function as BMPs. Flood control requirements will continue to be required.</li> <li>AMAFCA will abide by the NM OSE rule and plan/design its facilities to drain within 96 hours per the ISC/OSE guidance document. Using AMAFCA facilities for off-site mitigation would assure the community that New Mexico water law limits are being met at the AMAFCA facilities.</li> <li>AMAFCA's regional facilities may offer other MS4s an option for alternative compliance to manage the post construction stormwater quality volume.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>AMAFCA continued its primary function to provide regional flood control; this included stormwater quality projects that function as BMPs. Flood control requirements will continue to be required.</li> <li>AMAFCA abided by the NM ISC/OSE rule and plan/design its facilities to drain within 96 hours per the ISC/OSE requirements and guidelines.</li> <li>AMAFCA continued discussions with Middle Rio Grande MS4 permittees regarding using AMAFCA's regional facilities as an option for alternative compliance to manage the post construction stormwater quality volume.</li> </ul>
Not Included in NOI	75	<p>As required in Part I.D.5.b.(v).(f), when a Permittee determines a project applicant has demonstrated infeasibility due to site constraints specified in Part I.D.5.b.(v) to manage the design standard volume specified in Part I.D.5.b.(ii).(b) or a portion of the design standard volume on-site, the Permittee shall require one of the following mitigation options:</p> <p>A. The off-site mitigation option only applies to redevelopment sites and cannot be applied to new development. Management of the standard volume, or a portion of the volume, may be implemented at another location within the MS4 area, approved by the permittee. The permittee shall identify priority areas within the MS4 in which mitigation projects can be completed and shall determine who will be responsible for long-term maintenance on off-site mitigation projects.</p> <p>B. Implementation of a project that has been determined to provide an opportunity to replenish regional ground water supplies at an offsite location.</p> <p>C. Payment in lieu may be made to the permittee, who will apply the funds to a public storm water project. MS4s shall maintain a publicly accessible database of approved projects for which these payments may be used.</p>	<p>Part I.D.5.b.(v).(f) - AMAFCA may continue to coordinate with watershed MS4s and other entities within its jurisdiction to discuss areas requiring drainage and water quality improvements, project priorities, and multi-agency funding opportunities. Off-site stormwater quality mitigation projects will be included in these discussions. As part of the development of the AMAFCA Project Schedule, a system review will be completed. AMAFCA will publish projects, including schedule and cost sharing, in the biennial AMAFCA Project Schedule.</p> <p>AMAFCA, as part of the MS4 TAG, has discussed with EPA Region 6 (verbally and in writing) the MS4 Permit language for this section. The MS4 TAG members and EPA discussed how some of the terms/language of the Permit may limit the flexibility of the MS4s to allow off-site stormwater mitigation. The MS4s identified terms in the Permit which restrict the flexibility to achieve stormwater quality objectives by using alternate methods of compliance with post-construction permit requirements. The MS4 TAG provided this in writing to EPA on August 19, 2017 (letter from Dave Gatterman, SSCAFCA, "August 8, 2016 Meeting Follow-up"). This letter included scanned page 30 of Permit No. NMR04A000 to illustrate language changes the MS4 TAG think would allow the permittees to move forward and comply with both the Permit and state statute. Removing these limitations relative to post construction runoff will better allow the permittees flexibility to comply with New Mexico water law, protect the quality of the river, and not overly constrict development of our arid watershed. AMAFCA will continue discussions with EPA Region 6 regarding Permit language related to off-site stormwater mitigation.</p>	<ul style="list-style-type: none"> <li>AMAFCA may coordinate with watershed MS4s as well as other entities during project review, complete a system review, and publish projects, including schedule and cost sharing, in the AMAFCA Project Schedule. Off-site stormwater quality mitigation projects may be included in these discussions.</li> <li>AMAFCA will continue discussions with EPA Region 6 regarding Permit language related to off-site stormwater mitigation. Removing these Permit limitations relative to post construction runoff will better allow the permittees flexibility to comply with New Mexico water law, protect the quality of the river, and not overly constrict development of our arid watershed.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>In FY 2023, AMAFCA worked on the 2024 Project Schedule which covers a six-year planning horizon (2024-2029). The 2024 Project schedule will be finalized in 2024. Coordination meetings with watershed MS4s, TAG members, and other entities occurred during the development of this Project Schedule and included the ranking of stormwater quality projects.</li> <li>AMAFCA continued discussions with stakeholders regarding Permit language related to off-site stormwater quality mitigation. Utilizing the Permit opportunities relative to post construction runoff will better allow the permittees flexibility to comply with New Mexico water law, protect the quality of the river, and not overly constrict development of our arid watershed.</li> </ul>
2.9	76	<p>Estimation of the number of acres of IA and DCIA as required in Part I.D.5.b.(vi).</p>	<p>Part I.D.5.b.(vi) - AMAFCA will estimate the Impervious Area (IA) and Directly Connected Impervious Area (DCIA) within AMAFCA's jurisdiction and/or rights of way.</p>	<ul style="list-style-type: none"> <li>AMAFCA will estimate the IA and DCIA within AMAFCA's jurisdiction and/or rights of way. AMAFCA will update this estimate, as appropriate, given development in the watersheds. This will be a cooperative effort with other watershed MS4s.</li> </ul>	<p><b>Met FY 2023 Goal.</b></p> <ul style="list-style-type: none"> <li>This Permit activity was conducted cooperatively in FY 2023 and IA values will be updated in FY 2023 with AMAFCA projects.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
2.10	77	<p>Inventory and priority ranking as required in <a href="#">Part I.D.5.b.(vii)</a> for MS4-owned property and infrastructure (including public right-of-way) that may have the potential to be retrofitted with control measures designed to control the frequency, volume, and peak intensity of stormwater discharges to and from its MS4.</p> <p>The NM Office of the State Engineer (OSE) regulates the water delivery to the Rio Grande in order to meet water delivery requirements to Texas; therefore, AMAFCA's objective is to design its facilities to drain within 96 hours per the OSE requirements.</p>	<p><a href="#">Part I.D.5.b.(vii)</a> - AMAFCA will continue to keep an inventory and develop a priority ranking of AMAFCA owned properties and facilities that may have the potential for retrofitted control measures and stormwater quality facilities and BMPs. AMAFCA may continue to coordinate with watershed MS4s and other entities within its jurisdiction to discuss areas requiring drainage and water quality retrofits, project priorities, and multi-agency funding. AMAFCA will publish projects, including schedule and cost sharing, in the biennial AMAFCA Project Schedule. As part of the development of the AMAFCA Project Schedule, a system review will be completed. Internally, using the Project Schedule, water quality projects and water quality retrofit projects may be ranked and tabulated. AMAFCA may evaluate the existing BMPs based on their effectiveness and capacity in order to identify where additional BMPs are needed.</p> <p>AMAFCA is also a member of the cooperative MS4 TAG, facilitating cooperation and coordination with other watershed MS4s.</p> <p>AMAFCA will complete, as allowed, updated hydrologic analyses for the Rio Grande watersheds to assist with determining priority ranking.</p>	<ul style="list-style-type: none"> <li>• AMAFCA may continue to coordinate with watershed MS4s and other entities within its jurisdiction to discuss the areas requiring drainage and water quality retrofitting within the Middle Rio Grande Watershed, project priorities, and multi-agency funding contributions.</li> <li>• AMAFCA will publish the AMAFCA-funded projects, including the schedule and proposed cost-sharing, in the AMAFCA Project Schedule. As part of the development of the AMAFCA Project Schedule, a system review will be completed. AMAFCA may utilize the Project Schedule, in part, to rank and tabulate water quality projects and water quality retrofit projects.</li> <li>• AMAFCA will continue membership and involvement in the cooperative MS4 TAG which will facilitate cooperation and coordination with other MS4s in the Middle Rio Grande.</li> <li>• AMAFCA will operate and maintain Levelloggers in major channel inlets into the NDC on AMAFCA ROW and analyze the data to assist with priority ranking.</li> <li>• AMAFCA will complete updated hydrologic analyses, utilizing the AMAFCA White Paper Methodology, for the NDC watersheds, to assist with determining priority ranking.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• In FY 2023, AMAFCA worked on the 2024 Project Schedule which covers a six-year planning horizon (2024-2029). The 2024 Project schedule will be finalized in 2024. Coordination meetings with watershed MS4s, TAG members, and other entities occurred during the development of this Project Schedule and included the ranking of stormwater quality projects.</li> <li>• AMAFCA continued to operate and analyze data from 14 Levelloggers located at the channelized inlets to the NDC on AMAFCA ROW. Reports from this monitoring program are available upon request.</li> <li>• In FY 2023, AMAFCA continued working on Drainage Management Plans (DMPs) and Water Quality Plans to plan for flood protection and water quality volumes.</li> </ul>
2.11	78	<p>Incorporate watershed protection elements into regular planning or policy documents as required in <a href="#">Part I.D.5.b.(viii)</a>. As applicable to each permittee's MS4 jurisdiction, policy and/or planning documents must include the following:</p> <p><a href="#">Part I.D.5.b.(viii).(a)</a> - A description of master planning and project planning procedures to control the discharge of pollutants to and from the MS4.</p> <p><a href="#">Part I.D.5.b.(viii).(b)</a> - Minimize the amount of impervious surfaces (roads, parking lots, roofs, etc.) within each watershed, by controlling the unnecessary creation, extension and widening of impervious parking lots, roads and associated development.</p> <p><a href="#">Part I.D.5.b.(viii) (c)</a> - Identify environmentally and ecologically sensitive areas that provide water quality benefits and serve critical watershed functions within the MS4 and ensure requirements to preserve, protect, create and/or restore these areas are developed and implemented during the plan and design phases of projects in these identified areas.</p>	<p><a href="#">Part I.D.5.b.(viii).(a)</a> - AMAFCA will continue to produce and publish the AMAFCA Project Schedule for all regional drainage and water quality projects within AMAFCA's jurisdiction that will either be led or partly funded by AMAFCA. For the projects led by AMAFCA, watershed protection elements may be incorporated, when feasible, into drainage management plans, as appropriate, in order to identify watersheds which can be retrofitted with regional water quality facilities.</p> <p><a href="#">Part I.D.5.b.(viii).(b)</a> - This section is not applicable to AMAFCA's projects, which are regional flood control or water quality projects.</p> <p><a href="#">Part I.D.5.b.(viii).(c)</a> - During planning of AMAFCA projects, environmentally and ecologically sensitive areas that provide water quality benefits are considered.</p>	<ul style="list-style-type: none"> <li>• Produce and publish the AMAFCA Project Schedule.</li> <li>• AMAFCA may coordinate with MS4s to provide input for project planning of infrastructure retrofitting.</li> <li>• For projects led by AMAFCA, watershed protection elements may be incorporated into Drainage Management Plans, as appropriate, in order to identify watersheds which potentially can be retrofitted with regional water quality facilities.</li> <li>• All AMAFCA projects will obtain USFWS, USACE, and/or pueblo consultation, if required.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• In FY 2023, AMAFCA worked on the 2024 Project Schedule which covers a six-year planning horizon (2024-2029). The 2024 Project schedule will be finalized in 2024. Coordination meetings with watershed MS4s, TAG members, and other entities occurred during the development of this Project Schedule and included the ranking of stormwater quality projects.</li> <li>• In FY 2023, AMAFCA continued working on Drainage Management Plans (DMPs) and Water Quality Plans to plan for watershed flood protection and water quality volumes.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
2.11	79	<p>Continuation of incorporate watershed protection elements into regular planning or policy documents as required in Part I.D.5.b.(viii).</p> <p><u>Part I.D.5.b.(viii).(d)</u> - Implement stormwater management practices that minimize water quality impacts to streams, including disconnecting direct discharges to surface waters from impervious surfaces such as parking lots.</p> <p><u>Part I.D.5.b.(viii).(e)</u> - Implement stormwater management practices that protect and enhance groundwater recharge as allowed under the applicable water rights laws.</p> <p><u>Part I.D.5.b.(viii).(f)</u> - Seek to avoid or prevent hydromodification of streams and other water bodies caused by development, including roads, highways, and bridges.</p> <p><u>Part I.D.5.b.(viii).(g)</u> - Develop and implement policies to protect native soils, prevent topsoil stripping, and prevent compaction of soils.</p> <p><u>Part I.D.5.b.(viii).(h)</u> - The program must be specifically tailored to address local community needs (e.g. protection to drinking water sources, reduction of water quality impacts) and must be designed to attempt to maintain pre-development runoff conditions.</p>	<p><u>Part I.D.5.b.(viii).(d)</u> - This section is rarely applicable to AMAFCA's projects. In the arid southwest, direct discharges to surface waters are rare.</p> <p><u>Part I.D.5.b.(viii).(e)</u> - The NM OSE regulates the water delivery to the Rio Grande in order to meet water delivery requirements to Texas; therefore, AMAFCA's objective is to design its facilities to drain within 96 hours per the OSE requirements.</p> <p><u>Part I.D.5.b.(viii).(f)</u> - AMAFCA projects, to the extent feasible and as consistent with O&amp;M of sediment removal, will continue to seek to avoid or prevent hydromodification of streams and other water bodies.</p> <p><u>Part I.D.5.b.(viii).(g)</u> - AMAFCA projects and those in coordination with other MS4s, will, to the extent possible, protect native soils, prevent topsoil stripping, and prevent compaction of soils.</p> <p><u>Part I.D.5.b.(viii).(h)</u> - AMAFCA does not have jurisdictional authority pertaining to development or redevelopment activities. However, through AMAFCA's involvement with the MRGSQT and TAG, AMAFCA will support programs tailored to address local community needs and that are designed to attempt to maintain pre-development runoff conditions.</p>	<ul style="list-style-type: none"> <li>• AMAFCA will develop written procedures that include applicable watershed protection elements in Part I.D.5.b.(viii).(f), (g) and (h) as required in the MS4 Permit and as applicable to AMAFCA.</li> <li>• AMAFCA will continue to contribute and participate in the MRGSQT, which supports programs tailored to address local community needs and are designed to attempt to maintain pre-development runoff conditions.</li> <li>• AMAFCA will complete updated hydrologic analyses, utilizing the AMAFCA White Paper Methodology, for the NDC watersheds, to assist with understanding options for maintaining pre-development runoff conditions.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• Many of these applicable Permit activities are being conducted cooperatively.</li> <li>• AMAFCA continued to contribute and participate in the MRGSQT, which supports programs tailored to address local community needs and are designed to attempt to maintain pre-development runoff conditions.</li> </ul>
Not Included in NOI	80	<p>Update the SWMP document and annual report as required in <u>Part I.D.5.b.(ix)</u> and <u>Part I.D.5.b.(x)</u>. The permittee must update the SWMP as necessary to include a description of the mechanism(s) utilized to comply with the permit elements listed above as well as the citations/descriptions of design standards for structural and non-structural controls to control pollutants in runoff. The following information must be included in each Annual Report:</p> <p><u>Part I.D.5.b.(x).(a)</u> - Include a summary and analysis of all maintenance, inspections and enforcement, and the number and frequency of inspections performed annually.</p> <p><u>Part I.D.5.b.(x).(b)</u> - A cumulative listing of the annual modifications made to the Post-Construction Stormwater Management Program, and</p> <p><u>Part I.D.5.b.(x).(c)</u> - According to the schedule presented in Table 3, the permittee must:</p> <p>A. Report the no. of MS4-owned properties and infrastructure that have been retrofitted with control measures designed to control the frequency, volume, and peak intensity of stormwater discharges.</p> <p>B. As required in Part I.D.5.b.(vi), report the tabulated results for IA &amp; DCIA and its estimation methodology.</p>	<p><u>Part I.D.5.b.(ix)</u> - AMAFCA will update the SWMP as necessary to comply with the permit elements listed above as well as the citations and descriptions of design standards for structural and non-structural controls to control pollutants in stormwater runoff, including discussion of the methodology used during design for estimating impacts to water quality and selecting structural and non-structural controls.</p> <p><u>Part I.D.5.b.(x).(a)</u> - AMAFCA tracks all crew activity related to maintenance of all water quality structures.</p> <p><u>Part I.D.5.b.(x).(b)</u> - AMAFCA does not have any development or redevelopment projects - all AMAFCA projects are regional flood control or water quality projects. AMAFCA will continue to maintain a cumulative listing of the annual modifications made to the Post-Construction Stormwater Management Program.</p> <p><u>Part I.D.5.b.(x).(c).A</u> - AMAFCA will continue to maintain a list of properties and infrastructure within AMAFCA rights-of-way that have been retrofitted with control measures designed to control frequency, volume and peak intensity of stormwater discharges.</p> <p><u>Part I.D.5.b.(x).(c).B</u> - AMAFCA will estimate the Impervious Area (IA) and Directly Connected Impervious Area (DCIA) within AMAFCA's jurisdiction and/or rights of way (refer to ID 76).</p>	<ul style="list-style-type: none"> <li>• AMAFCA will update the SWMP as necessary to comply with the permit elements listed above.</li> <li>• AMAFCA will continue to annually inspect and track all crew activity related to maintenance of all AMAFCA owned water quality structures.</li> <li>• AMAFCA will continue to maintain a cumulative listing of the annual modifications made to the Post-Construction Stormwater Management Program.</li> <li>• AMAFCA will continue to provide a cumulative list of AMAFCA's retrofit BMPs. AMAFCA will incorporate documentation by reference into the Annual Report and plans to document progress on the AMAFCA website.</li> <li>• AMAFCA will estimate the IA and DCIA within AMAFCA's jurisdiction and/or rights of way. AMAFCA will update this estimate, as appropriate, given development in the watersheds. This will be a cooperative effort with other watershed MS4s (refer to ID 76).</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• AMAFCA conducted site inspections for 100% of the AMAFCA construction projects in accordance with this MS4 Permit in FY 2023.</li> <li>• Lists of MS4 program modifications and facility modifications/retrofits are available upon request.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
2.12	81	Enhance the program to include the elements in <u>Part I.D.5.b.(xi)</u> and <u>Part I.D.5.a.(xii)</u> . These include: <u>Part I.D.5.b.(xi)</u> - Use of stormwater educational materials; and <u>Part I.D.5.b.(xii)</u> - When choosing appropriate BMPs, the permittee may participate in locally-based watershed planning efforts, which attempt to involve a diverse group of stakeholders including interested citizens. and <u>Part I.D.5.b.(xiii)</u> - The permittee may incorporate the following elements in the Post-Construction Stormwater Management in New Development and Redevelopment program required in Part I.D.5.b.(ii)(b): (a) Provide requirements and standards to direct growth to identified areas to protect environmentally and ecologically sensitive areas such as floodplains and/or other areas with endangered species and historic properties concerns; (b) Include requirements to maintain and/or increase open space/buffers along sensitive water bodies, minimize impervious surfaces, and minimize disturbance of soils and vegetation; and (c) Encourage in fill development in higher density urban areas, and areas with existing storm sewer infrastructure.	<u>Part I.D.5.b.(xi)</u> - As part of the MRGSQT, AMAFCA will continue to use stormwater educational materials, either developed locally or provided by EPA, NMED environmental groups, public interest groups, trade organizations, and/or other MS4 as well as utilizing the MRGSQT. <u>Part I.D.5.b.(xii)</u> - AMAFCA may continue to participate in the watershed planning efforts with other MS4s in order to publish the AMAFCA Project Schedule biennially. AMAFCA will continue membership and involvement in the cooperative MS4 TAG, which will facilitate cooperation and coordination with other MS4s in the Middle Rio Grande watershed. <u>Part I.D.5.b.(xiii)</u> - These program enhancements are outside the AMAFCA's authority and mission. However, AMAFCA will cooperate with other watershed MS4s, as applicable, to support this program enhancement.	<ul style="list-style-type: none"> <li>• AMAFCA will continue to contribute and participate in the MRGSQT. The MRGSQT Outcomes Report will summarize the activities where educational materials were dispersed and shared with the public. This report is available upon request and AMAFCA plans to share this document on its website.</li> <li>• AMAFCA may coordinate with MS4s for project planning of infrastructure retrofitting. AMAFCA will continue to produce and publish the AMAFCA Project Schedule.</li> <li>• AMAFCA will continue membership and involvement in the cooperative MS4 Technical Advisory Group (MS4 TAG) which will facilitate cooperation and coordination with other MS4s in the Middle Rio Grande.</li> </ul>	<b>Met FY 2023 Goals.</b> <ul style="list-style-type: none"> <li>• AMAFCA continued to contribute and participate in the MRGSQT, which supports post-construction education and outreach programs. The Outcomes Report is included as a Program Summary to this Annual Report.</li> <li>• In FY 2023, AMAFCA worked on the 2024 Project Schedule which covers a six-year planning horizon (2024-2029). The 2024 Project schedule will be finalized in 2024. Coordination meetings with watershed MS4s, TAG members, and other entities occurred during the development of this Project Schedule and included the ranking of stormwater quality projects.</li> <li>• AMAFCA continued to be involved in the MS4 TAG group, facilitating cooperation and coordination with other MS4s in the Middle Rio Grande.</li> <li>• AMAFCA participated as a review partner for the Bernalillo County's updated technical standards, which includes the Green Stormwater Infrastructure/Low Impact Development (GSI/LID) Standards document. During 2023, Bernalillo County completed updating its Technical Standards. Integration of GSI/LID into the Technical Standards and review process was a key focus of this update. As a part of this update, the County developed a stand-alone GSI/LID Standards document that identifies GSI/LID BMPs that are arid-appropriate and support Bernalillo County's Stormwater Quality Ordinance, representing an increased commitment from the County toward the goal of broad implementation of GSI/LID in the</li> </ul>
2.13	82	Item from MS4 Permit NOI. Describe other proposed activities to address the Post-Construction Stormwater Management in New Development and Redevelopment Measure.	Because AMAFCA is a flood control authority, the legal authority and jurisdiction granted to it by the State of New Mexico is limited. AMAFCA has begun requiring, and will continue to require, MS4 permit elements into construction contracts.	<ul style="list-style-type: none"> <li>• AMAFCA will continue, as appropriate, to insert MS4 Permit elements into construction contracts to provide AMAFCA with a contractual mechanism for MS4 elements.</li> </ul>	<b>Met FY 2023 Goals.</b> <ul style="list-style-type: none"> <li>• AMAFCA continued to, as appropriate, insert MS4 Permit elements into construction contracts to provide AMAFCA with a contractual mechanism for MS4 elements.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
	83	<b>TABLE 4: Pollution Prevention/Good Housekeeping for Municipal/Co-permittee Operations - Part I.D.5.c</b>			
3.1	84	Develop or update the Pollution Prevention/Good Housekeeping program to include the elements in Part I.D.5.c.(i). Elements include: <u>Part I.D.5.c.(i).(a)</u> - Employee training program to incorporate pollution prevention and good housekeeping, including a tracking procedure; <u>Part I.D.5.c.(i).(b)</u> - O&M activities, schedules, and long term inspections procedures for structural and non-structural stormwater controls; <u>Part I.D.5.c.(i).(c)</u> - Controls for reducing or eliminating the discharge of pollutants from AMAFCA maintenance and storage yards and shop; <u>Part I.D.5.c.(i).(d)</u> - Procedures for properly disposing of waste removed from separate storm sewers and facilities listed in Part I.D.5.c.(i).(c) (such as dredged spoil, accumulated sediments, floatables, and other debris); <u>Part I.D.5.c.(i).(e)</u> - Procedures to ensure that new flood management projects assess the impacts on water quality and examine existing projects for incorporating additional water quality protection devices or practices .	<u>Part I.D.5.c.(i)</u> - AMAFCA will continue its Pollution Prevention/Good Housekeeping Program. <u>Part I.D.5.c.(i).(a)</u> - AMAFCA will continue employee training as it becomes available to incorporate pollution prevention and good housekeeping; <u>Part I.D.5.c.(i).(b)</u> - AMAFCA will adhere to its current O&M and Safety procedures, which include employee training for maintenance of AMAFCA flood control and water quality facilities and BMPs. <u>Part I.D.5.c.(i).(c)</u> - AMAFCA will implement and maintain controls for reducing the discharge of pollutants from AMAFCA maintenance and storage yards and shop; <u>Part I.D.5.c.(i).(d)</u> - AMAFCA will develop procedures, where appropriate, for properly disposing of waste removed from AMAFCA facilities (sediment, floatables, and other debris); <u>Part I.D.5.c.(i).(e)</u> - AMAFCA ensures that new projects will assess the impacts on water quality and existing projects will be examined for retrofit opportunities as part of AMAFCA's Post Construction Control Measures.	<ul style="list-style-type: none"> <li>• AMAFCA will document training provided to its employees &amp; include pollution prevention and good housekeeping into training, as needed.</li> <li>• AMAFCA encourages that crew members are trained in spill prevention &amp; control, as well as truck fueling activities during the Permit term.</li> <li>• AMAFCA will adhere to its current O&amp;M and Safety Procedures.</li> <li>• In the Annual Report, AMAFCA will consider projected costs for the operation and maintenance of its stormwater quality facilities.</li> <li>• AMAFCA will review new projects to assess the impacts on water quality and will examine existing projects for retrofit opportunities as part of AMAFCA's Post Construction Control Measure.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• In FY 2023, stormwater continued to be a topic at the staff and crew meetings, including discussions related to pollution prevention and good housekeeping.</li> <li>• Training records for AMAFCA staff &amp; crew are available upon request.</li> <li>• In FY 2023, AMAFCA adhered to its current O&amp;M and Safety Procedures.</li> <li>• The FY 2023 annual cost for maintenance of its stormwater quality facilities is available upon request.</li> <li>• Refer to AMAFCA's Post Construction Control Measure in this Annual Report for additional information on new and retrofit project assessments for impacts on water quality.</li> <li>• In FY 2023, AMAFCA worked on the 2024 Project Schedule which covers a six-year planning horizon (2024-2029). The 2024 Project schedule will be finalized in 2024. Coordination meetings with watershed MS4s, TAG members, and other entities occurred during the development of this Project Schedule and included the ranking of stormwater quality projects.</li> </ul>
3.2	85	The program will include the elements in Part I.D.5.c.(ii). These include: <u>Part I.D.5.c.(ii).(a)</u> - Develop or update the existing list of all stormwater quality facilities by drainage basin, including location and description;	<u>Part I.D.5.c.(ii).(a)</u> - As part of the Program, AMAFCA will continue to up-date a map of all stormwater quality facilities by drainage basin, including location and description.	<ul style="list-style-type: none"> <li>• AMAFCA will continue to up-date a map of all AMAFCA stormwater quality facilities by drainage basin, including location and description.</li> </ul>	<p><b>Met FY 2023 Goal.</b></p> <ul style="list-style-type: none"> <li>• AMAFCA's crew tracking system and database lists each of its stormwater quality facilities by drainage basin. These facilities are also shown on AMAFCA Maintenance Map, available online: <a href="https://amafca.org/gis-maps-data/">https://amafca.org/gis-maps-data/</a></li> </ul>
3.2	86	<u>Part I.D.5.c.(ii).(b)</u> - Develop or modify existing operational manual for de-icing activities addressing alternate materials and methods to control impacts to stormwater quality;	<u>Part I.D.5.c.(ii).(b)</u> - N/A - AMAFCA only has jurisdiction to maintain its facilities; AMAFCA does not engage in the following: de-icing, roadway debris control, street sweeping, or roadway pollutant removal.	N/A	N/A
3.2 & 3.4	87	<u>Part I.D.5.c.(ii).(c)</u> - Develop or modify existing program to control pollution in stormwater runoff from equipment and vehicle maintenance yards and maintenance center operations located within the MS4;	<u>Part I.D.5.c.(ii).(c)</u> - For compliance with this section of the MS4 Permit, AMAFCA's focus is to evaluate and modify, where necessary, the existing program to control pollution in stormwater runoff from AMAFCA's equipment and vehicle maintenance yard and satellite facilities.	<ul style="list-style-type: none"> <li>• AMAFCA will continue to implement and maintain administrative and structural BMPs.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• AMAFCA continued to review the Good Housekeeping Assessments for AMAFCA facilities.</li> </ul>
3.2	88	<u>Part I.D.5.c.(ii).(d)</u> - Develop or modify existing street sweeping program. Assess possible benefits from changing frequency or timing of sweeping activities or utilizing different equipment for sweeping activities;	<u>Part I.D.5.c.(ii).(d)</u> - N/A - AMAFCA only has jurisdiction to maintain its facilities; AMAFCA does not engage in the following: de-icing, roadway debris control, street sweeping, or roadway pollutant removal.	N/A	N/A

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
3.2	89	<u>Part 1.D.5.c.(ii).(e)</u> - A description of procedures used by permittees to target roadway areas most likely to contribute pollutants to and from the MS4 (i.e., runoff discharges directly to sensitive receiving water, roadway receives majority of de-icing material, roadway receives excess litter, roadway receives greater loads of oil and grease);	<u>Part 1.D.5.c.(ii).(e)</u> - AMAFCA only has jurisdiction to maintain its facilities; AMAFCA does not engage in the following: de-icing, roadway debris control, street sweeping, or roadway pollutant removal. AMAFCA will continue coordination, as applicable, with other MS4s in the watershed related to illicit discharge detection and elimination from roadways - refer to the Illicit Discharges and Improper Disposal Control Measure.	N/A	N/A
3.2	90	<u>Part 1.D.5.c.(ii).(f)</u> - Develop or revise existing standard operating procedures for collection of used motor vehicle fluids (at a minimum oil and antifreeze) and toxics (including paint, solvents, fertilizers, pesticides, herbicides, and other hazardous materials) used in permittee operations or discarded in the MS4, for recycle, reuse, or proper disposal.	<u>Part 1.D.5.c.(ii).(f)</u> - For compliance with this section of the MS4 Permit, AMAFCA's focus is to evaluate and modify, where necessary, the existing program to control pollution in stormwater runoff from the equipment and vehicle maintenance yard.	<ul style="list-style-type: none"> <li>• AMAFCA will maintain the existing program to control polluted stormwater runoff from its equipment and maintenance yard.</li> <li>• AMAFCA will continue to implement and maintain BMPs.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• AMAFCA continued the existing program to control pollutants to stormwater runoff from its equipment and maintenance yard.</li> <li>• AMAFCA coordinated with local landfills for appropriate testing requirements for material disposal as a result of maintaining agency equipment, as needed.</li> <li>• AMAFCA continued to review the Good Housekeeping Assessments for AMAFCA facilities.</li> </ul>
3.2	91	<u>Part 1.D.5.c.(ii).(g)</u> - Standard operating procedure for disposal of accumulated sediments, floatables, and debris;	<u>Part 1.D.5.c.(ii).(g)</u> - AMAFCA performs waste disposal for sediment, floatables, and other debris in accordance with the "AMAFCA Operations and Maintenance Manual for Dams" and "AMAFCA Operation and Maintenance Repair Replacement and Rehabilitation Manual" (OMRRR). As a cooperative program, AMAFCA is a participant in an OMRRR with Bernalillo County, the MRGCD, and the Bureau of Reclamation related to facilities that are connected to MRGCD ditches (primarily in the SW Valley of Albuquerque).	<ul style="list-style-type: none"> <li>• Continue to perform all waste disposal for sediment, floatables, and other debris in accordance with the operation and maintenance manuals and direct vendor contractors to collect and dispose of trash, floatables, and debris.</li> <li>• AMAFCA will develop standard operating procedures, as applicable, for these disposal activities.</li> <li>• AMAFCA will continue to participate, as appropriate, in the Operation Maintenance Repair, Replacement, and Rehabilitation (OMRRR) - Southwest Valley Flood Reduction Project cooperative program with MRGCD, Bernalillo County, and Bureau of Reclamation.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• AMAFCA continued to perform all waste disposal for sediment, floatables and other debris in accordance with the O&amp;M manuals and direct vendor contractors to collect and dispose of trash, floatables, and debris.</li> <li>• AMAFCA continued to follow standard operating procedures, as applicable.</li> <li>• AMAFCA coordinated with local landfills for appropriate testing requirements for material disposal as a result of maintaining agency equipment, as needed.</li> <li>• AMAFCA continued to participate in the OMRRR - cooperative program with MRGCD, Bernalillo County, and Bureau of Reclamation.</li> </ul>
3.2	92	<u>Part 1.D.5.c.(ii).(h)</u> - litter source control program, include targeted public awareness campaign;	<u>Part 1.D.5.c.(ii).(h)</u> - Through involvement in the MRGSQT, AMAFCA will continue to collaborate with the MS4 permittees to improve upon the existing litter source control program, including a targeted public awareness campaign.	<ul style="list-style-type: none"> <li>• AMAFCA will continue its involvement with and financial support of the MRGSQT.</li> <li>• AMAFCA will continue to collaborate with the MS4 permittees to improve upon the existing litter source control program.</li> <li>• The MRGSQT Outcomes Report is available upon request and AMAFCA plans to share this document on its website.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• AMAFCA continued to contribute and participate in the MRGSQT, which supports litter source control public awareness programs. The MRGSQT Outcomes Report is included as a Program Summary to the Annual Report. A summary of trash removed from all AMAFCA facilities is provided in a Program Summary and information related to each AMAFCA facility is available upon request.</li> </ul>



NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
3.2	93	<p>Part 1.D.5.c.(ii).(i) - Develop or review and revise, as necessary, the criteria, procedures and schedule to evaluate existing flood control devices, structures and drainage ways to assess the potential of retrofitting to provide additional pollutant removal from stormwater. Implement routine review to ensure new and/or innovative practices are implemented where applicable.</p>	<p>Part 1.D.5.c.(ii).(i) - AMAFCA may continue to coordinate with watershed MS4s and other entities within its jurisdiction to discuss areas requiring drainage and water quality retrofits, project priorities, and multi-agency funding. AMAFCA will publish projects, including schedule and cost sharing, in the AMAFCA Project Schedule.</p> <p>Operation and Maintenance procedures, inspections, repairs, and retrofits are evaluated through the annual cooperative Agency and Area Wide and Miscellaneous contracts.</p>	<ul style="list-style-type: none"> <li>• AMAFCA may continue to coordinate with watershed MS4s and other entities within its jurisdiction to discuss the areas requiring drainage and water quality retrofitting within the Middle Rio Grande Watershed, project priorities, and multi-agency funding contributions. AMAFCA will continue to produce and publish the AMAFCA Project Schedule, which includes projects for retrofitting existing flood control devices, structures and drainage ways to provide additional pollutant removal from stormwater.</li> <li>• AMAFCA will continue to participate in the cooperative Agency and Area Wide contract and utilize the Miscellaneous contract to address rehabilitation, repair, and retrofit activities for AMAFCA structures.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• In FY 2023, AMAFCA worked on the 2024 Project Schedule which covers a six-year planning horizon (2024-2029). The 2024 Project schedule will be finalized in 2024. Coordination meetings with watershed MS4s, TAG members, and other entities occurred during the development of this Project Schedule and included the ranking of stormwater quality projects.</li> <li>• AMAFCA continued to utilize the Agency and Area Wide and Miscellaneous contracts to address rehabilitation, repair, and retrofit activities for AMAFCA structures and cooperative maintenance projects.</li> </ul>
3.2	94	<p>Part 1.D.5.c.(ii).(j) - Enhance inspection and maintenance programs by coordinating with maintenance personnel to ensure that a target number of structures per basin are inspected and maintained per quarter;</p>	<p>Part 1.D.5.c.(ii).(j) - AMAFCA has in place a well-defined and implemented routine inspection and O&amp;M program that includes both formal and informal inspections and maintenance schedules. This program will be enhanced to ensure a target number of structures per basin are inspected and maintained per quarter, as required by the MS4 Permit, for annual compliance with the MS4 Permit.</p> <p>AMAFCA will enhance its inspection and maintenance programs, as required by the MS4 Permit, through improved coordination. AMAFCA will, depending on funding available, utilize the Agency and Area Wide and Miscellaneous contracts to address portions of the required inspection and maintenance.</p>	<ul style="list-style-type: none"> <li>• AMAFCA will continue coordination between maintenance personnel and staff to ensure that, on average, two (2) structures per basin are inspected and maintained per quarter.</li> <li>• AMAFCA will, depending on funding available, utilize the Agency and Area Wide and Miscellaneous contracts to address portions of the required inspection and maintenance.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• AMAFCA O&amp;M activities are discussed at staff and crew meetings to allow coordination among staff and crew.</li> <li>• In this Permit term, AMAFCA inspected AMAFCA structures as required by the MS4 Permit.</li> <li>• AMAFCA continued to participate in the Agency and Area Wide contract and issue tasks under the annual Miscellaneous contract to address rehabilitation, repair, and retrofit activities for AMAFCA structures and cooperative maintenance projects.</li> </ul>
3.2	95	<p>Part 1.D.5.c.(ii).(k) - Enhance the existing program to control the discharge of floatables and trash from the MS4 by implementing source control of floatables in industrial and commercial areas;</p>	<p>Part 1.D.5.c.(ii).(k) - AMAFCA does not have jurisdiction over industrial and commercial areas in the MS4. AMAFCA will continue coordination with the MRG MS4s, as well as involvement with the MRGSQT and the MS4 TAG, to enhance the program to control the discharge of floatables and trash from the MS4 by implementing source control of floatables in industrial and commercial areas.</p>	<ul style="list-style-type: none"> <li>• AMAFCA will continue its involvement with and financial support of the MRGSQT.</li> <li>• AMAFCA will continue to collaborate with the MS4 permittees to improve upon the source control of floatables in industrial and commercial areas.</li> <li>• AMAFCA will continue membership and involvement in the cooperative MS4 TAG.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• AMAFCA continued to contribute and participate in the MRGSQT, which supports trash and litter control public awareness programs.</li> <li>• AMAFCA continued to be involved in the MS4 TAG group, facilitating cooperation and coordination with other MS4s in the Middle Rio Grande.</li> </ul>



NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
3.2	96	<p><u>Part 1.D.5.c.(ii).(l)</u> - Include in each Annual Report, a cumulative summary of retrofit evaluations conducted during the permit term on existing flood control devices, structures and drainage ways to benefit water quality. Update the SWMP to include a schedule (with priorities) for identified retrofit projects;</p>	<p><u>Part 1.D.5.c.(ii).(l)</u> - AMAFCA may continue to coordinate with watershed MS4s and other entities within its jurisdiction to discuss areas requiring drainage and water quality retrofits, project priorities, and multi-agency funding. As part of the development of the AMAFCA Project Schedule, a system review will be completed. AMAFCA will publish projects, including schedule and cost sharing, in the AMAFCA Project Schedule. Using the Project Schedule process, water quality projects and water quality retrofit projects may be ranked and prioritized.</p>	<ul style="list-style-type: none"> <li>• AMAFCA will continue to provide a cumulative list of AMAFCA's retrofit BMPs. AMAFCA will incorporate documentation by reference into the Annual Report - refer to the Post-Construction Control Measure.</li> <li>• AMAFCA will continue including facility evaluations as part of AMAFCA studies, including drainage management plans, facility plans, and other analysis projects, as appropriate.</li> <li>• AMAFCA will continue to include BMP/water quality facility retrofit projects in the Project Schedule.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• In FY 2023, AMAFCA worked on the 2024 Project Schedule which covers a six-year planning horizon (2024-2029). The 2024 Project schedule will be finalized in 2024. Coordination meetings with watershed MS4s, TAG members, and other entities occurred during the development of this Project Schedule and included the ranking of stormwater quality projects.</li> </ul>
3.2	97	<p><u>Part 1.D.5.c.(ii).(m)</u> - Flood management projects: review and revise, as necessary, technical criteria guidance documents and program for the assessment of water quality impacts and incorporation of water quality controls into future flood control projects. The criteria guidance document must include the following elements:  <u>Part 1.D.5.c.(ii).(m).A.</u> - Describe how new flood control projects are assessed for water quality impacts.  <u>Part 1.D.5.c.(ii).(m).B.</u> - Provide citations and descriptions of design standards that ensure water quality controls are incorporated in future flood control projects.  <u>Part 1.D.5.c.(ii).(m).C.</u> - Include method for permittees to update standards with new and/or innovative practices.  <u>Part 1.D.5.c.(ii).(m).D.</u> - Describe master planning and project planning procedures and design review procedures.</p>	<p><u>Part 1.D.5.c.(ii).(m).A.</u> - AMAFCA, through its processes, will assess new flood control projects for water quality impacts. As new flood control projects are constructed, AMAFCA will consider the appropriate time and location for the collection of water quality data to assess project water quality impacts. During facility planning, AMAFCA will adhere to current and future drainage and water quality management plans passed by the AMAFCA Board of Directors, Bernalillo County Commission, or Albuquerque City Council. AMAFCA will continue its proactive policy of incorporating stormwater quality BMPs into new flood control projects when feasible. AMAFCA will publish projects, including schedule and cost sharing, in the AMAFCA Project Schedule. Using the Project Schedule process, water quality projects and water quality retrofit projects may be ranked and prioritized.  <u>Part 1.D.5.c.(ii).(m).B.</u> - AMAFCA is assessing the use of National design standards related to water quality controls.  <u>Part 1.D.5.c.(ii).(m).C.</u> - AMAFCA will continually assess design standards and practices, technical specifications, and BMPs and implement them, as applicable.  <u>Part 1.D.5.c.(ii).(m).D.</u> - AMAFCA has established procedures for master planning through its Drainage Master Plan development, project planning procedures using its Project Schedule, and design review procedures used by its Development Review Engineer.</p>	<ul style="list-style-type: none"> <li>• AMAFCA has all of the elements of the Technical Criteria Guidance Document as part of their various programs but not as part of one document. Many of these elements are done in cooperation with watershed MS4s.</li> <li>• AMAFCA's Project Schedule process includes, in part, coordination with watershed MS4s, TAG members, and other entities within its jurisdiction and may include the ranking of flood control and stormwater quality projects.</li> <li>• AMAFCA is assessing the use of National design standards related to water quality controls.</li> <li>• AMAFCA will continually assess design standards and practices and implementing them, as applicable.</li> <li>• AMAFCA will continue to follow its established procedures for Drainage Master Plan development, project planning procedures using its Project Schedule, and design review procedures.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• In FY 2023, AMAFCA worked on the 2024 Project Schedule which covers a six-year planning horizon (2024-2029). The 2024 Project schedule will be finalized in 2024. Coordination meetings with watershed MS4s, TAG members, and other entities occurred during the development of this Project Schedule and included the ranking of stormwater quality projects.</li> <li>• AMAFCA is assessing the use of ASCE's "Standard Guidelines for the Design of Urban Stormwater Systems, Standard Guidelines for Installation of Urban Stormwater Systems, and Standard Guidelines for the Operation and Maintenance of Urban Stormwater Systems" for national design standards related to water quality controls.</li> <li>• AMAFCA participated as a review partner for the Bernalillo County's updated technical standards, which includes the GSI/LID Standards document. During 2023, Bernalillo County completed updating its Technical Standards. Integration of GSI/LID into the Technical Standards and review process was a key focus of this update.</li> <li>• AMAFCA continued to follow its established procedures for Drainage Master Plan development, project planning procedures using its Project Schedule (refer to the Post-Construction section of the Annual Report for additional information), and design review procedures used by its Development Review Engineer.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
3.2	98	<p>Part I.D.5.c.(ii).(n) -Develop procedures to control the discharge of pollutants related to the storage and application of pesticides, herbicides, and fertilizers applied, by the permittee's employees or contractors, to public right-of-ways, parks, and other municipal property. The permittee must provide an updated description of the data monitoring system for all permittee departments utilizing pesticides, herbicides and fertilizers.</p>	<p>Part I.D.5.c.(ii).(n) - AMAFCA will only allow licensed staff or professionally licensed contractors to apply herbicides and pesticides within AMAFCA rights-of-way (AMAFCA does not apply fertilizers in its operations). In addition, AMAFCA will review, as necessary, leases and licenses, to ensure wording is included addressing the control of discharge of pollutants related to the storage and application of pesticides, herbicides, and fertilizers applied by entities leasing or licensed to use AMAFCA lands. AMAFCA will develop a tracking system to monitor herbicides and pesticides within AMAFCA rights-of-way (AMAFCA does not apply fertilizers in its operations). AMAFCA will store all herbicides and pesticides according to direction by product vendors.</p>	<ul style="list-style-type: none"> <li>• AMAFCA personnel will typically not apply fertilizers in its operations.</li> <li>• AMAFCA will only allow professional licensed contractors or licensed crew members to apply herbicides and pesticides within AMAFCA rights-of-way.</li> <li>• AMAFCA will be reviewing, as necessary, leases and licenses, to ensure wording is included addressing the control of discharge of pollutants related to the storage and application of herbicides, pesticides, and fertilizers applied by entities leasing or licensed to use AMAFCA lands.</li> <li>• AMAFCA will continue developing a tracking system to monitor herbicide and pesticide applications within AMAFCA ROW.</li> <li>• AMAFCA will store all herbicides and pesticides according to direction by product vendors.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• In FY 2023, the AMAFCA licensed crew members or professional licensed contractors were used when herbicide and/or pesticide application was necessary.</li> <li>• Herbicide and pesticide storage was reviewed as part of the Good Housekeeping assessment.</li> <li>• AMAFCA has a tracking system for the herbicide and pesticide inventory.</li> </ul>
3.3	99	<p>Develop or update a list and a map of industrial facilities owned or operated by the permittee as required in Part I.D.5.c.(iii).</p>	<p>Part I.D.5.c.(iii) - N/A - No EPA Multi Sector General Permit (MSGP) facilities within AMAFCA rights-of-way. This has been discussed and confirmed with NMED. This was submitted to EPA in AMAFCA's NOI and accepted.</p>	N/A	N/A
Not Included in NOI	100	<p>Update the SWMP document and annual report as required in I.D.5.c.(iv) and Part I.D.5.c.(v).</p> <p>Part I.D.5.c.(iv) - The permittee must include in the SWMP a description of the mechanism(s) utilized to comply with each of the elements required in Part I.D.5.c.(i) throughout Part I.D.5.c.(iii) and its corresponding measurable goal. and</p> <p>Part I.D.5.c.(v) - The permittee shall assess the overall success of the program, and document the program effectiveness in the Annual Report.</p>	<p>Part I.D.5.c.(iv) - AMAFCA's Stormwater Quality Engineer will review the program requirements for the above-mentioned SWMP elements during the Annual Report process. The measurable goals in this section of the SWMP are the mechanisms used to comply with the Permit elements. A strategy to implement any new program requirements will be developed as needed.</p> <p>Part I.D.5.c.(v) - The Annual Report will serve as the progress report for this program, if applicable. AMAFCA will incorporate documentation by reference into the Annual Report.</p>	<ul style="list-style-type: none"> <li>• As part of the Annual Report process, the Stormwater Quality Engineer will review the program requirements listed in Part I.D.5.c, for the above-mentioned SWMP elements and develop a strategy to implement any new program requirements.</li> <li>• The Annual Report will serve as the progress report for this program, if applicable. AMAFCA will incorporate documentation by reference into the Annual Report.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• During the Annual Report preparation, AMAFCA's Storm Water Quality Engineer reviewed the program requirements listed in Part I.D.5.c, for the program SWMP elements, and considered program needs and requirements.</li> <li>• This Annual Report documents the program effectiveness and program success in the status of implementation and performance assessment for each MS4 Permit requirement.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
	101	<b>TABLE 5: Industrial and High Risk Runoff - Part I.D.5.d</b>			
4	102	As described in Part I.D.5.d, the permittees shall: (i) control the contribution of pollutants to the municipal storm sewer by stormwater discharges associated with industrial activity and the quality of stormwater discharged from sites of industrial activity as defined in 40 CFR 122.26(b)(14)(i)-(ix) and (xi). If no such industrial activities are in a permittees jurisdiction, that permittee may certify that this program element does not apply.	Part I.D.5.d - Activity removed from AMAFCA's SWMP (Rev. 0, December 1, 2015). AMAFCA certifies with submittal of this SWMP that no such industrial activities are in AMAFCA's jurisdiction and this program element does not apply. This was submitted to EPA in AMAFCA's NOI and accepted.	N/A	N/A

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
	103	<b>TABLE 6: Illicit Discharges and Improper Disposal - Part I.D.5.e</b>			
See NOI Sections Below	104	As described in <u>Part I.D.5.e.(i)</u> , the permittee shall develop, revise, implement, and enforce a program to detect and eliminate illicit discharges (as defined at 40 CFR 122.26(b)(2)) entering the MS4. Permittees previously covered under NMS000101 or NMR040000 must continue existing programs while updating those programs, as necessary, to comply with the requirements of this permit. The permittee must (see required items listed below):	<u>Part I.D.5.e.(i)</u> - AMAFCA has developed a program to detect and eliminate illicit discharges. The program elements, as they relate to the permit requirements, are described in detail below.	<ul style="list-style-type: none"> <li>The AMAFCA Stormwater Quality Engineer will continue to review, revise, and implement the Illicit Discharge Detection and Elimination Program requirements, as needed.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>In FY 2023, AMAFCA followed its policy of immediate coordination with downstream MS4 permittees and/or appropriate local, state, tribal, or federal regulatory agencies when such discharges were detected by AMAFCA personnel. The Illicit Discharge Response Plan specifies that AMAFCA alert the proper agency, if required.</li> </ul>
5.1	105	Mapping as required in <u>Part I.D.5.e.(i)(a)</u> . Develop, if not already completed, a storm sewer system map, showing the names and locations of all outfalls as well as the names and locations of all waters of the United States that receive discharge from those outfalls. Identify all discharge points into major drainage channels draining more than twenty (20) percent of the MS4 area;	<u>Part I.D.5.e.(i)(a)</u> - AMAFCA will continue to update its Maintenance Responsibilities for Drainage Facilities in the Albuquerque Metropolitan Area (Map). This is a color coded, detailed maintenance map showing all AMAFCA facilities (water quality BMPs, channels, large diameter storm drains, ponds, berms or dikes, dams, and receiving waters) and AMAFCA outfalls. AMAFCA cooperates with COA, NMDOT, Bernalillo County, SSCAFCA, Village of Los Ranchos, and MRGCD to collect their data for AMAFCA's map. This map is available on the AMAFCA website: <a href="http://www.amafca.org/maps-2/">http://www.amafca.org/maps-2/</a>	<ul style="list-style-type: none"> <li>AMAFCA will continue to keep this maintenance map up to-date for AMAFCA facilities and other MS4 permittee facilities, as information is provided. Cooperation with other MS4s will continue related to this map.</li> <li>AMAFCA will continue to update the map and publish this map on-line.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>In FY 2023, AMAFCA updated the GIS and webpage Interactive Map. This map is available online: <a href="https://amafca.org/gis-maps-data/">https://amafca.org/gis-maps-data/</a></li> </ul>
5.2	106	Ordinance (or other control method) as required in <u>Part I.D.5.e.(i)(b)</u> .	<p>Because AMAFCA is a flood control authority, the legal authority and jurisdiction granted to it by the State of New Mexico is limited.</p> <p><u>Part I.D.5.e.(i)(b)</u> - AMAFCA will contractually and/or administratively require the control of non-stormwater discharges from third-party operations within AMAFCA's jurisdiction and/or rights of way to the extent allowable under State, Tribal, or local law.</p>	<ul style="list-style-type: none"> <li>AMAFCA will contractually and/or administratively require the control of non-stormwater discharges on turn-key projects that AMAFCA will take over for operation and maintenance after construction to the extent allowable under State, Tribal, or local law.</li> </ul>	N/A
5.3	107	Develop and implement a IDDE plan as required in <u>Part I.D.5.e.(i)(c)</u> . The permittee must include the following elements in the plan: A. Procedures for locating priority areas likely to have illicit discharges including field tests for selected pollutant indicators (ammonia, boron, chlorine, color, conductivity, detergents, E. coli, enterococci, total coliform, fluoride, hardness, pH, potassium, conductivity, surfactants), and visually screening outfalls during dry weather; B. Procedures for enforcement, including enforcement escalation procedures for recalcitrant or repeat offenders; C. Procedures for removing the source of the discharge; D. Procedures for program evaluation and assessment; and E. Procedures for coordination with adjacent municipalities and/or state, tribal, or federal regulatory agencies to address situations where investigations indicate the illicit discharge originates outside the MS4 jurisdiction.	<u>Part I.D.5.e.(i)(c)</u> - AMAFCA will continue to assess its IDDE program, as appropriate.	<ul style="list-style-type: none"> <li>AMAFCA will continue to implement the updated IDDE program elements.</li> <li>AMAFCA will continue membership and involvement in the cooperative MS4 Technical Advisory Group (MS4 TAG) which will facilitate cooperation and coordination with other MS4s in the Middle Rio Grande related to the IDDE program.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>AMAFCA continued its membership and involvement in the cooperative MS4 TAG, which facilitated cooperation and coordination with other MS4s in the Middle Rio Grande related to the IDDE program.</li> <li>In FY 2023, AMAFCA continued to add the ABCWUA monthly DMR reports for SSOs to a maintained GIS database to help identify sources, trends, and issues. ABCWUA's CMOM Annual Report (which includes the Overflow Emergency Response Plan) is available upon request to the ABCWUA.</li> <li>AMAFCA continued utilizing established IDDE screening procedures, protocols, and response plan.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
5.4	108	Develop an education program as required in Part I.D.5.e.(i).(d). Develop an education program to promote, publicize, and facilitate public reporting of illicit connections or discharges, and distribution of outreach materials. The permittee shall inform public employees, businesses and the general public of hazards associated with illegal discharges and improper disposal of waste.	Part I.D.5.e.(i).(d) - AMAFCA will continue to participate in the MRGSQT and collaborate with the MS4 permittees to provide educational information regarding stormwater quality to the community. This information will promote, publicize, and facilitate public reporting of illicit connections or discharges, and distribution of outreach materials. This program informs the public of hazards associated with illicit discharges and improper waste disposal, as well as proper ways to dispose of hazardous wastes.	<ul style="list-style-type: none"> <li>• AMAFCA will continue work with the MRGSQT to inform the general public of the hazards associated with illegal discharges and improper disposal of waste.</li> <li>• AMAFCA will continue its involvement with and financial support of BEMP and through the MRGSQT.</li> <li>• The MRGSQT Outcomes Report is available upon request.</li> <li>• AMAFCA will continue an in-house training program for its administrative, engineering, and field employees regarding illegal discharges and improper disposal of waste.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• AMAFCA continued its partnership with the MRGSQT to inform the general public of the hazards associated with illegal discharges and improper disposal of waste.</li> <li>• In FY 2023, AMAFCA continued its involvement with and financial support of BEMP through the MRGSQT.</li> <li>• The MRGSQT Outcomes Report summarizes the educational and outreach programs for FY 2023. This report is included as a Program Summary.</li> <li>• Stormwater continues to be a topic at the weekly staff and monthly crew meetings, including discussions related to pollution prevention and good housekeeping. In addition, pertaining to AMAFCA employees, AMAFCA continues utilizing the IDDE Incident Report Form.</li> </ul>
5.5	109	Establish a hotline as required in Part I.D.5.e.(i).(e).	Part I.D.5.e.(i).(e) - MS4s that are members of the MRGSQT benefit from the Albuquerque 311 Citizen Contact Center. The 311 service is a single telephone number for all non-emergency inquiries and services. This program includes citizen calls regarding illicit discharges.	<ul style="list-style-type: none"> <li>• MS4s in the watershed will continue to participate in the 311 call in program.</li> </ul>	<p><b>Met FY 2023 Goal.</b></p> <ul style="list-style-type: none"> <li>• AMAFCA investigated and documented all jurisdictional illicit discharge complaints received through the 311 call in program, as well as other complaints received directly by AMAFCA staff through email, phone, or ABCWUA's monthly DMR Sanitary Sewer Overflow Reports provided to AMAFCA. AMAFCA continued use of the IDDE Incident Report Form, which is used to report illicit discharges that were witnessed by or reported to AMAFCA staff. The 311 complaints that are not in AMAFCA's jurisdiction are directed to the appropriate jurisdictional agency.</li> <li>• AMAFCA continued to discuss illicit discharges (events, issues, and follow-up) at staff meetings.</li> <li>• A copy of the IDDE Incident Report Form as well as the current Illicit Discharge Response Plan and testing procedures are available upon request.</li> </ul>
5.6	110	Investigate suspected significant/severe illicit discharges as required in Part I.D.5.e.(i).(f). Investigate suspected significant/severe illicit discharges within forty-eight (48) hours of detection and all other discharges as soon as practicable; elimination of such discharges as expeditiously as possible; and, requirement of immediate cessation of illicit discharges upon confirmation of responsible parties.  Illicit Discharge is defined in 40 CFR 122.26(b)(2) as "Illicit discharge means any discharge to a municipal separate storm sewer that is not composed entirely of stormwater except discharges pursuant to a NPDES permit (other than the NPDES permit for discharges from the municipal separate storm sewer) and discharges resulting from fire fighting activities."	Part I.D.5.e.(i).(f) - AMAFCA will continue its policy of investigation of suspected significant/severe illicit discharges within forty-eight (48) hours of detection/reporting and all other discharges as soon as practicable. AMAFCA plans to continue removing/treating such discharges as expeditiously as possible and requiring immediate cessation of illicit discharges upon confirmation of responsible parties. AMAFCA will continue its procedures for illicit discharge investigation and use of its IDDE Incident Report Form.  "Illicit discharge" also covers illegal or improper disposal or dumping of wastes into AMAFCA facilities. For AMAFCA, "illicit discharges" typically fall into two categories: (1) liquid discharge, or (2) solid discharge (dumped trash, debris, dirt/sediment, tires). Liquid discharges are considered urgent in order to quickly determine if they are significant/severe illicit discharges and are investigated within forty-eight (48) hours of detection. Solid discharge are investigated and identified for clean-up during the weekly staff meetings.	<ul style="list-style-type: none"> <li>• AMAFCA will continue its policy of investigation of suspected significant/severe illicit discharges within 48 hours of detection and all other discharges as soon as practicable.</li> <li>• MS4s in the watershed will continue to participate in the 311 call in program.</li> <li>• AMAFCA will continue membership and involvement in the cooperative MS4 Technical Advisory Group (MS4 TAG) which will facilitate cooperation and coordination with other MS4s in the Middle Rio Grande related to investigation of illicit discharges.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• In FY 2023, AMAFCA continued its policy of investigation of suspected significant/severe illicit discharges within 48 hours of detection and all other discharges as soon as practicable.</li> <li>• In addition, AMAFCA investigated and documented all jurisdictional illicit discharge complaints received through the 311 call in program, as well as other complaints received directly by AMAFCA staff through email, phone, or received through ABCWUA's monthly DMR Sanitary Sewer Overflow Report provided to AMAFCA. The 311 complaints that are not in AMAFCA's jurisdiction are directed to the jurisdictional agency.</li> <li>• AMAFCA continued to be involved in the MS4 TAG group, facilitating cooperation and coordination with other MS4s in the Middle Rio Grande.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
5.7	111	Review complaint records and develop a targeted source reduction program as required in <a href="#">Part I.D.5.e.(i)(g)</a> . Review complaint records for the last permit term and develop a targeted source reduction program for those illicit discharge/improper disposal incidents that have occurred more than twice in two (2) or more years from different locations.	<a href="#">Part I.D.5.e.(i)(g)</a> - AMAFCA will continue its policy of reviewing complaint records. In addition, complaint records that are determined to be illicit discharges will be added to the AMAFCA GIS database. The location, date, type of illicit discharge, and source (if known) will be documented. This database was developed in 2014 and is updated annually. To meet the Permit requirements in Table 1.a (Part I.C.2), regarding discharges to impaired waters with a TMDL (E. coli), AMAFCA's review of complaint records will include a focus on illicit discharges contributing bacteria to the MS4. AMAFCA will develop a targeted source reduction program for those illicit discharge/improper disposal incidents that have occurred more than twice in 2 or more years from different locations. AMAFCA coordinates with COA and the Albuquerque Bernalillo Water Utility Authority (ABCWUA) for notification of illicit discharges.	<ul style="list-style-type: none"> <li>• AMAFCA will continue its policy of reviewing complaint records. This will include a focus on illicit discharges contributing bacteria to the MS4.</li> <li>• Annually, AMAFCA will reevaluate its targeted source reduction program. Potential future targets will be determined and cooperative efforts for targeted source reduction programs with MRGSQT members will be considered.</li> <li>• AMAFCA will continue adding illicit discharge complaint records for the Permit term to the AMAFCA GIS database to help identify sources and trends.</li> <li>• AMAFCA will continue coordination with other agencies for this program element.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• In FY 2023, AMAFCA continued to keep a record of the MS4 311 call in program complaints and communicated with the appropriate agency regarding these notifications.</li> <li>• In FY 2023, AMAFCA continued to add the ABCWUA monthly DMR reports for SSOs to a maintained GIS database to help identify sources, trends, and issues. ABCWUA's CMOM Annual Report (which includes the Overflow Emergency Response Plan) is available upon request from the ABCWUA.</li> </ul>
Not Included in NOI	112	As required in <a href="#">Part I.D.5.e.(ii)</a> , the permittee shall address the following categories of non-stormwater discharges or flows (e.g., illicit discharges) only if they are identified as significant contributors of pollutants to the MS4: water line flushing, landscape irrigation, diverted stream flows, rising ground waters, uncontaminated ground water infiltration (as defined at 40 CFR 35.2005(90)), uncontaminated pumped ground water, discharges from potable water sources, foundation drains, air conditioning condensation, irrigation water, springs, water from crawl space pumps, footing drains, lawn watering, individual residential car washing, flows from riparian habitats and wetlands, dechlorinated swimming pool discharges, and street wash water. Note: Discharges or flows from fire fighting activities are excluded from the effective prohibitions against non-stormwater and need only be addressed where they are identified a significant sources of pollutants to water of the United States).	<a href="#">Part I.D.5.e.(ii)</a> - Any such discharge that is identified as a significant contributor of pollutants to the AMAFCA MS4, or is causing or contributing to a water quality standards violation, will be addressed as an illicit discharge pursuant to Part I.D.5.e of the MS4 Permit. The Permit lists authorized non-stormwater discharges in Part I.D.5.e.(ii). Many of these authorized non-stormwater discharges are not applicable to AMAFCA and none of these discharges are expected to be significant contributors of pollutants to the MS4. The AMAFCA Stormwater Quality Engineer will continue coordination & communication with ABCWUA regarding well flushing and rehabilitation schedules to ensure that AMAFCA is aware of authorized non-stormwater discharges into its facilities.	<ul style="list-style-type: none"> <li>• The AMAFCA Stormwater Quality Engineer will review this list annually to check that the categories of authorized non-stormwater discharges are still not considered significant contributors of pollutants to the MS4.</li> <li>• The AMAFCA Stormwater Quality Engineer will communicate with ABCWUA regarding well flushing and rehabilitation schedules to ensure that AMAFCA is aware of authorized non-stormwater discharges into its facilities.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• The AMAFCA Storm Water Quality Engineer reviewed this list as part of the Annual Report preparation to check that the categories of authorized non-stormwater discharges are still not considered significant contributors of pollutants to the MS4.</li> <li>• The AMAFCA Storm Water Quality Engineer continued coordination &amp; communication with ABCWUA regarding well, tank, and line flushing schedules to ensure that AMAFCA was aware of authorized non-stormwater discharges into its facilities.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
5.8	113	<p>As required in <a href="#">Part I.D.5.e.(iii)</a>, the permittee must screen the entire jurisdiction at least once every five (5) years and high priority areas at least once every year. High priority areas include any area where there is ongoing evidence of illicit discharges or dumping, or where there are citizen complaints on more than five (5) separate events within twelve (12) months. The permittee must:</p> <p>(a) Include in its SWMP document a description of the means, methods, quality assurance and controls protocols, and schedule for successfully implementing the required screening, field monitoring, laboratory analysis, investigations, and analysis evaluation of data collected.</p> <p>(b) Comply with the dry weather screening program established in Table 6 and the monitoring requirements specified in Part III.A.2.</p> <p>(c) If applicable, implement the priority ranking system developed in previous permit term.</p>	<p>AMAFCA will continue to make progress with its IDDE activities and program. Much of this effort may be in coordination with MS4 permittees COA, Bernalillo County, and NMDOT, as the AMAFCA facilities are stormwater collectors for the basins that are primarily controlled by other MS4 programs, rules, and regulations.</p> <p><a href="#">Part I.D.5.e.(ii).(a)</a> - IDDE screening methods and protocols for implementing the required screening, field monitoring, laboratory analysis, investigations, and analysis evaluation of data collected has been developed. AMAFCA has in place a well-defined and implemented routine inspection and O&amp;M program that includes both formal and informal inspections. These O&amp;M inspections are part of the IDDE screening program.</p> <p><a href="#">Part I.D.5.e.(ii).(b)</a> - AMAFCA screening procedures and protocols will comply with the dry weather screening program monitoring requirements specified in Part III.A.2 of the MS4 Permit. COA and AMAFCA have a cooperative dry weather screening program.</p> <p><a href="#">Part I.D.5.e.(ii).(c)</a> - For AMAFCA, facility screening is part of AMAFCA's routine O&amp;M activities. All areas are screened and there are no low priority areas.</p>	<ul style="list-style-type: none"> <li>• AMAFCA has developed screening procedures, protocols, and plan.</li> <li>• AMAFCA will continue routine inspections through its O&amp;M program, including both formal and informal inspections. These O&amp;M inspections are part of the IDDE screening program.</li> <li>• As a cooperative program, COA will continue to perform dry weather screening.</li> <li>• AMAFCA will continue membership and involvement in the cooperative MRGSQT and TAG, which will facilitate cooperation and coordination with other MS4s in the Middle Rio Grande related to screening for illicit discharges.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• AMAFCA continued utilizing established IDDE screening procedures, protocols, and plan.</li> <li>• In FY 2023, AMAFCA continued routine inspections through its O&amp;M program, including both formal and informal inspections. These O&amp;M inspections were part of the IDDE screening program.</li> <li>• As a cooperative program, COA continued to perform dry weather screening. Additional information for this is provided in the Dry Weather Screening section of the Annual Report.</li> <li>• AMAFCA continued its Levellogger monitoring program in FY 2023, which includes monthly dry weather screening of 14 channelized inlets to the NDC on AMAFCA ROW. Copies of the Levellogger reports are available upon request.</li> <li>• AMAFCA continued membership and involvement in the cooperative MRGSQT and TAG, both which facilitated cooperation and coordination with other MS4s in the Middle Rio Grande related to screening for illicit discharges.</li> </ul>
5.9	114	<p>Develop, update, and implement a Waste Collection Program as required in <a href="#">Part I.D.5.e.(iv)</a>.</p>	<p><a href="#">Part I.D.5.e.(iv)</a> - Activity removed from AMAFCA's SWMP. Public waste collection is the responsibility of the municipalities. AMAFCA does not have the jurisdictional authority to perform these activities. AMAFCA will continue to regularly collect waste within its rights-of-way. This was submitted to EPA in AMAFCA's NOI and accepted.</p>	N/A	N/A
5.10	115	<p>Develop, update and implement a Spill Prevention and Response program to prevent, contain, and respond to spills that may discharge into the MS4 as required in <a href="#">Part I.D.5.e.(v)</a>. The Spill Prevention and Response program shall include:</p> <p>(a) Where discharge of material resulting from a spill is necessary to prevent loss of life, personal injury, or severe property damage, the permittee(s) shall take, or ensure the party responsible for the spill takes, all reasonable steps to control or prevent any adverse effects to human health or the environment: and</p> <p>(b) The spill response program may include a combination of spill response actions by the permittee (and/or another public or private entity), and legal requirements for private entities within the permittee's municipal jurisdiction.</p>	<p><a href="#">Part I.D.5.e.(v)</a> - AMAFCA will continue its Spill Prevention and Response program. This program element relates to Illicit Discharge, reporting requirements, crew training, spill response materials on hand (in maintenance vehicles), and good housekeeping. For AMAFCA facilities, AMAFCA encourages that crew members are trained in spill prevention and control (refer to Pollution Prevention/Good Housekeeping Control Measure).</p>	<ul style="list-style-type: none"> <li>• AMAFCA will continue development of its cooperative Spill Response Program with agency partners.</li> <li>• AMAFCA encourages that crew members are trained in spill prevention and control (refer to Pollution Prevention/Good Housekeeping Control Measure).</li> <li>• AMAFCA will continue membership and involvement in the cooperative MS4 TAG and the MRGSQT, which will facilitate cooperation and coordination with other MS4s in the Middle Rio Grande related to spill prevention and response.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• AMAFCA continued to follow the Spill Prevention and Response Plan.</li> <li>• AMAFCA continued development of its cooperative Spill Prevention and Response Program with agency partners. As part of this cooperative, MS4s have established contracts with an environmental clean-up company to assist the Middle Rio Grande MS4s with IDDE response.</li> <li>• AMAFCA continued to be involved in the MS4 TAG group, facilitating cooperation and coordination with other MS4s in the Middle Rio Grande.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
Not Included in NOI	116	<p><u>Part 1.D.5.e.(vi)</u> - The permittee must include in the SWMP a description of the mechanism(s) utilized to comply with each of the elements required in Part 1.D.5.e.(i) throughout Part 1.D.5.e.(v) and its corresponding measurable goal.</p> <p>A description of the means, methods, quality assurance and controls protocols, and schedule for successfully implementing the required screening, field monitoring, laboratory analysis, investigations, and analysis evaluation of data collected; and</p> <p><u>Part 1.D.5.e.(vii)</u> - The permittee shall assess the overall success of the program, and document the program effectiveness in the Annual Report.</p>	<p><u>Part 1.D.5.e.(vi)</u> - AMAFCA's Stormwater Quality Engineer will review the program requirements listed for the above-mentioned program elements, during the Annual Report process. A review of the screening completed and the data collected, if any, will be available upon request and AMAFCA will incorporate documentation by reference into the Annual Report.</p> <p><u>Part 1.D.5.e.(vii)</u> - AMAFCA will document the program effectiveness and program success. AMAFCA will incorporate documentation by reference into the Annual Report.</p>	<ul style="list-style-type: none"> <li>As part of the Annual Report process each year, the Stormwater Quality Engineer will review the program requirements listed in Part 1.D.5.e, for the above-mentioned SWMP elements, and develop a strategy, if applicable, to implement any new program requirements.</li> <li>A review of the screening completed and the data collected, if any, will be available upon request and AMAFCA will incorporate documentation by reference into the Annual Report.</li> <li>AMAFCA will document the program effectiveness and program success. AMAFCA will incorporate documentation by reference into the Annual Report.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>AMAFCA's Program was reviewed by the Storm Water Quality Engineer for the reporting period as part of this Annual Report process.</li> <li>Screening documentation in the Levellogger monitoring reports is available upon request. The Levellogger locations focus on the NDC watershed, which is a water quality priority area for AMAFCA because of the larger residential, industrial, and commercial developments in this watershed.</li> <li>This Annual Report and associated Program Summaries document the program effectiveness and program success in the status of implementation and performance assessment for each MS4 Permit requirement.</li> </ul>
5.11	117	<p>Enhance the program to include requirements in <u>Part 1.D.5.e.(ix)</u>. The permittee may: (a) Divide the jurisdiction into assessment areas where monitoring at fewer locations still provides sufficient information; (b) Downgrade high priority areas after the area has been screened at least once and there are citizen complaints on no more than 5 separate events within a 12 month period; (c) Rely on a cooperative program with other MS4s for detection and elimination of illicit discharges and illegal dumping; (d) If cooperative program, required detection program frequencies may be based on the combined jurisdictional area rather than individual jurisdictional areas to reduce total number of screening locations; (e) After screening a non-high priority area once, adopt an "in response to complaints only" IDDE for that area (no more than 2 separate events within a 12 month period); (f) Enhance the program to utilize methodologies consistent with those described in "Illicit Discharge Detection and Elimination, A Guidance Manual for Program Development and Technical Assessments."</p>	<p><u>Part 1.D.5.e.(ix).(a)</u> - AMAFCA operates and maintains rainfall gauges for the NDC watershed to better understand runoff and evaluate monitoring locations. Future telemetry project will add screening capabilities for other outfalls.</p> <p><u>Part 1.D.5.e.(ix).(b)</u> - This enhancement may be considered and included in the future.</p> <p><u>Part 1.D.5.e.(ix).(c)</u> - AMAFCA currently coordinates with MS4s, as appropriate, and the ABCWUA for notification of illicit discharges. AMAFCA will continue to pursue developing similar cooperative coordination with other agencies.</p> <p><u>Part 1.D.5.e.(ix).(d) and (e)</u> - These cooperative elements may be considered in the future.</p> <p><u>Part 1.D.5.e.(ix).(f)</u> - AMAFCA had a consultant evaluate the AMAFCA IDDE program and develop recommendations for improving the program in order to comply with the MS4 Permit. The report included evaluating the procedures and methodologies described in "IDDE, A Guidance Manual for Program Development and Technical Assessments", for incorporation into AMAFCA's IDDE program. AMAFCA will continue to implement recommendations from this report, as appropriate.</p>	<ul style="list-style-type: none"> <li>AMAFCA will document progress made, if any, with these program enhancement activities.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>In FY 2023, AMAFCA continued monitoring water Levelloggers to better understand runoff and evaluate monitoring locations and needs. Monthly, throughout FY 2023, the Levelloggers were monitored in the field with accompanying photo documentation and this allowed for additional dry weather/IDDE screening.</li> <li>In FY 2023, AMAFCA worked with COA and ABCWUA for notification of illicit discharges. AMAFCA also cooperated with Bernalillo County and NMDOT related to IDDE in FY 2023.</li> </ul>
5.12	118	<p>Item from MS4 Permit NOI. Describe other proposed activities to address the Illicit Discharges and Improper Disposal Measure.</p>	<p>AMAFCA will continue to utilize the Annual Report process as a means to perform a self-audit with the goal to improve its MS4 Programs.</p>	<ul style="list-style-type: none"> <li>AMAFCA will annually document progress made, if any, related to the Annual Report and SWMP revision process as a means to perform a self-audit on the MS4 Program elements.</li> </ul>	<p><b>Met FY 2023 Goal.</b></p> <ul style="list-style-type: none"> <li>AMAFCA continued to utilize the Annual Report process as a means to perform a self-audit on the MS4 Program elements.</li> </ul>



NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
	119	<b>TABLE 7: Control of Floatables Discharges - Part I.D.5.f</b>			
6.1	120	As required in Part I.D.5.f.(i), the permittee must develop, update, and implement a program to address and control floatables in discharges into the MS4. The floatables control program shall include source controls and, where necessary, structural controls. Permittees previously covered under NMS000101 or NMR04A000 must continue existing programs while updating those programs, as necessary, to comply with the requirements of this permit. The permittee shall develop or update a schedule to implement as required in Part I.D.5.f.(i).(a). Note: AMAFCA and COA should update the schedule according to the findings of the 2005 AMAFCA/COA Floatable and Gross Pollutant Study and other studies.	Part I.D.5.f.(i) and (i).(a) - AMAFCA will continue to implement a program to address and control floatables in discharges into the MS4. AMAFCA will continue to install stormwater quality features to control floatables, such as ported risers, trash racks, and screened inlets in both new construction and retrofits where appropriate. AMAFCA will continue to coordinate with COA relative to structural BMPs within AMAFCA rights-of-way.	<ul style="list-style-type: none"> <li>The AMAFCA Stormwater Quality Engineer will continue to review, revise, and implement a program to address and control floatables in discharges into the MS4.</li> <li>AMAFCA will continue to cooperate and coordinate with COA relative to structural BMPs within AMAFCA rights-of-way.</li> <li>AMAFCA will continue membership and involvement in the cooperative MS4 Technical Advisory Group (MS4 TAG), which will facilitate cooperation and coordination with other MS4s in the Middle Rio Grande related control of floatables discharges.</li> <li>AMAFCA will continue utilizing the manual trash collection contracts.</li> <li>AMAFCA is pursuing developing a cooperative program for this program element.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>The AMAFCA Storm Water Quality Engineer continued to implement a program to address and control floatables in discharges into the MS4.</li> <li>AMAFCA continued to be involved in the MS4 TAG, facilitating cooperation and coordination with other MS4s in the Middle Rio Grande.</li> <li>AMAFCA continued utilizing the manual trash collection contracts in FY 2023.</li> <li>Photos of AMAFCA operations to remove floatables and sediment in FY 2023 are provided in the Pollution Prevention/ Good Housekeeping Program &amp; Control of Floatables Program Summary.</li> </ul>
6.2	121	Estimate the annual volume of floatables and trash removed from each control facility and characterize the floatable type as required in Part I.D.5.f.(i).(b).	Part I.D.5.f.(i).(b) - AMAFCA will continue to estimate the annual volume of floatables and trash removed from each control facility as well as to characterize the floatable type. The AMAFCA operations and maintenance crew and subcontractors track the volume of floatables, sediment, trash, and debris removed from AMAFCA facilities. This tracking procedure includes the location of removal by facility and watershed.	<ul style="list-style-type: none"> <li>AMAFCA will continue to estimate the annual volume of floatables and trash removed from each control facility and characterize the floatable type.</li> <li>AMAFCA will continue to utilize crew activity tracking, allowing AMAFCA to better and more easily determine the volume of floatables and sediment removed from each AMAFCA facility.</li> <li>AMAFCA has updated, cooperative waste characterization study in the watershed during the Permit term.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>In FY 2023, AMAFCA continued to implement its crew tracking system and database. A summary of trash, sediment, and vegetation removed within AMAFCA's jurisdiction is included in the relevant Program Summary.</li> </ul>
6.3	122	Item from MS4 Permit NOI. Describe other proposed activities to address the Control of Floatables Discharges Measure.	AMAFCA will continue to utilize the Annual Report and SWMP revision process as a means to perform a self-audit with the goal to improve its MS4 Programs.	AMAFCA will document progress made, if any, related to the Annual Report and SWMP revision process as a means to perform a self-audit on the MS4 Program elements.	<p><b>Met FY 2023 Goal.</b></p> <ul style="list-style-type: none"> <li>AMAFCA continued to utilize the Annual Report process as a means to perform a self-audit on the MS4 Program elements.</li> </ul>
Not Included in NOI	123	Update the SWMP document and Annual Report as required in Part I.D.5.f.(ii) and Part I.D.5.f.(iii). Part I.D.5.f.(ii) - The permittee must include in the SWMP a description of the mechanism(s) utilized to comply with each of the elements required in Part I.D.5.f.(i). Part I.D.5.f.(iii) - The permittee shall assess the overall success of the program, and document the program effectiveness in the Annual Report.	Part I.D.5.f.(ii) - AMAFCA's Stormwater Quality Engineer will review the program requirements listed for the above-mentioned program elements, during the Annual Report process. A strategy to implement any new program requirements or improve the compliance with program requirements will be developed as needed. Part I.D.5.f.(iii) - AMAFCA will document the program effectiveness and program success. AMAFCA will incorporate documentation by reference into the Annual Report.	<ul style="list-style-type: none"> <li>As part of the Annual Report process each year, the Stormwater Quality Engineer will review the program requirements listed in Part I.D.5.f, for the above-mentioned SWMP elements, and assess the overall success of the program. AMAFCA will document the program effectiveness and program success. AMAFCA will incorporate documentation by reference into the Annual Report.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>In FY 2023, as part of the Annual Report development, AMAFCA's Storm Water Quality Engineer reviewed the program requirements listed in Part I.D.5.f for this section.</li> <li>This Annual Report and associated Program Summaries document the program effectiveness and program success in the status of implementation and performance assessment for each MS4 Permit requirement. Additional documentation available upon request.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
	124	<b>TABLE 8: Public Education and Outreach on Stormwater Impacts - Part I.D.5.g</b>			
7.1	125	Develop, revise, implement, and maintain an education and outreach program as required in <a href="#">Part I.D.5.g.(i)</a> and <a href="#">Part I.D.5.g.(ii)</a> . This comprehensive stormwater program should educate the community, employees, businesses, and the general public of hazards associated with the illegal discharges and improper disposal of waste and about the impact that stormwater discharges on local waterways, as well as the steps that the public can take to reduce pollutants in stormwater.	<a href="#">Part I.D.5.g.(i)</a> - Through involvement in the MRGSQT and Bernalillo County, AMAFCA will continue to collaborate with the MS4 permittees to implement and improve upon the existing Public Education and Outreach program. The MRGSQT has a consulting firm under contract to act as Stormwater Coordinator and assist the team in providing public education and outreach on stormwater impacts. Included in the Stormwater Coordinator scope is to provide an Outcomes Report to the team members to summarize the yearly outreach activities through different media and methods, target audiences, and estimate of people reached. In addition to the cooperative elements with MRGSQT, AMAFCA will continue to conduct education and outreach presentations to the community specific to AMAFCA facilities and water quality.	<ul style="list-style-type: none"> <li>AMAFCA will continue to contribute to and participate in the MRGSQT.</li> <li>AMAFCA will continue to conduct education and outreach presentations to the community specific to AMAFCA facilities and water quality. AMAFCA's efforts will be included in the MRGSQT Outcomes Report. This report is available upon request and AMAFCA plans to share this document on its website.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>AMAFCA continued to contribute to and participate in the MRGSQT.</li> <li>AMAFCA's efforts are included in the MRGSQT Outcomes Report. This report is included as a Program Summary.</li> </ul>
Not Included in NOI	126	<a href="#">Part I.D.5.g.(ii)</a> , the permittee must implement a public education program to distribute educational knowledge to the community or conduct equivalent outreach activities about the impacts of storm water discharges on water bodies and the steps that the public can take to reduce pollutants in storm water runoff. The permittee must: <a href="#">Part I.D.5.g.(ii)(a)</a> , Define the goals and objectives of the program based on high priority community-wide issues; <a href="#">Part I.D.5.g.(ii)(b)</a> , Develop or utilize appropriate educational materials, such as printed materials, billboard and mass transit advertisements, signage at select locations, radio advertisements, television advertisements, and websites.	<p><a href="#">Part I.D.5.g.(ii)(a)</a> - The MRGSQT has developed a matrix to define the Public Education and Outreach objectives, priorities, and target audiences. The matrix will be reviewed and updated, as necessary, throughout the Permit term.</p> <p><a href="#">Part I.D.5.g.(ii)(b)</a> - The MRGSQT will continue to develop and utilize appropriate educational materials such as brochures, media campaigns, public presentations/events, giveaways, display booths/kiosks, signage at select locations, and postings on social media sites (Facebook) and websites. The types of materials utilized by the MRGSQT are summarized in the annual Outcomes Report.</p>	<ul style="list-style-type: none"> <li>AMAFCA, through its participation in the MRGSQT will review, throughout the Permit term, and update, as necessary, the program matrix to define the Public Education and Outreach and Public Involvement and Participation objectives, priorities, and target audiences.</li> <li>The MRGSQT will continue to develop and utilize appropriate educational materials such as brochures, media campaigns, public presentations/events, giveaways, display booths/kiosks, signage at select locations, and postings on social media sites (Facebook) and websites.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>The MRGSQT continued to use the matrix this year to guide the Public Education and Outreach and Public Involvement and Participation objectives, priorities, and target audiences.</li> <li>The types of materials utilized are summarized in the attached Program Summary MRGSQT Outcomes Report. The Facebook page and website (<a href="http://www.keeptheriogrande.org">www.keeptheriogrande.org</a>) remained active in FY 2023.</li> <li>MRGSQT continued to distribute BMP brochures in English and Spanish for specific industries (Contractors, Food Preparation or Service, Parking Lots and Drive Through Lanes, Fueling Stations, Vehicle and Equipment Repair, Carpet and Upholstery Cleaning, Scrap Metal Recycling, and Landscaping). These materials are available upon request.</li> </ul>
Not Included in NOI	127	<a href="#">Part I.D.5.g.(ii)(c)</a> , Inform individuals and households about ensuring proper septic system maintenance, ensuring the proper use and disposal of landscape and garden chemicals including fertilizers and pesticides, protecting and restoring riparian vegetation, and properly disposing of used motor oil or household hazardous wastes;	<a href="#">Part I.D.5.g.(ii)(c)</a> - The MRGSQT's program matrix and Public Education and Outreach programs include proper septic system maintenance, proper use and disposal of landscape and garden chemicals including fertilizers and pesticides, and properly disposing of household hazardous wastes.	<ul style="list-style-type: none"> <li>The MRGSQT will continue to include these specific educational areas in their program matrix and reporting on these areas in their annual Outcomes Report.</li> </ul>	<p><b>Met FY 2023 Goal.</b></p> <ul style="list-style-type: none"> <li>The MRGSQT Outcomes Report typically includes a table summarizing the MS4 Permit Public Education and Outreach Component/reference with the MRGSQT activities, as well as including the type of audiences reached. In addition, information on these topics is available on the MRGSQT website (<a href="http://www.keeptheriogrande.org">www.keeptheriogrande.org</a>).</li> <li>In FY 2023, the MRGSQT continued distribution of brochures targeting septic system education.</li> <li>AMAFCA and Bernalillo County continued to distribute BMPs brochures for specific industries. Landscaping was one industry area of focus.</li> <li>Both COA and Bernalillo County sponsor Household Hazardous Waste (HHW) collection events throughout the year.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
Not Included in NOI	128	<p><u>Part 1.D.5.g.(ii).(d).</u> Inform individuals and groups how to become involved in local stream and beach restoration activities as well as activities that are coordinated by youth service and conservation corps or other citizen groups.</p>	<p><u>Part 1.D.5.g.(ii).(d)</u> - The MRGSQT, which AMAFCA is a member, utilizes volunteers throughout communities within the watershed to assist with park, open space, trail, and river cleanup projects. Communication for Public Education and Outreach and Public Involvement and Participation is achieved by activities organized with youth service groups, conservation corps, and other citizen groups. In addition, AMAFCA will continue to foster Public Education and Outreach and Public Involvement and Participation programs, including Earth Force - Keep it Clean student outreach, Talking Talons Youth Leadership Activities, and Rocky Mountain Youth Corps programs.</p>	<ul style="list-style-type: none"> <li>The MRGSQT will continue communication for public involvement and participation activities as well as assist with communication for Public Education and Outreach and Public Involvement and Participation activities organized by youth service groups, conservation corps, and other citizen groups. These volunteer activities will be summarized in the annual MRGSQT Outcomes Report. The MRGSQT Outcomes Report is available upon request and AMAFCA plans to share this document on its website.</li> <li>Through the MRGSQT, two partner education programs, BEMP and , are supported. is an innovative, long-term outreach program that integrates water resource topics with computer technology, student writing, and a hands-on curriculum to meet specific, measurable outcomes. The main objective of the Stormwater Science outreach education program BEMP is to teach students that the health of the Rio Grande is directly related to the health of the surrounding watershed.</li> <li>AMAFCA will continue to foster Public Education and Outreach and Public Involvement and Participation programs, including Earth Force, Talking Talons Youth Leadership Activities, and Rocky Mountain Youth Corps programs.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>The MRGSQT Outcomes Report typically documents volunteer participation in park, open space, trail, and river cleanup projects. The Keep the Rio Grande website has been updated to better assist with implementation of this activity.</li> <li>Through the MRGSQT, three partner education and student involvement programs, Arroyo Classroom, BEMP, and RiverXchange, were supported in FY 2023.</li> </ul>
Not Included in NOI	129	<p><u>Part 1.D.5.g.(ii).(e).</u> Use tailored public education program, using a mix of locally appropriate strategies, to target specific audiences and communities. Examples of strategies include distributing brochures or fact sheets, sponsoring speaking engagements before community groups, providing public service announcements, implementing educational programs targeted at school age children, and conducting community-based projects such as storm drain stenciling, and watershed cleanups;</p>	<p><u>Part 1.D.5.g.(ii).(e)</u> - The MRGSQT will continue to organize comprehensive Public Education and Outreach programs with appropriate strategies to target specific audiences in the Middle Rio Grande community.</p>	<ul style="list-style-type: none"> <li>The MRGSQT will continue to include comprehensive education programs with appropriate strategies to target specific audiences in the Middle Rio Grande community. The target audiences for the educational programs will be identified in the Outcomes Report.</li> </ul>	<p><b>Met FY 2023 Goal.</b></p> <ul style="list-style-type: none"> <li>The MRGSQT Outcomes Report includes information on the comprehensive Public Education and Outreach programs, community events, presentations, and participation activities in FY 2023. The MRGSQT participated in a wide variety of community events. Through the MRGSQT, three partner education and student involvement programs, Arroyo Classroom, BEMP, and RiverXchange, were supported in FY 2023. The target audiences for these activities are typically identified in the Outcomes Report. The Keep the Rio Grande website has been updated to better assist with implementation of this activity.</li> </ul>
Not Included in NOI	130	<p><u>Part 1.D.5.g.(ii).(f).</u> Use materials or outreach programs directed toward targeted groups of commercial, industrial, and institutional entities likely to have significant stormwater impacts. For example, providing information to restaurants on the impact of grease clogging storm drains and to garages on the impact of oil discharges. The permittee may tailor the outreach program to address the viewpoints and concerns of all communities, particularly minority and disadvantaged communities, as well as any special concerns relating to children. The permittee must make information available for non-English speaking residents, where appropriate.</p>	<p><u>Part 1.D.5.g.(ii).(f)</u> - The MRGSQT will continue to include Public Education and Outreach programs directed toward commercial, industrial, engineering/contractors, and other institutional entities to meet the MS4 Permit requirements. Where outreach target groups include Spanish-speaking residents, MRGSQT may have Spanish-translations available of public meeting announcements and data sheets. The need for bi-lingual outreach will be assessed by the MRGSQT as needed.</p>	<ul style="list-style-type: none"> <li>The MRGSQT cooperative programs will continue to include information on Public Education and Outreach and Public Involvement and Participation programs directed toward commercial, industrial, engineering/contractors, and other institutional entities.</li> <li>Where outreach target groups include Spanish-speaking residents, MRGSQT may have Spanish-translations available of public meeting announcements and data sheets. The need for bi-lingual outreach will be assessed by the MRGSQT as needed.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>The MRGSQT Outcomes Report includes information on Public Education and Outreach and Public Involvement and Participation programs directed toward commercial, industrial, engineering/contractors, and other institutional entities.</li> <li>The MRGSQT continued to distribute BMP brochures in English and Spanish for specific industries (Contractors, Food Preparation or Service, Parking Lots and Drive Through Lanes, Fueling Stations, Vehicle and Equipment Repair, Carpet and Upholstery Cleaning, Scrap Metal Recycling, and Landscaping). These materials are available upon request.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
7.2	131	<p>Update the SWMP document and Annual Report as required in Part I.D.5.g.(iii) and Part I.D.5.g.(iv).</p> <p><u>Part I.D.5.g.(iii)</u>. The permittee must include the following information in the SWMP document:</p> <p>(a) A description of a program to promote, publicize, facilitate public reporting of the presence of illicit discharges or water quality associated with discharges from MS4s;</p> <p>(b) A description of the education activities, public information activities, and other appropriate activities to facilitate the proper management and disposal of used oil and toxic materials;</p> <p>(c) A description of the mechanism(s) utilized to comply with each of the elements required in Part I.D.5.g.(i) and Part I.D.5.g.(ii) and its corresponding measurable goal.</p> <p><u>Part I.D.5.g.(iv)</u>. The permittee must assess the overall success of the program, and document both direct and indirect measurements of program effectiveness in the Annual Report.</p>	<p><u>Part I.D.5.g.(iii)</u> - (a) MS4s that are members of the MRGSQT benefit from the Albuquerque 311 Citizen Contact Center. Reports for illicit discharge can be done by phone, on-line, e-mail, or through an app on cellular phones.</p> <p>(b) Educational and public outreach activities are primarily handled through the MRGSQT.</p> <p>(c) This SWMP, AMAFCA's Annual Reports, and the MRGSQT outreach coordinator contract all serve as mechanisms to comply with the elements in this section of the permit. Refer to the above SWMP program elements for additional information. AMAFCA's Stormwater Quality Engineer will review the program requirements listed for the above-mentioned program elements during the SWMP update and Annual Report process. A strategy to implement any new program requirements or improve compliance with the program requirements will be discussed with the MRGSQT and developed as needed.</p> <p><u>Part I.D.5.g.(iv)</u> - AMAFCA will document the program effectiveness and program success. AMAFCA will incorporate documentation by reference into the Annual Report.</p>	<ul style="list-style-type: none"> <li>The AMAFCA Stormwater Quality Engineer will review and include the program requirements listed in Part I.D.5.g during the SWMP update and Annual Report process.</li> <li>AMAFCA will document the program effectiveness and program success. AMAFCA will incorporate documentation by reference into the Annual Report.</li> <li>AMAFCA (both through the MRGSQT and individually) will use surveys to assist with determining the effectiveness of programs.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>The SWMP was reviewed during the FY 2023 Annual Report development.</li> <li>The MRGSQT website (<a href="http://www.keepertheriogrande.org">www.keepertheriogrande.org</a>) has links related reporting illicit discharge and the COA website promotes the 311 Citizen Contact Center.</li> <li>AMAFCA projects require SWPPP Management boards for all their construction projects to provide the public with contact information for reporting indicators of stormwater discharges.</li> <li>This Annual Report and the MRGSQT Outcomes Report document the program effectiveness and program success in the status of implementation and performance assessment for each MS4 Permit requirement in this section of the Permit.</li> <li>The MRGSQT utilized updated stormwater surveys to assess the effectiveness of the Public Education and Outreach and Public Involvement and Participation program elements. An example of the MRGSQT/AMAFCA survey, as well as survey results trendline data, are available upon request.</li> </ul>
7.2	132	<p>Enhance the program to include Program Flexibility Elements in Part I.D.5.g.(v) through Part I.D.5.g.(viii).</p> <p><u>Part I.D.5.g.(v)</u>. Where necessary to comply with the MS4 Permit, the permittee should develop a program or modify/revise an existing education and outreach program to:</p> <p>(a) Promote, publicize, and facilitate the use of GI/LID/Sustainability practices; and</p> <p>(b) Include an integrated public education program regarding litter reduction, reduction in pesticide/herbicide use, recycling, and disposal (including yard waste, hazardous waste materials, and used motor vehicle fluids), and GI/ LID/ Sustainable practices (as allowed by the NM OSE).</p>	<p><u>Part I.D.5.g.(v)(a) and (b)</u> - AMAFCA will continue to include in its (and in the cooperative MRGSQT) Public Education and Outreach program: GI/LID/sustainability practices, litter reduction, herbicide and pesticide proper use and reduction (AMAFCA does not apply fertilizers in its operations), recycling, proper disposal of hazardous waste, proper disposal motor vehicle fluids, and proper disposal of yard waste.</p>	<ul style="list-style-type: none"> <li>AMAFCA will document progress made with these program enhancement activities.</li> </ul>	<p><b>Met FY 2023 Goal.</b></p>
Not Included in NOI	133	<p>Enhance the program to include Program Flexibility Elements in Part I.D.5.g.(v) through Part I.D.5.g.(viii) [continued]</p> <p><u>Part I.D.5.g.(vi)</u>. The permittee may collaborate or partner with other MS4 operators to maximize the program and cost effectiveness of the required outreach.</p>	<p><u>Part I.D.5.g.(vi)</u> - The MRGSQT is a cooperative effort allowing watershed MS4 participants to maximize their education, outreach, participation, and involvement programs in a cost effective manner. Through involvement in the MRGSQT, AMAFCA will continue to collaborate with the MS4 permittees to implement and improve upon the existing Public Education and Outreach and Public Involvement and Participation programs.</p>	<ul style="list-style-type: none"> <li>AMAFCA will continue to contribute to and participate in the MRGSQT in order to maximize their Public Education and Outreach and Public Involvement and Participation programs in a cost effective manner.</li> </ul>	<p><b>Met FY 2023 Goal.</b></p> <ul style="list-style-type: none"> <li>AMAFCA continued to contribute to and participate in the MRGSQT.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
Not Included in NOI	134	Enhance the program to include Program Flexibility Elements in Part I.D.5.g.(v) through Part I.D.5.g.(viii). [continued]  Part I.D.5.g. (vii). The education and outreach program may use citizen hotlines as a low-cost strategy to engage the public in illicit discharge surveillance.	Part I.D.5.g.(vii) - MS4s that are members of the MRGSQT benefit from the Albuquerque 311 Citizen Contact Center. The 311 service is a single telephone number for all non-emergency inquiries and services. This program includes citizen calls regarding illicit discharges and notifies AMAFCA of such calls within its jurisdiction.	• MS4s that are members of the MRGSQT benefit from the Albuquerque 311 Citizen Contact Center. This is discussed in more detail in the Illicit Discharges and Improper Disposal Control Measure.	<b>Met FY 2023 Goal.</b> • AMAFCA continued to participate in the 311 citizen hotline as well as the Illegal Dumping Partnership, which has various jurisdictional reporting contacts. The MRGSQT website ( <a href="https://keeptheriogrand.org/resources/">https://keeptheriogrand.org/resources/</a> ) has additional information. This is discussed in more detail in the Illicit Discharges and Improper Disposal section of the Annual Report.
Not Included in NOI	135	Enhance the program to include Program Flexibility Elements in Part I.D.5.g.(v) through Part I.D.5.g.(viii). [continued]  Part I.D.5.g. (viii). The permittee may use stormwater educational materials provided by the State, Tribe, EPA, environmental groups, public interest or trade organ., or other MS4s. The permittee may also integrate the education and outreach program with existing education and outreach programs in the MRG area. Examples of existing programs include: Classroom education on stormwater that allows students to develop watershed map to help students visualize area impacted and develop pet specific education. As well as education and outreach programs for commercial activities, lawn and garden activities, sustainable practices, pet waste management, proper disposal of household waste, trash management, water conservation practices designed to reduce pollutants in stormwater for home residences. Existing programs should include regular employee trainings with industry groups and contribute and participate in Stormwater Quality Team.	Part I.D.5.g.(viii) - The MRGSQT may utilize educational materials provided by the State, Tribe, EPA, environmental groups, public interest or trade organizations, or other MS4s.	• The MRGSQT may utilize materials, as appropriate, provided by the State, Tribe, EPA, environmental groups, public interest or trade organizations, or other MS4s. The types of materials and program focus for the materials utilized will be summarized in the annual MRGSQT Outcomes Report. This report is available upon request.	<b>Met FY 2023 Goal.</b> • Educational materials are provided on the MRGSQT website ( <a href="https://keeptheriogrand.org">https://keeptheriogrand.org</a> ) and are typically summarized in the MRGSQT Outcomes Report.

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
<b>TABLE 9: Public Involvement and Participation - Part I.D.5.h</b>					
8.1	137	Develop (or update), implement, and maintain a public involvement and participation plan as required in <u>Part I.D.5.h.(ii)</u> . This plan should provide opportunities for participation in the review, modification and implementation of the SWMP; develop and implement a process by which public comments to the plan are received and reviewed by the person(s) responsible for the SWMP; and make the SWMP available to the public and to the operator of any MS4 or Tribal authority receiving discharges from the MS4.	<u>Part I.D.5.h.(ii)</u> - AMAFCA will continue its Public Involvement and Participation program to encourage public involvement in the review, modification and implementation of the AMAFCA SWMP.	<ul style="list-style-type: none"> <li>• AMAFCA will post the draft SWMP, any SWMP amendments or modifications, and draft Annual Reports to the <a href="http://www.amafca.org">www.amafca.org</a> website with an explanation of the public comment period and instructions on how to submit comments. The posted documents will provide explanations of substantial changes, if applicable.</li> <li>• At least 30-days prior to submission of each updated SWMP, AMAFCA will provide public notice and make a draft copy of the updated SWMP available for public review and comment.</li> <li>• At least 45-days prior to submission of each Annual Report, AMAFCA will provide public notice and make a draft copy of the Annual Report available for public review and comment, as required in Part III.B of the MS4 Permit.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• AMAFCA posted the availability of a draft Annual Report on the <a href="http://www.AMAFCA.org">www.AMAFCA.org</a> website with an explanation of the public comment period and instructions on how to submit comments.</li> <li>• AMAFCA met the Permit required 45-day notice period for the draft FY 2023 Annual Report.</li> </ul>
8.1	138	As required in <u>Part I.D.5.h.(iii)</u> , the Public Involvement and Participation Plan shall include a comprehensive planning process which involves public participation and where necessary intergovernmental coordination. The permittee must include the following elements in the plan: (a) A detailed description of the general plan for informing the public of involvement and participation opportunities, including types of activities; target audiences; how interested parties may access the SWMP; and how the public was involved in development of the SWMP; (b) The development and implementation of at least one (1) assessment of public behavioral change following a public education and/or participation event; (c) A process to solicit involvement by environmental groups, environmental justice communities, civic organizations or other neighborhoods /organizations interested in water quality-related issues; and (d) An evaluation of opportunities to utilize volunteers for stormwater pollution prevention activities and awareness throughout the area.	<p><u>Part I.D.5.h.(iii)</u> - As allowed in this Permit section's "Program Flexibility Elements", AMAFCA, through its involvement with the MRGSQT, has integrated this section of the Public Involvement and Participation program with the existing Public Education and Outreach programs in the Middle Rio Grande area.</p> <p>The program includes:                      (a) A general plan for public of involvement and participation opportunities, including types of activities; target audiences; how interested parties may access the SWMP; and how to encourage public involvement in development and updates of the SWMP;                      (b) The development and implementation of water quality surveys to assess public knowledge and behavioral change following a public education and/or participation event;                      (c) A process to solicit involvement in development and updates of the SWMP through following the 45-day Annual Report and 30-day SWMP public comment period; and                      (d) An evaluation of opportunities to utilize volunteers for stormwater pollution prevention activities, including maintaining Mutt Mitt stations.</p>	<ul style="list-style-type: none"> <li>• AMAFCA will contribute and participate in the MRGSQT, which participates in public events and solicits public participation and feedback by way of volunteer participation and water quality surveys. Both the BEMP and program include participation metrics. In addition, the MRGSQT has developed and will include surveys for public behavior changes and feedback at their events.</li> <li>• AMAFCA will continue to follow the 45-day Annual Report and 30-day SWMP public comment period during the term of this Permit.</li> <li>• AMAFCA will continue to provide Mutt Mitt stations and seek volunteers to maintain the stations. AMAFCA will continue tracking this activity and reviewing metrics during the term of this Permit.</li> </ul>	<p><b>Met FY 2023 Goal.</b></p> <ul style="list-style-type: none"> <li>• AMAFCA continued to contribute to and participate in the MRGSQT; the Outcomes Report is attached to this Annual Report. BEMP, River Xchange, and Arroyo Classroom programs continued in FY 2023.</li> <li>• AMAFCA met the Permit required notice period for the FY 2023 Annual Report documents public review.</li> <li>• When appropriate, AMAFCA held project specific project meetings to solicit involvement from organization interested in water quality related issues. In addition, AMAFCA participates in the Water Protection Advisory (WPAB) Board Public Involvement Committee (PIC) and presented to the Board in FY 2023.</li> <li>• AMAFCA continued its focus on reducing pet waste through providing Mutt Mitt Stations and bags, maintained by community volunteers. Summary information for the Mutt Mitt Stations Program is available upon request.</li> </ul>
8.2	139	Comply with State, Tribal, and local notice requirements when implementing a Public Involvement and Participation Program as required in <u>Part I.D.5.h.(iv)</u> . Reporting notification requirements also in <u>Part III.D.4</u> .	<u>Part I.D.5.h.(iv) &amp; Part III.D.4</u> - AMAFCA will provide digital copies of all MS4 compliance reporting documents to the NMED, Pueblos of Sandia and Isleta as required of the MS4 Permit. The SWMP and Annual Reports are also available on the <a href="http://www.amafca.org">www.amafca.org</a> website.	<ul style="list-style-type: none"> <li>• AMAFCA will provide digital copies of MS4 compliance reporting documents, as appropriate, to the NMED, Pueblos of Sandia and Isleta as required here and in Part III.D.4 of the MS4 Permit.</li> <li>• AMAFCA will continue to post the SWMP and Annual Reports on the <a href="http://www.amafca.org">www.amafca.org</a> website.</li> </ul>	<p><b>Met FY 2023 Goal.</b></p> <ul style="list-style-type: none"> <li>• AMAFCA provided copies of the FY 2023 Annual Report to the NMED, Pueblo of Sandia, and Pueblo of Isleta as required here and in Part III.D.4 of the MS4 Permit.</li> <li>• AMAFCA continued its process of posting the current SWMP and the most recent Annual Report on the <a href="http://www.keepertheriogrando.org">www.keepertheriogrando.org</a> and/or the <a href="http://www.amafca.org">www.amafca.org</a> websites.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
8.3	140	Include elements as required in <a href="#">Part I.D.5.h.(v)</a> . The public participation process must reach out to all economic and ethnic groups. Opportunities for members of the public to participate in program development and implementation include serving as citizen representatives on a local stormwater management panel, attending public hearings, working as citizen volunteers to educate other individuals about the program, assisting in program coordination with other preexisting programs, or participating in volunteer monitoring efforts.	<a href="#">Part I.D.5.h.(v)</a> - As allowed in this Permit section's "Program Flexibility Elements", AMAFCA, through its involvement with the MRGSQT cooperative programs, has integrated this section of the Public Involvement and Participation program with existing Public Education and Outreach programs in the Middle Rio Grande area. AMAFCA will continue to include stormwater quality information for the public at events, including public meetings. AMAFCA may have Spanish translations, as needed, of public meeting announcements and data sheets.	<ul style="list-style-type: none"> <li>• AMAFCA will continue to include (along with the cooperative MRGSQT programs) water quality information for the public at events, including public meetings. Where neighborhoods include Spanish-speaking residents, MRGSQT may have Spanish-translations available of public meeting announcements and data sheets. By attending a variety of events at widespread locations throughout the area and by using the leading area newspaper (Albuquerque Journal) to advertise events, the MRGSQT ensures that a wide-range of economic and ethnic groups are reached, as documented in the Outreach Report.</li> <li>• AMAFCA will use the Watershed Protection Advisory Board, Public Involvement Committee as a mechanism to reach out to the community for volunteers and to solicit input through public meetings and discussions.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• AMAFCA participated in the Watershed Protection Advisory Board (WPAB) Public Involvement Committee (PIC).</li> </ul>
8.4	141	Update the SWMP document and Annual Report as required in <a href="#">Part I.D.5.h.(vi)</a> , <a href="#">Part I.D.5.h.(vii)</a> , and <a href="#">Part I.D.5.h.(viii)</a> . The permittee must include in the SWMP a description of the mechanisms utilized to comply with each of the elements required in Parts I.D.5.h.(i) throughout part I.D.5.h.(iv) and its corresponding measurable goal. The permittee shall assess the overall success of the program, and document the program effectiveness in the Annual Report. The permittee must provide public accessibility of the SWMP and Annual Reports online via the Internet and during normal business hours at the MS4 operator's main office for public inspection and copying consistent with any applicable federal, state, tribal, or local open records requirements. Upon a showing of significant public interest, the MS4 operator is encouraged to hold a public meeting (or include in the agenda of in a regularly scheduled city council meeting, etc.) on the NOI, SWMP, and Annual Reports.	<p><a href="#">Part I.D.5.h.(vi)</a> - AMAFCA's Stormwater Quality Engineer will review the program requirements listed for the above-mentioned program elements during the SWMP update and Annual Report process. A strategy to implement any new program requirements or improve compliance with the program requirements will be discussed with the MRGSQT, if applicable, and developed as needed.</p> <p><a href="#">Part I.D.5.h.(vii)</a> - AMAFCA will document the program effectiveness and program success. AMAFCA will incorporate documentation by reference into the Annual Report.</p> <p><a href="#">Part I.D.5.h.(viii)</a> - AMAFCA will provide public accessibility of the SWMP and Annual Reports online via the Internet on the <a href="http://www.amafca.org">www.amafca.org</a> website.</p> <p>At least 30-days prior to submission of each updated SWMP, AMAFCA will provide public notice and make a draft copy of the updated SWMP available for public review and comment and at least 45-days prior to submission of each Annual Report, AMAFCA will provide public notice and make a draft copy of the Annual Report available for public review and comment, as required in Part III.B of the MS4 Permit.</p>	<ul style="list-style-type: none"> <li>• The AMAFCA Stormwater Quality Engineer will review and include the program requirements listed in Part I.D.5.g during the SWMP update and Annual Report process.</li> <li>• AMAFCA will document the program effectiveness and program success. AMAFCA will incorporate documentation by reference into the Annual Report.</li> <li>• AMAFCA will provide public accessibility of the current SWMP document and the most recent Annual Report online via the Internet on the <a href="http://www.amafca.org">www.amafca.org</a> website.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• AMAFCA continued to utilize the Annual Report process as a means to perform a self-audit on the MS4 Program elements.</li> <li>• This Annual Report and the MRGSQT Outcomes Report document the program effectiveness and program success in the status of implementation and performance assessment for each MS4 Permit requirement. The MRGSQT Outcomes Report document is an attached Program Summary.</li> <li>• AMAFCA continued to provide public accessibility of the current SWMP document and the most recent Annual Report online via the Internet (<a href="http://www.amafca.org">www.amafca.org</a> and/or <a href="http://www.keeptheriogrand.org">www.keeptheriogrand.org</a>) and during normal business hours at the AMAFCA office. AMAFCA is located at 2600 Prospect Avenue NE, Albuquerque, NM 87107. The phone number is 505-884-2215.</li> <li>• AMAFCA met the Permit required 45-day notice period for the FY 2023 Annual Report. Documentation for the public review notices are provided in this section of the Annual Report.</li> </ul>
8.5	142	Enhance the program to include requirements in <a href="#">Part I.D.5.h.(ix)</a> . The permittee may integrate the public involvement and participation program with existing education and outreach programs in the Middle Rio Grande area. Example of existing programs include: Adopt-A-Stream Programs; Attitude Surveys; Community Hotlines (e.g. establishment of a '311'-type number and system established to handle storm-water-related concerns, setting up a public tracking/reporting.	<a href="#">Part I.D.5.h.(ix)</a> - AMAFCA will continue to include in its (and in the cooperative MRGSQT programs) public involvement and participation programs: funds toward groups which include public participation, such as Boy or Girl Scouts of America, the Bosque Ecosystem Monitoring Program (BEMP), Earth Force - Keep it Clean student outreach, Talking Talons Youth Leadership Activities, and Youth Corps programs. MS4s that are members of the MRGSQT benefit from the Albuquerque 311 Citizen Contact Center.	<ul style="list-style-type: none"> <li>• AMAFCA will document progress made with these program enhancement activities. AMAFCA and the MRGSQT will continue to review, update, and enhance public involvement and participation programs. The MRGSQT Outcomes Report will provide the documentation for this Permit activity. This report is available upon request.</li> <li>• MS4s that are members of the MRGSQT benefit from the Albuquerque 311 Citizen Contact Center. This is discussed in more detail in the Illicit Discharges and Improper Disposal Control Measure.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>• The MRGSQT Outcomes Report summarizes the public involvement and participation programs and activities for FY 2023. This report is an attached Program Summary.</li> <li>• AMAFCA continued to participate in the 311 call in program. This is discussed in more detail in the Illicit Discharges and Improper Disposal Control Measure section.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
8.6	143	Item from MS4 Permit NOI. Describe other proposed activities to address the Public Involvement and Participation Measure.	AMAFCA will continue to utilize the Annual Report and SWMP revision process as a means to perform a self-audit with the goal to improve its MS4 Programs.	• AMAFCA will document progress made, if any, related to the Annual Report and SWMP revision process as a means to perform a self-audit on the MS4 Program elements.	<p><b>Met FY 2023 Goal.</b></p> <ul style="list-style-type: none"> <li>• AMAFCA continued to utilize the Annual Report process as a means to perform a self-audit on the MS4 Program elements.</li> </ul>



NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
	144	<b>Part III - Monitoring, Assessment and Reporting Requirements</b>			
	145	<b>TABLE 10: Wet Weather Monitoring Program - Part III.A.1</b>			
See NOI Sections Below	146	<p>According to the requirements in Part III.A.1., The permittee must develop, in consultation with NMED and EPA (and affected Tribes if monitoring locations would be located on Tribal lands), and implement a comprehensive monitoring and assessment program. The permittees shall conduct wet weather monitoring to gather information on the response of receiving waters to wet weather discharges from the MS4 during both wet season (July 1 through October 31) and dry season (November 1 through June 30).</p> <p>Wet Weather Monitoring shall be conducted at outfalls, internal sampling stations, and/or in-stream monitoring locations at each water of the US that runs in each entity or entities' jurisdiction(s).</p>	<p>Part III.A.1 - Wet weather screening is synonymous with compliance monitoring. In the MRG MS4 Permit area, stormwater runoff discharges to the Rio Grande at outfall locations via major drainage channels, storm drains, and pump stations. The Rio Grande, the only perennial river in the watershed, enters the MRG Watershed in one location (North of Albuquerque) and leaves the MRG Watershed south of Albuquerque. Details for this program are provided in the SWMP sections below.</p>	<p>The program details and measurable goals are described below. The Final Sampling Plan for Cooperative Compliance Monitoring (CMC) was submitted to EPA on May 5, 2016. The sampling plan was accepted by the EPA and NMED.</p> <p>The current 2014 Middle Rio Grande Watershed Based Municipal Separate Storm Sewer System (MS4) Permit, NPDES Permit No. NMR04A000, expired on December 19, 2019. The MRG Watershed Based MS4 Permit entered into administrative continuance in Dec. 2019 when EPA Region 6 did not issue a new MS4 Permit before the current MS4 Permit expirations date. The MS4 TAG sent EPA an Administrative Continuance letter dated October 15, 2019. Until a new MS4 Permit is issued, there are no wet and dry weather monitoring requirements in the Rio Grande. However, during administrative continuance, the CMC members will evaluate and may choose to continue sampling to support their MS4 program needs, demonstrate program progress, or gather additional data in support of the future Permit compliance.</p>	<p>See specific Permit activity below.</p>
IV	147	<p><b>Part III.A.3.1.b. Option B: Cooperative Monitoring Program</b></p> <p>Develop a cooperative wet weather monitoring program with other permittees in the Middle Rio Grande Watershed. The program will monitor waters coming into the watershed (upstream) and leaving the watershed (downstream). The program must include sampling for TSS, TDS, COD, BOD5, DO, oil and grease, E. coli, pH, total kjeldahl nitrogen, nitrate plus nitrite, dissolved phosphorus, total ammonia plus organic nitrogen, total phosphorus, PCBs and Gross alpha. Monitoring of temperature shall be also conducted at outfalls and/or Rio Grande monitoring locations. Permittees must include additional parameters from monitoring conducted under permits NMS000101, NMR04A000 or/and NMR040001 whose mean values are at or above a WQS. The monitoring program must sample the pollutants for a minimum of 7 storm events per location during the permit term with at least 3 events in the wet season and 2 events in the dry season.</p>	<p>Part III.A.3.1.b. Option B: Cooperative Monitoring Program -The cooperative wet weather compliance monitoring will monitor waters coming into the watershed (upstream) and leaving the watershed (downstream) for a minimum of 7 storm events per location during the Permit term with at least 3 in the events in the wet season and 2 events in the dry season. The wet season is defined in the permit as July 1 through October 31 and the dry season as November 1 through June 30.</p> <p>AMAFCA joined the Compliance Monitoring Cooperative (CMC) group, which includes 12 watershed partners. The participatory permittees have developed a cooperative wet weather compliance monitoring program to assess the effect of stormwater discharges on the receiving water, the Middle Rio Grande. This monitoring plan was reviewed and discussed with NMED and EPA during its development. The cooperative sampling plan was accepted by EPA and permittees submitted the sampling plan on May 5, 2016 and sampling certification to EPA on June 28, 2016. At the end of FY 2019, all Permit required samples have been obtained by the CMC.</p>	<ul style="list-style-type: none"> <li>If the CMC does continue wet weather compliance monitoring during administrative continuance of this Permit, the monitoring program will follow the Permit requirements for parameters tested (TSS, TDS, COD, BOD5, DO, oil and grease, E. coli, pH, total kjeldahl nitrogen, nitrate plus nitrite, dissolved phosphorus, total ammonia plus organic nitrogen, total phosphorus, PCBs, Gross alpha, and temperature). In addition, parameters from stormwater monitoring conducted under Permit NMS000101, whose mean values were at or above a WQS, will also be tested. The complete list of parameters is listed in the CMC sampling plan. In addition, DO, pH, conductivity, and temperature will be analyzed in the field within 15 minutes of sample collection.</li> <li>If the CMC does continue wet weather compliance monitoring during administrative continuance of this Permit, the parameter list may be modified based on a review of the results obtained within the watershed and the program assessment needs for the permittees. AMAFCA will document, as applicable, any wet weather monitoring activity. AMAFCA will incorporate documentation by reference into the Annual Report and plans to document progress on the AMAFCA website.</li> <li>If the CMC does continue wet weather compliance monitoring during administrative continuance of this Permit, the monitoring program will be conducted according to the approved Sampling Plan for Compliance</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>The required CMC sampling for the MS4 Permit term in the Rio Grande (2016 to 2019) was completed in FY 2019. The MRG Watershed Based MS4 Permit entered into administrative continuance in Dec. 2019 when EPA Region 6 did not issue a new MS4 Permit before the current MS4 Permit expired. The MS4 TAG sent EPA an Administrative Continuance letter dated October 15, 2019, acknowledging that until a new MS4 Permit is issued, there are no compliance monitoring requirements in the Rio Grande. Although compliance sampling is currently not required, the CMC has opted to continue collecting samples while the permit is in administrative continuance. One (1) CMC monitoring and sampling event was conducted in FY 2023. The CMC sampled a wet season storm event on October 5-6, 2022.</li> <li>The CMC continued to maintain a database of the analysis results from the collected samples for the approved parameters. This database is available upon request. The E. coli loading and load allocation calculations related to the CMC monitoring program are available upon request for the cooperative sampling completed in FY 2016 – FY 2023.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
IV	148	As required in <a href="#">Part III.A.1.e.</a> and <a href="#">Table 10</a> , the permittees shall submit wet weather monitoring preference Option A or Option B to EPA (i.e., individual monitoring program vs. cooperative monitoring program) with NOI submittals.	<a href="#">Part III.A.1.e, Table 10</a> - AMAFCA submitted its NOI in compliance with the permit requirements and schedule. AMAFCA will participate in Option B - cooperative monitoring program.	<ul style="list-style-type: none"> <li>This Permit activity is complete.</li> </ul>	Permit Activity is Complete.
Not Included in NOI	149	<a href="#">Part III.A.1.e, Table 10</a> - Submit a detailed description of the monitoring scheme to EPA and NMED for approval. The monitoring scheme should include: a list of pollutants; a description of monitoring sites with an explanation of why those sites were selected; and a detailed map of all proposed monitoring sites. In addition, as required in <a href="#">Part III.A.1.h</a> , the monitoring program must include a contingency plan for collecting additional monitoring data within the MS4 or at additional appropriate instream locations should monitoring results indicate that MS4 discharges may be contributing to instream exceedances of WQS. The purpose of this additional monitoring effort would be to identify sources of elevated pollutant loadings so they could be addressed by the SWMP.	<a href="#">Part III.A.1.e, Table 10</a> - AMAFCA joined the Compliance Monitoring Cooperative (CMC) group, which includes 12 watershed partners. The participatory permittees have developed a wet weather cooperative monitoring program to assess the effect of stormwater discharges on the receiving water, the Middle Rio Grande. This monitoring plan was reviewed and discussed with NMED and EPA during its development. Multiple drafts were submitted to EPA and NMED by the CMC, including drafts on Sept. 16, 2015 and Dec. 21, 2015. The cooperative monitoring plan was accepted by EPA and permittees submitted the sampling plan on May 5, 2016 and sampling certification to EPA on June 28, 2016. Modifications to this sampling may be submitted to the EPA in the future, as needed for approval.	<ul style="list-style-type: none"> <li>This Permit activity is complete.</li> <li>The CMC members have met all requirements for wet weather compliance monitoring. If the CMC does continue wet weather monitoring during administrative continuance of this Permit, the monitoring program will be conducted according to the EPA/NMED approved monitoring plan.</li> </ul>	Permit Activity is Complete.
Not Included in NOI	150	<a href="#">Part III.A.1.e, Table 10</a> - Submit certification that all wet weather monitoring sites are operational and begin sampling.	<a href="#">Part III.A.1.e, Table 10</a> - AMAFCA submitted its sampling certification to EPA on June 28, 2016.	<ul style="list-style-type: none"> <li>This Permit activity is complete.</li> <li>AMAFCA, with its cooperative partners, has submitted certifications to the EPA that all wet weather compliance monitoring sites are operational and the CMC has begun sampling, according to the Permit requirements.</li> </ul>	Permit Activity is Complete.
Not Included in NOI	151	As required in <a href="#">Part III.A.1.e</a> , update SWMP document and submit Annual Reports. The results of the Wet Weather Monitoring must be provided in each Annual Report.  As required in <a href="#">Part III.D.1</a> -Monitoring results obtained during the reporting period running from July 1st to June 30th shall be submitted on discharge monitoring report (DMR) forms along with the Annual Report required by <a href="#">Part III.B</a> . A separate DMR form is required for each monitoring period (season) specified in <a href="#">Part III.A.1</a> . If any individual analytical test result is less than the minimum quantification level (MQL) listed for that parameter, then a value of zero (0) may be used for that test result for the DMR calculations and reporting requirements. The Annual Report shall include the actual value obtained, if test result is less than the MQL.	<a href="#">Part III.A.1.e, Table 10</a> - AMAFCA's Stormwater Quality Engineer will review the program requirement for the above-mentioned program elements, during the Annual Report process. A strategy to implement any new program requirements or improve compliance with the program requirements will be developed as needed.  <a href="#">Part III.D.1</a> - The wet weather compliance monitoring results obtained by the CMC from July 1st to June 30th will be submitted as required by the EPA using the NetDMR online website or as otherwise approved by EPA as part of the cooperative sampling program. EPA has required that the NetDMR online system be used to submit DMR results. Since this Permit will be in administrative continuance, and all required compliance monitoring results have been obtained, AMAFCA anticipates additional coordination with EPA relative to future samples uploaded to the NetDMR system.  AMAFCA will continue internal watershed stormwater quality monitoring, which typically collects samples from various locations. Collection of these samples are weather and equipment dependent. Monitoring results obtained from any continued CMC stormwater quality monitoring are available upon request.	<ul style="list-style-type: none"> <li>As part of the Annual Report process each year, the Stormwater Quality Engineer will review the program requirements listed in <a href="#">Part III.A.1</a>, for the above-mentioned SWMP elements, and assess the overall success of the program. AMAFCA will document the program effectiveness and program success. AMAFCA will incorporate documentation by reference into the Annual Report.</li> <li>The CMC members have met all requirements for wet weather compliance monitoring. If the CMC does continue wet weather monitoring during administrative continuance of this Permit, the wet weather compliance monitoring results obtained from July 1st to June 30th will be submitted as required by the EPA using the NetDMR online website or as otherwise approved by EPA as part of the cooperative sampling program. Since this Permit is in administrative continuance, and all required compliance monitoring results have been obtained, AMAFCA anticipates additional coordination with EPA relative to future samples uploaded to the NetDMR system.</li> <li>Monitoring results obtained from any continued CMC stormwater quality monitoring are available upon request.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>Refer to ID # 30 above for monitoring program updates for FY 2023.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
	152	<b>Dry Weather Discharge Screening of MS4 - Part III.A.2</b>			
Not Included in NOI	153	<p>According to the requirements in <a href="#">Part III.A.2</a>, Each permittee shall identify, investigate, and address areas within its jurisdiction that may be contributing excessive levels of pollutants to the Municipal Separate Storm Sewer System as a result of dry weather discharges (i.e., discharges from separate storm sewers that occur without the direct influence of runoff from storm events, e.g. illicit discharges, allowable non-stormwater, groundwater infiltration, etc.). Due to the arid and semi-arid conditions of the area, the dry weather discharges screening program may be carried out during both wet season (July 1 through October 31) and dry season (November 1 through June 30). Results of the assessment shall be provided in each Annual Report.</p>	<p><a href="#">Part III.A.2</a> - The program details and measurable goals are described below, in the Pollution Prevention/Good Housekeeping Control Measure, and in the Illicit Discharge and Improper Disposal Control Measure.</p> <p>There are no perennial streams in the Albuquerque area that contribute to the Rio Grande. As such, the dry weather screening program serves a dual purpose as an illicit discharge screening analysis.</p>	<p>The program details and measurable goals are described below, in the Pollution Prevention/Good Housekeeping Control Measure, and in the Illicit Discharge and Improper Disposal Control Measure.</p>	<p><b>Met FY 2023 Goal.</b></p> <ul style="list-style-type: none"> <li>The program details and measurable goals are described below, in the Pollution Prevention/Good Housekeeping Control Measure, and in the Illicit Discharge and Improper Disposal Control Measure.</li> </ul>
Not Included in NOI	154	<p><a href="#">Part III.A.2</a> -This program may be coordinated with the illicit discharge detection and elimination program required in Part I.D.5.e. The dry weather screening program shall be described in the SWMP and comply with the schedules contained in Part I.D.5.e.(iii). The permittee shall:</p> <p>a) Include sufficient screening points to adequately assess pollutant levels from all areas of the MS4.</p> <p>b) Screen for, at a minimum, BOD5, sediment or a parameter addressing sediment (e.g., TSS or turbidity), E. coli, Oil and Grease, nutrients, any pollutant that has been identified as cause of impairment of a waterbody receiving discharges from that portion of the MS4, including temperature.</p> <p>c) Specify the sampling and non-sampling techniques to be issued for initial screening and follow-up purposes.</p> <p>d) Perform monitoring only when an antecedent dry period of at least 72 hours after a rain event greater than 0.1 inch in magnitude is satisfied. Monitoring methodology shall consist of collecting a minimum of 4 grab samples spaced at a minimum interval of 15 minutes each.</p>	<p><a href="#">Part III.A.2</a> - AMAFCA will continue with the existing, cooperative Dry Weather Screening program in place under MS4 Permit NMS000101. The existing Dry Weather Screening program cooperative program with COA includes screening various locations, which screen 100% of COA/AMAFCA jurisdiction and targets industrial areas. Should any discharge be present in a quantity sufficient for analysis, it will be screened for BOD5, sediment (e.g., TSS or turbidity), E. coli, oil and grease, and nutrients. Any discharge collected will be a grab sample according to the Permit monitoring methodology.</p> <p>In addition, AMAFCA has in place a well-defined and implemented routine inspection and O&amp;M program that includes both formal and informal inspections and maintenance schedules for its watershed protection elements.</p> <p>AMAFCA will continue membership and involvement in the cooperative MS4 Technical Advisory Group (MS4 TAG), which will facilitate cooperation and coordination with other MS4s in the Middle Rio Grande related to screening for illicit discharges.</p>	<ul style="list-style-type: none"> <li>Under MS4 Permit NMR04A000, COA has taken the lead on this program and is responsible for the dry weather screening and documentation for this existing program. Screening results collected by the COA can be provided upon request.</li> <li>AMAFCA will continue to perform inspections according to the applicable O&amp;M Manuals and Plans. These inspections also function as dry weather inspections.</li> <li>AMAFCA will continue membership and involvement in the cooperative MS4 Technical Advisory Group (MS4 TAG) which will facilitate cooperation and coordination with other MS4s in the Middle Rio Grande related to screening for illicit discharges.</li> </ul>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>In cooperation with the COA, the Dry Weather Screening for 40 locations throughout the Middle Rio Grande Watershed, including the AMAFCA MS4, was completed and shared with AMAFCA by COA. The screening followed the requirements in (a) through (d) for this Permit element. The screening report is included as a Program Summary for the Annual Report.</li> <li>In FY 2023, AMAFCA continued to implement routine inspections and maintenance that included both formal and informal inspections and maintenance schedules for its watershed protection elements. These inspections also functioned as dry weather inspections. Refer to the Pollution Prevention/Good Housekeeping Control Measure for additional information. In FY 2023, AMAFCA continued to perform inspections according to the applicable Manuals and Plans.</li> <li>AMAFCA continued dry weather/illicit discharge inspections with its Levelogger monitoring. Fourteen (14) sites on AMAFCA ROW were inspected monthly and inspections (with photos) documented in the monitoring reports. Refer to the Illicit Discharges and Improper Disposal Program Summary for additional information.</li> <li>AMAFCA continued to be involved in the MS4 TAG group in FY 2023.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
	155	<b>Floatables Monitoring - Part III.A.3</b>			
Not Included in NOI	156	<p>According to the requirements in Part III.A.3., The permittees shall establish locations for monitoring/assessing floatable material in discharges to and/or from their MS4. A cooperative monitoring program may be established in partnership with other MS4s to monitor and assess floatable material in discharges to and/or from a joint jurisdictional area or watershed basis.</p> <p>Floatable material shall be monitored at least twice per year at priority locations and at minimum of two (2) stations. The amount of collected material shall be estimated in cubic yards.</p> <p>a) One (1) station should be located in the North Diversion (only applicable to COA and AMAFCA).</p>	<p>Part III.A.3 - AMAFCA will continue to monitor floatable material and the amount collected in participation with other MS4s. AMAFCA will monitor floatable material in the settling area of the NDC and at the I-25/SDC Baffle Chute Stormwater Quality Facility. Note the NDC settling area is within the AMAFCA easement on Sandia Pueblo property, but that is where AMAFCA has monitored floatables for many years. The requirements in this Permit section will be completed in conjunction with the requirements in TABLE 7: Control of Floatables Discharges - Part I.D.5.f. AMAFCA monitors and tracks collection of floatables at all AMAFCA facilities.</p>	<p>AMAFCA will continue to monitor floatable material and estimate the amount collected at least twice per year at a minimum of 2 stations.</p> <p>AMAFCA will maintain its 5 drying stations, locations where floatable material, sediment and debris is hauled, separated, and properly disposed of. These stations help AMAFCA meet the requirements for this activity.</p>	<p><b>Met FY 2023 Goals.</b></p> <ul style="list-style-type: none"> <li>AMAFCA continued to monitor floatables and the amount collected in the settling area of the NDC and at the I-25/SDC Baffle Chute Stormwater Quality Facility. In addition to these two locations, AMAFCA continued the task of determining the amount of floatables collected from each of the AMAFCA water quality facilities. In FY 2023, AMAFCA continued to use its crew tracking system and database created internally, specifically to meet the MS4 Permit needs. AMAFCA has estimated quantities for the volume of trash, sediment, and vegetation removed from its water quality facilities in FY 2023. Refer to the Annual Report Program Summary for additional information related to control of floatables.</li> </ul>

NOI Section	ID	Permit Activity Description	Plan SWMP Rev. 7 - July 1, 2024	Measurable Goal SWMP Rev. 7 - July 1, 2024	Status of Implementation and Performance Assessment Permit Year July 2023 to June 2023 (FY 2023)
	157	<b>Industrial and High Risk Runoff Monitoring - Part III.A.4</b>			
4	158	The permittees shall monitor stormwater discharges from Type 1 and 2 industrial facilities which discharge to the MS4 provided such facilities are located in their jurisdiction. (Note: if no such facilities are in the permittee's jurisdiction, the permittee must certify that this program element does not apply).	Activity removed from AMAFCA's SWMP (Rev. 0, December 1, 2015). AMAFCA certifies with submittal of this SWMP that no such industrial activities are located in AMAFCA's jurisdiction and this program element does not apply. This was submitted to EPA in AMAFCA's NOI and accepted.	N/A	N/A